

# **REPORT ON SITE SERVICES STUDY**

For

**TORONTO ZOO**

Prepared for:

**Mr. Eric Morris (Manager)  
Toronto Zoo  
Facilities and Services  
361 A Old Finch Avenue  
Scarborough, Ontario  
M1B 5W6**

Prepared by:

**PARADIGM ENGINEERING GROUP INC.  
Project No: 850**

September , 1999



## EXECUTIVE SUMMARY

Paradigm Engineering Group Inc. reviewed five systems, which service the site. These are the water, gas, sewer, electrical and communication systems. An overview of each system is found in Section 2 of the Report. This summary is broken down into three components as follows: Terms of Reference, Study Findings and Summary Report.

### A. Terms of Reference

Subsequent to a proposal dated November 16, 1998, Paradigm Engineering Group Inc. was retained to conduct a Condition Survey of the Toronto Zoo site services located on the Zoo property in Scarborough, Ontario. Authorization to proceed was notified by Mr. Eric Morris, Manager of Facilities and Services on behalf of the Toronto Zoo.

### B. Study Findings

Water: The physical condition of the water supply and distribution system was found to be generally in good condition. For the most part, the flow rates and water pressures were found to be adequate with the exception of approximately three hydrants where water pressures were found to be low. The findings also revealed that adequate water is available to service the current needs of the Zoo. Any proposed addition or expansion to the Zoo requiring water supply must address the above low-pressure problem.

There are two key areas of concern with the water supply system namely;

1. The entire site is currently supplied from a single line connected to the City. Should a major line break requiring the shut down of the water system occur on a day when the Zoo is very busy with visitors needing access to water, there will be a significant negative consequence, hence we have recommended that consideration be given to the installation of a second linefeed to the Zoo from another City main. For the short term, the sections of water mains that have leaked in the past should be replaced. The cost of this immediate repair is shown in the Appendices.
2. The existing water mains hydrant connections contain some dead ends without a loop. The above feature is not in conformance with the requirements of the City of Scarborough, which required that all lines leading to the fire hydrant be looped.

The long term solution to the first problem is to install a second line fee at an approximate budget cost of \$1,000,000. The solution to the second concern is to install loops at all hydrants without loops. Detailed discussion of these concerns and their corrective measures are given in the Appendices.

Gas: The physical condition of the Gas supply and distribution system was found to be generally in good condition. For the most part, the gas flow rates and pressures were found to be adequate. The findings also revealed that adequate gas is available to service the current needs. The adequacy of proposed expansions, including extension of gas facilities to the Eurasia exhibits area will be determined after design loads are known.

Sewers: The audit of the sewer system revealed that the sewer system has adequate capacity to service current needs and proposed expansions, however the entire storm and sanitary sewers contains a significant level of debris. We have recommended a complete flushing of the system to enhance its functional capacity.

Electrical: The audit of the electrical system indicates that there is adequate electrical capacity to service current needs, but any further expansion or addition to electrical energy loads must contemplate and include upgrading the electrical service. The electrical systems and equipment are in fair condition, despite the high incidence of failures. Given the age of the system and the reported frequency of disruption of operation resulting from power failures, we will recommend a phased replacement of all underground cables and submersible transformers.

Communication: The audit of the communication system indicates that there is adequate capacity to service current needs and proposed expansions. The communication equipment and systems are in good condition.

**C. Summary Cost Report**

The attached Portfolio Summary Report details the projected cost requirements for Capital Improvements, Required Repairs and Preventive Maintenance.

## **TABLE OF CONTENTS**

### **1.0 INTRODUCTION**

- 1.1 Terms of Reference
- 1.2 Scope of Work
- 1.3 Study Goals
- 1.4 Study Methodology
- 1.5 Description of the Complex
- 1.6 Acknowledgments
- 1.7 Life Cycle Costing Assumptions

### **2.0 REPORT FINDINGS**

- 2.1 *Water System*
  - 2.1.1 General Description of the System
  - 2.1.2 Audit Procedure
  - 2.1.3 Audit Findings
  - 2.1.4 Comment on Existing Usage/Reserve Capacity and Future Requirements
- 2.2 *Gas System*
  - 2.2.1 General Description of the System
  - 2.2.2 Audit Procedure
  - 2.2.3 Audit Findings
  - 2.2.4 Comment on Existing Usage/Reserve Capacity and Future Requirements
- 2.3 *Sewer System*
  - 2.3.1 General Description of the System
  - 2.3.2 Audit Procedure
  - 2.3.3 Audit Findings
  - 2.3.4 Comment on Existing Usage/Reserve Capacity and Future Requirements
- 2.4 *Electrical System*
  - 2.4.1 General Description of the System
  - 2.4.2 Audit Procedure
  - 2.4.3 Audit Findings
  - 2.4.4 Comment on Existing Usage/Reserve Capacity and Future Requirements
- 2.5 *Communications/Data System*
  - 2.5.1 *General* Description of the System
  - 2.5.2 Audit Procedure
  - 2.5.3 Audit Findings
  - 2.5.4 Comment on Existing Usage/Reserve Capacity and Future Requirements

<i>APPENDIX</i>	DESCRIPTION
<i>Appendix 1</i>	Potfolio Summary Report
<i>Appendix 2</i>	Detailed Cost Reports (Required Repairs, Preventative maintenance, Capital Improvement)
<i>Appendix 3</i>	Recommendation Report (Required Repairs, Preventative maintenance, Capital Improvement)
<i>Appendix 4</i>	1997 Energy Report
<i>Appendix 5</i>	GT Wood – High Voltage Maintenance Report, dated 1995.
<i>Appendix 6</i>	List of Gas-Fired Equipment
<i>Appendix 7</i>	Fire Hydrant Test Results
<i>Appendix 8</i>	Gas Test Results
<i>Appendix 9</i>	Water Test Results
<i>Appendix 10</i>	Sanitary Sewer Test Results (Print)
<i>Appendix 11</i>	Sanitary Sewer Test Results (Video)
<i>Appendix 12</i>	Storm Sewer Test Results (Print)
<i>Appendix 13</i>	Storm Sewer Test Results (Video)
<i>Appendix 14</i>	Component Quantity Take-offs
<i>Appendix 15</i>	City of Scarborough Fire Protection Water Services Policy
<i>Appendix 16</i>	Coorespondence from Enbridge Consumers Gas
<i>Appendix 17</i>	Correspondence from Graig Rose of Marshall Macklin Monaghan Consulting Engineers
<i>Appendix 18</i>	Fire Protection Water Supply Guideline for Part 3 in the Ontario Building Code
<i>Appendix 19</i>	Black & McDonald -- High Voltage Maintenance Reports dated August 1999, Reference No. 6621
<i>Appendix 20</i>	Black & McDonald – Submersible Transformer Failure/Replacement Report dated August 1999, Reference No.6638

## **1.0 INTRODUCTION**

### **1.1 Terms of Reference**

Subsequent to a proposal dated November 16, 1998, Paradigm Engineering Group Inc. was retained to conduct a Condition Survey of the Toronto Zoo site services located on the Zoo property in Scarborough, Ontario. Authorization to proceed was notified by Mr. Eric Morris, Manager of Facilities and Services on behalf of the Toronto Zoo.

### **1.2 Scope of Work**

In general, the scope of work consists of a Condition Survey of the water, gas, electrical and communication/data services and storm/sanitary sewer systems on the site to determine if any deficiencies exist. The study was broken down into 2 phases:

Phase I	Facility Audit
Phase II	Development of Life Cycle Repair/Replacement and Maintenance Program

Details of the complete scope of work are contained in the Request for Proposal Document and the Proposal.

### **1.3 Study Goals**

The objective of this assignment is to evaluate the existing functional and physical adequacy and capacity of the existing site services at the Toronto Zoo (Zoo) complex and identify retrofit / replacement / repair / maintenance / expansion needs. This survey will address the needs of the Zoo by ensuring that the existing facilities are adequate to meet both the existing demand and reasonably foreseeable future expansion to Zoo facilities.

The Site Services Study is a comprehensive study of the condition of the utility systems and their components. The audit includes a complete inventory of the current use and capacity of the services. A summary of the goals of this project is:

1. Identify and quantify current deficiencies in all components of the services.
2. Develop an understanding of the future needs of the Zoo complex so that the Zoo can predict the funding necessary to maintain the services in an appropriate condition after the reduction or elimination of the current required repairs liability.
3. Provide an inventory of the existing use of the services including renewal cost allocation.
4. Use the study as the basis of a dynamic management tool which will continue to provide an accurate record of the state of the physical plant. The system should be capable of predicting the funding required to maintain desired conditions and will foster the creation of multi-year comprehensive capital implementation plans.

## 1.4 Study Methodology

Each utility system and site component is inspected and measured. The costs associated with each component are grouped into 3 distinct categories as follows:

### Type 1: Required Repairs Costs

This category includes costs to rectify actual component deficiencies. All components of the systems, which exhibit or suffer from actual deficiencies at the time of this audit, are referred to as "Required Repairs". These deficiencies will require to be rectified in order to ensure that the components continue to serve their intended functions. All costs associated with required repairs are Required Repairs costs.

### Type 2: Preventive Maintenance Costs

This category will affect all the components of the systems requiring periodic inspections/servicing and maintenance. For example, a sump pump requiring cleaning every year will be classified under preventive maintenance.

### Type 3: Capital Improvement Costs

All site servicing systems/components are captured under this category. The repair and replacement of a component is a function of the natural wear/tear and the life expectancy of a component. Over the life of a project, components require periodic renewals in order to maintain the integrity of the facility. All costs associated with capital improvements are called capital improvement costs.

All visible deficiencies for the entire physical plant are identified. Each of the utility and site systems is examined and the remaining useful life of each component is estimated. Finally, the current replacement value of the utility systems and site components is calculated.

The Site Services Study includes deficiencies and anticipated requirements of the utility systems and site components. This comprehensive approach produces a total profile for the entire plant within a conceptual framework consistent with the standard approach for such service systems.

As a physical plant continues to age, additional components wear out. The analysis of life cycle maintenance costs is projected over a long period (25 years for the systems) in order to obtain reasonable average annual projections of the amount of money each component will require to maintain existing conditions.

The information gathered during this audit is analyzed and entered into PEG's Facility Renewal Planning software. The software generates the following three types of reports:

Portfolio Summary Cost Report: This report provides a highly condensed summary of the costs associated with each cost type. The cost columns over the 25-year planning horizon are divided into 10 groups. The costs for the first five years are given on a year by year basis. The costs for the remaining 20 years are put into five (5) year groups. All the future costs are inflated to reflect cost escalation and inflation. The last column gives the subtotal.



**Detailed Cost Report:** This report provides a condensed summary of the costs associated with each element of repair requirement. The cost columns over the 25-year planning horizon is divided into 10 groups and is similar to the Portfolio Summary Cost described above.

**Recommendation Report:** This report provides a detailed description of each repair requirements. The report is divided into 7 columns. Column 1 gives an identity number to each repair need. Column 2 describes the location of the repair need. Column 3 gives the priority of the work required relative to other work requirements. A description of the priorities is given below. Column 4 gives the category of the work required. Column 5 gives the description of the deficiency resulting in the need for repairs. Column 6 describes the correction needed to rectify the problem. Alternative solutions are also described. Column 7 gives the budget cost in today's dollar for rectifying the deficiency. The format of the recommendation report for Capital Improvement Costs is slightly different and self-explanatory, consisting of 14 columns.

**Priority Ranking Of Recommended Repairs**

Each observed required repair is assigned a number that defines the priority of the work relative to others.

Priority No.	Description
1	Repairs of a safety nature where deficiencies have significant probability of harm to people and animals causing death and severe injury.
2	Repairs of a safety nature where deficiencies have significant probability of causing damage to health and minor injuries.
3	Repairs where deficiencies have a risk of consequential damage with high financial cost.
4	Repairs where deficiencies have risk of consequential damage with medium financial cost.
5	Repairs where deficiencies have a risk of consequential damage with low financial cost.
6	Repairs where deficiencies have no risk of consequential damage but are necessitated by the need for upgrades to improve or replace building components.

Categories Definition

All building systems and components repair/retrofit costs are grouped into categories, which define their impact.

Category Name:	Description
Regulatory:	These are costs, which arise as a result of regulatory requirements from all regulatory agencies. For example, costs incurred to upgrade existing access to achieve barrier free access for the handicapped will fall into this category.
Energy:	These are costs associated with energy conservation measures. For example, costs incurred to upgrade lighting fixtures from incandescent to florescent, etc.
Building Integrity:	There are costs, which are related to the overall integrity and soundness of a building, particularly the building envelope and structural systems. For example, rusting and delamination of concrete cladding, cracking of caulking.
Life Safety:	These are costs, which are associated with life and health safety concerns. For example, costs incurred to repair damaged or missing exit signs, dysfunctional heat detectors, etc.
Air Quality:	These are costs associated with health safety, primarily arising from air quality concern. For example, costs incurred to clean the ductwork to improve the quality and flow of air.
Functional:	These are costs, which are associated with upgrading systems to meet their functional requirements. For example, upgrading lighting to higher lux levels, repairing flashing to shed water away from joints, etc.
Appearance	These are cost that is associated mainly with integrity of interior finishes and a esthetic considerations. For example, missing acoustic ceiling tiles, soiled carpet, missing cover plates, etc.
Hazardous Material:	These are costs associated with the removal of hazardous materials.
Environmental:	These are costs associated with environmental concerns such as implementation of the BEPAC program, costs to implement the 3R program, etc.

## 1.5 Description of the Complex

The Zoo property is a rolling, wooded area approximately 710 acres in extent, with approximately 300 developed acres of discrete, fenced areas for the maintenance and exhibit of wild life from around the world. Individual exhibits are provided with gas, water, electrical and sewage services for the care and comfort of the animals and the patrons, and given the area of the site and its combination of wooded hills and streams, there are several kilometres of underground services to be assessed. All distribution systems are underground. This presents both advantages, such as freedom from damage due to wind, snow, vehicles, animals, etc. and disadvantages such as difficulty of access, flooding, corrosion, etc. Construction of the Zoo complex started approximately 25 years ago and has been on-going since, with further changes and expansions proposed for the near future.

## 1.6 Acknowledgments and Assembly of the Report

Numerous consultants and specialists have assisted with the investigations and preparation of this document. In some instances, third and fourth opinions have been obtained. Those consulted, including texts, are noted in the appropriate sections.

Under the direction of Paradigm Engineering Group Inc., the following companies comprise the investigation team:

Paradigm Engineering Group Inc.	Prime Consultant Mechanical/Electrical Engineering
A-1 Fire Hydrant Services (Hydrants, Water Valves)	Inspection/Testing Specialists
Trans Video Inspections (Camera Survey)	Inspection/Testing Specialists
Trade Gas Services (Gas Pressure)	Inspection/Testing Specialists
Civil Underground Limited (Soil excavation)	Inspection/Testing Specialists

The assembly of the information required to prepare this comprehensive Site Services Study was coordinated by Mr. Ernest Onyido, P.Eng of Paradigm Engineering Group Inc.

All files, notes, source data, test results and master files are retained in the offices of Paradigm Engineering Group Inc. and remain the property of the Consultant.

All opinions, conclusions and recommendations are those of the Consultant and represent their best judgement under the natural limitations imposed by the scope of work.

## 1.7 Life Cycle Costing Assumptions

The determination of the life expectancies and replacement costs is somewhat subjective. Every effort has been made to make the numbers as precise as possible, but the actual life of any component may differ substantially from the estimate made. For this reason, we recommend a dynamic approach to the planning and administration of this long term Retrofit/Replacement Program. This report provides a format. It should be reviewed annually as a part of the budget preparation process to reflect actual results and new information available.

The planning horizon for this project is 25 years, however, the projected costs beyond 5 years has limited accuracy and reliability. As a result, we urge that the schedule be revised and issued every five years. The costs for the first five years are given on a yearly basis. The costs for the remaining 20 years are grouped into 5-year increments. Every five years, all work completed should be entered into the system and the next 5 year period will be expanded into yearly costs.

### Limitations

This report is limited in scope to only those service system components, which are specifically referenced in the text. Any components not included have not been reviewed.

This report is intended solely for the client named. It should not be distributed further without our knowledge.

All cost estimates are given in current dollars, and are provided for approximate budget purposes only. Accurate figures can only be obtained by preparing detailed specifications, tendering and receiving competitive quotes from suitable contractors. Lifespan projections are estimates only based upon visual evaluation of existing conditions.

As many of the activities covered by the report involve aesthetic qualities, there is an element of judgment in identifying costs and life cycles for certain elements, particularly finishes. While we endeavor to reflect our perception of the existing standards, adjustments to the life cycle cost may be necessary to comply with the expectation of the owners.

## **2.0 REPORT FINDINGS**

### **2.1 Water System**

#### **2.1.1 General Description of the System**

The above site is supplied with a 14" diameter water main from the City of Scarborough. The water main consists of various pipe sizes and materials. The 14" and 12" mains are of cast iron pipes. The 10" and 8" are of ductile iron and the 4" and 6" mains are made of PVC pipes. There are 29 Fire Hydrants in the existing yards. The incoming pressure is 50 to 55 psi. However, the static pressure drops to about 30 psi in some areas such as the African Savanna exhibit.

The water system comprises of approximately 12700 linear meters of piping, 29 fire hydrants, 148 Valves of various types, 1 Pumping Station and 1 Water Main Chamber. Detailed quantity take-off of the major system components of the underground plant are provided in Appendix 14.

#### **2.1.2 Audit Procedure**

The audit of the water system comprised of a combination of a site walkthrough visual inspection, a review of existing documentation, interviews with maintenance personnel at the Zoo and testing.

##### **a) Site Walkthrough Visual Inspection**

The site was visited on several occasions to inspect representative samples of valve chambers, shut off valves, and back-flow-preventers and fire hydrants.

##### **b) Documentation /History Review**

We were provided with the site services layout drawings for the water system. In addition, we were provided with a copy of the Energy Report prepared by the City of Toronto Corporate Services, Energy Management Office for 1997.

All the above documentation was thoroughly reviewed prior to our site inspections.

##### **c) Interviews with Zoo and City of Scarborough Personnel**

Our inspection team interviewed Mr. Dean Evans and members of his staff during the inspection process to gather information on the types and locations of any known system failures. We also obtained information on the water supply parameters from the City of Scarborough and the Zoo personnel. The audit team also interviewed Mr. Paul Metteta of the City of Scarborough to discuss the requirement of the City of Scarborough for water supply for fire fighting. Mr. Metteta noted that the City of Scarborough requires that the water supply for fire fighting be constructed with a minimum of 8" mains and the mains be constructed in a looped system.

The team also held discussions with various other individuals including Andy Empringham, John Mayoock and Steve Doran of the Scarborough Fire Department. The team spoke with Craig Rose of Marshall Macklin and Monaghan. Through these discussions, it was revealed that the Scarborough Fire Prevention Department accepted the 1995 modifications to the water main for purposes of fire fighting (see Appendix 17).

A copy of this policy is attached as Appendix 15. The Zoo staff reported that there were two water leaks at the 14" main near the parking lot area. They also stated that the leak was repaired.

#### d) Testing

Testing was conducted on all fire hydrants to determine flow rates, residual GPM and static pressures. Excavation and examination of the buried water mains for reported leaks were completed in April, 1999.

### 2.1.3 Audit Findings

#### General Condition of the System

The inspection of a representative sampling of the water supply system and a review of test reports revealed that most of the fire hydrants had adequate water flow rates and pressures. The water flow rate and static/residual pressures were reported to be marginal (30 psi) at two fire hydrant locations, namely; African Pavilion/McDonalds restaurant and the Savana Pavilion/Restaurant. The criteria for minimum pressures needed for fire fighting for a given type of facility is established by the Ontario Building and Fire Codes. The Ontario Fire Marshall's Office has published the "Fire Protection Water Supply" guideline for Part 3 in the Ontario Building Code. See Appendix 18. Table 2 gives the minimum water supply flow rates. Except for the reported water leaks, it is our opinion that the water supply system (buried pipes) is in good condition.

Detailed discussion of our observations is given in Appendixes 1 to 3 under the following cost categories:

- i) Required Repairs
- ii) Preventive Maintenance
- iii) Capital Improvement

### 2.1.4 Comment on Existing Usage/Reserve Capacity and Future Requirements

From our review of the energy report, the water consumption for 1997 was 330,480 cubic meters. In 1995 the consumption was 273,371 cubic meters. There was an increase in water consumption of 20.9% from 1995 to 1997. Our calculations indicate that there is considerable water available to the system, in the order of 5 – 6 times the existing consumption. Water pressure for fire fighting purposes was marginal in some areas. Although water volume is adequate, future expansions or additions to water usage must contemplate upgrading the water system. We have recommended the installation of a second water supply line. This solution will be designed and implemented to address the concern with marginal water pressures. Cost for implementing this system is estimated at approximately \$1.0 M

## 2.2 Gas System

### 2.2.1 General Description of the System

The existing facility at the present time is serviced by a 4" diameter gas main. Distributed throughout the site by a combination of 1", 2", 3" and 4" mains. We understand from the Zoo that the design pressure is 50 psi. However, the actual pressure on-site is about 44 psi. The gas service presently supplies heating equipment such as boilers, make-up air-handling units, furnaces, domestic water heaters and rooftop hot water tanks, pool heaters, McDonald Restaurant kitchen equipment, emergency

generators for various Pavilions, etc. Quantity take-offs of the major system components and the underground plant are provided in Appendix 14.

### 2.2.2 Audit Procedure

The audit of the gas system comprised of a combination of a site walkthrough visual inspection, a review of existing documentation, interviews with Consumers Gas and maintenance personnel at the Zoo and testing.

#### a) Site Walkthrough Visual Inspection

The site was visited on several occasions to inspect representative samples of the gas regulators, valves, connections and the condition of exposed gas pipes. Selected sites for gas flow tests were chosen to permit inspection and examination of the gas distribution and control system.

#### b) Documentation /History Review

We were provided with the site services drawings showing the gas mains and branches. In addition, we were provided with a list of all the gas-fired equipment for various areas and pavilions. We were also provided with the following report:

1. Energy Report prepared by the City of Toronto Corporate Services, Energy Management Office for 1997.

All the above documentation was thoroughly reviewed prior to our site inspections.

#### c) Interviews with Zoo Maintenance Personnel and Consumers Gas

Our inspection team interviewed Mr. Dean Evans, Mr. Gary Bowerman and other members of the Zoo staff during the inspection process to gather information on the types and locations of any known system failures. No system deficiency was reported by Zoo staff, although it was reported by Zoo staff that a gas software survey based on the supply pressure, pipes sizes and lengths, indicated that there is a possible insufficiency in gas supply. The Zoo also reported that the existing Eurasia exhibit presently has no gas supply and heating is currently electric. The Zoo staff stated that it is proposed to supply gas to this area, hence the need to conduct an analysis of the feasibility and cost of this proposal. Mr. Brian Black of Consumers Gas was interviewed and he provided the following information.

- a) Ten years ago, there were gas leaks at the Monorail line and the monkey exhibit area. He stated that significant portions of the gas pipes were replaced.
- b) The Consumers Gas Company does conduct an annual gas leaks survey at the Zoo covering all underground pipes. He stated that the 1999 survey revealed no leaks.
- c) The Consumers Gas Company does not conduct an annual corrosion survey unless leak detection failed.
- d) He stated that all the pipes are protected anodes which slows down the corrosion of steel pipes. He recommended that a corrosion survey be completed to assure the integrity of the gas line system.

#### d) Testing

Gas pressure tests were performed at the main incoming supply and at several other locations including the Indo-Malayan Pavilion and the North Main Service building.

### 2.2.3 Audit Findings

#### General Condition of the System

An inspection of a representative sampling of gas lines and accessories and a review of the test reports indicated that there is a discrepancy between the design pressure and the actual pressure. The design pressure of 50 psi is higher than the actual test pressure of 44 psi.

Detailed discussion of our observations is given in Appendixes 1 to 3 under the following categories.

- i) Required Repairs
- ii) Preventive Maintenance
- iii) Capital Improvement

### 2.2.4 Comment on Existing Usage/Reserve Capacity and Future Requirements

From our review of the energy report, the gas consumption for 1997 was 2,011,432 cubic meters. In 1995 the consumption was 1,802,733 cubic meters. There was an increase in gas consumption of 11.6% from 1995 to 1997. Discussion with Consumer's Gas indicate that the available capacity of the existing service in the order of 3 times the existing consumption, hence there is adequate capacity for the expansions proposed for the North America area and Eurasia area. Given that the size of the loadings and point of connection on the gas service for the proposed North American area and Eurasia areas are not known, a definite conclusion cannot be made. If the proposed design load is within the existing supply capacity, no upgrade will be required, otherwise the service will have to be upgraded to deliver higher pressure. Consumers Gas has confirmed that the existing supply pressure can be boosted to deliver up to 60 psi to the Zoo system.

## 2.3 Sewer System

### 2.3.1 General Description of the System

The above site has a 14" Class 2400 A.C. sanitary main which connects to the City main. The 12", 10", 8" and 6" diameter branches serve areas and Pavilions.

The storm main is 42" concrete, class IV, which connects from the site through 27", 24", 18", etc. pipes and storm water is dumped into creeks and the Rouge River. Quantity take-offs of the major system components and the underground plant are provided in Appendix 14.

### 2.3.2 Audit Procedure

The audit of the sewer system comprised of a combination of a site walkthrough visual inspection, a review of existing documentation, interviews with maintenance personnel at the Zoo and testing.

#### a) Site Walkthrough Visual Inspection

The site was visited on several occasions to inspect representative samples of manholes, catch basins, drains and piping.

#### b) Documentation /History Review



We were provided with the sanitary and storm sewer site services drawings. All the above drawings thoroughly reviewed prior to our site inspections.

c) Interviews with Zoo Maintenance Personnel

Our inspection team interviewed Mr. Dean Evans and members of his staff during the inspection process to gather information on the types and locations of any known system failures. We were informed of a situation in the African Savannah area where 2 – 8” lines come together into 1 – 12” line. Sewer backup has been experienced in this area.

d) Testing

Based on information from interviews and drawing review, camera surveys of the sewer systems was conducted.

2.3.3 Audit Findings

General Condition of the System

A camera survey of a representative sampling of sanitary and storm sewers was done. Deposits of debris and some calcite formation were observed in the sanitary system. Considering then extensive nature of the sanitary system, together with its age and the environmental condition to which it is subject, the system is in overall good condition.

The storm sewer system had considerably heavier debris deposits, to the point where camera access was blocked in numerous runs. The variety and amount of debris is to be expected considering the uncontrolled nature of materials entering the system. Considering the extensive nature of the storm system, together with its age and environmental and loading conditions to which it is subject, the system is considered to be in good condition. The complete flushing of the system is recommended to bring it up to functional adequacy.

Detailed discussion of our observations is given in Appendixes 1 to 3 under the following categories

- i) Required Repairs
- ii) Preventive Maintenance
- iii) Capital Improvement for the sewer system are given in Appendixes 1 - 3.

2.3.4 Comment On Existing Usage/Reserve Capacity and Future Requirements

Our inspection and review of the videotapes revealed that the existing demand or flow is approximately 20-40% of the available capacity of the sewers. It is our opinion that under the circumstances there is sufficient reserve capacity to accommodate the proposed expansions of Zoo facilities, namely:

- Relocation of the Canadian area to the North American area;

Unlike the electrical and water systems, the actual demand/loading of the storm and sanitary sewer system cannot be precisely quantified. One approach to the determination of existing demand and reserve capacity is to conduct an analysis of storm water run-off and waste water discharge into the system based on the current location of the buildings and facilities and the spatial distribution of the landscaped areas. Results would be compared with information gathered from the original design. The

second approach is to examine and estimate the actual loading in the sewers from a camera survey of selected locations. The latter approach is more realistic and it has been adopted in this study.

## 2.4 Electrical System

### 2.4.1 General Description of the System

The Zoo property is served by a 3-ph, 27.6kV line fed from a Scarborough Public Utilities Commission pole line on Old Finch Avenue. The service comes in to outdoor 27.6kV, 600A main switchgear on Zoo property and is distributed at 27.6kV through 28kV, single conductor cables running to a number of buried transformer vaults throughout the grounds. Cables are direct buried in sand-filled trenches between transformers, except where the cables pass under roadways where they are installed in concrete duct banks.

Cables are run as often as possible directly between transformers and from transformers to buildings, but there are some instances where splicing for taps has been done directly in the trench. Exterior transformers are submersible type, ranging from 300kVA to 750kVA, 27.6kV input, 208V/120V output to the utilization equipment inside the buildings. There are 49 exterior transformers in 27 underground vaults and approximately 9 miscellaneous outlets throughout the grounds. The parking lots have 33 lighting standards. Quantity take-offs of the major system components and the underground plant are provided in Appendix 14.

### 2.4.2 Audit Procedure

The audit of the electrical system comprised of a combination of a site walkthrough visual inspection, a review of existing test documentation and interviews with maintenance personnel at the Zoo

#### a) Site Walkthrough Visual Inspection

The site was visited on several occasions to inspect representative samples of manholes, transformer vaults and exterior switchgear. Selected transformer vaults were de-energized to permit inspection of the transformers and the condition of the cabling and vaults. Twenty-five percent of the vaults were inspected.

#### b) Documentation /History Review

We were provided with the electrical service drawings. In addition, we were provided with two reports on the electrical system, namely:

1. G.T. Wood test report on transformers and switchgear dated December, 1994, reference No. 9951.
2. Black & McDonald -- High Voltage Maintenance Reports dated August 1999, Reference No. 6621
3. Black & McDonald -- Submersible Transformer Failure/Replacement Report dated August 1999, Reference No.6638
4. Energy Report prepared by the City of Toronto Corporate Services, Energy Management Office for 1997.

All the above documentation was thoroughly reviewed prior to our site inspections.

6

c) Interviews with Zoo Maintenance Personnel

Our inspection team interviewed Mr. Dean Evans and members of his staff during the inspection process to gather information on the types and locations of any known system failures. We were informed of approximately 7 cable failures and 2 transformer breakdowns.

d) Testing

Based on information from interviews and document review, testing of the electrical system was not deemed necessary and was not conducted.

2.4.3 Audit Findings

General Condition of the System

An inspection of a representative sampling of vaults and cable chambers and a review of repair records was done. Considering the extensive nature of the electrical system, together with its age and the environmental conditions to which it is subject, the overall system is in average condition.

Detailed discussion of our observations is given in Appendixes 1 to 3 under the following categories

- i) Deferred Maintenance
- ii) Preventive Maintenance
- iii) Capital Improvement

2.4.4 Comment on Existing Usage/Reserve Capacity and Future Requirements

From our review of the energy report, the electrical energy consumption for 1997 was 10,171,317 kWh. In 1995 the consumption was 10,206,299 kWh. There was a decrease in electrical energy consumption of 0.3% from 1995 to 1997. The Electrical Code requires that the sizing of electrical power services be designed so that the load is no more than 80% of the service capacity. The 1997 demand was reported to be 19031 KW and the available capacity is 22919 KW. This translates to 83% of available capacity. The demand has marginally exceeded the Code prescribed limit. As a result, any further expansion or addition to electrical energy loads must contemplate and include upgrading the electrical service.

Ontario Hydro and the local utilities have been examining their vulnerability to potential Y2K problems and have initiated measures to ensure the continuity of electrical supply.

2.5 Communications/Data

2.5.1 General Condition of the System

Bell Telephone service is provided from the pole line along Old Finch Avenue. The service is routed underground to the Administration Building. Bell Telephone Service is located around Pavilions and restaurant areas to supply public telephones but is not extended to the Paddock areas. The system is serviced by a 50-pair underground cable system. The Zoo provides an internal telephone system (PAX), Mitel No. SX-2000SG, fire detection in each building, computer service and security monitoring. We understand that the Zoo purchased (not leased) the Mitel system in 1994 and installed and service it themselves. The Mitel communication system is serviced by 2-200 pair underground cables run to all buildings and areas of the Zoo. Data and power cables may be routed in the same

trench, duly segregated, and use separate cable chambers. Take-offs of the major system components and the underground plant are provided in Appendix 15.

### 2.5.2 Audit Procedure

The audit of the communications/data system comprised of a combination of a site walkthrough visual inspection, a review of existing documentation and interviews with Mitel Corporation and maintenance personnel at the Zoo.

#### a) Site Walkthrough Visual Inspection

The site was visited on several occasions to inspect representative samples of connections and cables.

#### b) Documentation /History Review

We were provided with the site services drawings showing the communication line routing.

All the above drawings were thoroughly reviewed prior to our site inspections.

#### c) Interviews with Zoo Maintenance Personnel

Our inspection team interviewed Mr. Dean Evans and other members of his staff during the inspection process to gather information on the types and locations of any known system failures. It was reported by the Zoo that several pairs in the Bell cable between the old Administration building and the Indo-Malayan Pavilion are inoperative.

### 2.5.3 Audit Findings

#### General Condition of the System

There have been no reports of dissatisfaction with the Zoo's internal PAX system and all exposed cable and connections which were examined appeared to be in good condition.

### 2.5.4 Comment on Existing Usage/Reserve Capacity and Future Requirements

From our discussions with the supplier, we understand that this system is expandable to provide several thousand lines. We conclude that the existing system is suitable to service any anticipated expansion of the Zoo's facilities with respect to voice communication.

The system is not specifically protected against possible Y2K problems, but if it is being used for communication purposes only, with no business or data transfer applications, date problems will not affect this system and equipment, except as incoming power for the system power supply may be adversely affected.

**APPENDIX 1**

**PORTFOLIO SUMMARY REPORT**



## Portfolio Summary Report

METROPOLITAN TORONTO ZOO

Building Name	Replacement	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal
<b>Capital Improvement</b>											
Toronto Zoo	\$1,150,000.00	\$85,000	\$118,450	\$108,212	\$79,223	\$187,960	\$266,009	\$571,292	\$406,648	\$392,535	\$2,215,329
Capital Improvement	\$1,150,000	\$85,000	\$118,450	\$108,212	\$79,223	\$187,960	\$266,009	\$571,292	\$406,648	\$392,535	\$2,215,329
<b>Preventive Maintenance</b>											
Toronto Zoo	\$1,150,000.00	\$55,600	\$57,268	\$58,986	\$60,756	\$62,578	\$342,204	\$396,708	\$459,893	\$533,142	\$2,027,135
Preventive Maintenance	\$1,150,000	\$55,600	\$57,268	\$58,986	\$60,756	\$62,578	\$342,204	\$396,708	\$459,893	\$533,142	\$2,027,135
<b>Required Repairs</b>											
Toronto Zoo	\$1,150,000.00	\$338,150									\$338,150
Required Repairs	\$1,150,000	\$338,150	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$338,150
<b>Total</b>		\$478,750	\$175,718	\$187,198	\$139,978	\$250,538	\$608,212	\$966,000	\$666,541	\$825,678	\$4,580,614





**APPENDIX 2**

**DETAILED COST REPORT**

***REQUIRED REPAIRS***

***CAPITAL IMPROVEMENT***

***PREVENTIVE MAINTENANCE***



# Detailed Cost Report

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING, 361A Old Finch Road,  
 TORONTO ZOO  
 Scarborough

Project Number 98820  
 26-Oct-99  
 Page: 1  
 METROPOLITAN TORONTO ZOO

Toronto Zoo  
 Required Repairs

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal
<b>ELECTRICAL</b>											
ELRR-001	Primary and Secondary Cables	\$20,000									\$20,000
ELRR-002	Flooding of Cables										\$0
ELRR-003	Main Outdoor Switchgear	\$10,000									\$10,000
ELRR-004	Outdoor Switchgear										\$0
ELRR-005	Vaults	\$3,000									\$3,000
ELRR-006	Power Cables										\$0
ELRR-007	Transformers										\$0
ELRR-008	Black & McDonald Report	\$45,000									\$45,000
<b>ELECTRICAL</b>		<b>\$78,000</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$78,000</b>
		<b>Sub Total</b>									

<b>WATER SYSTEM</b>											
WSRR-001	Main	\$100,000									\$100,000
WSRR-002	Hydrant	\$500									\$500
WSRR-003	Hydrant	\$500									\$500
WSRR-004	Hydrant	\$2,000									\$2,000
WSRR-005	Hydrant	\$600									\$600
WSRR-006	Hydrant	\$400									\$400
WSRR-007	Hydrant	\$150									\$150
WSRR-008	Hydrant	\$600									\$600
WSRR-009	Hydrant	\$500									\$500
WSRR-010	Hydrant	\$2,000									\$2,000
WSRR-011	General	\$40,000									\$40,000
<b>WATER SYSTEM</b>		<b>\$147,250</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$147,250</b>
		<b>Sub Total</b>									

<b>STORM/SANITARY SEWER</b>											
SSRR-001		\$30,000									\$30,000
SSRR-002		\$300									\$300
SSRR-003											\$0
SSRR-004											\$0
SSRR-005											\$0
SSRR-006		\$10,000									\$10,000
SSRR-007		\$2,000									\$2,000
SSRR-008	None	\$65,000									\$65,000
SSRR-009	General	\$600									\$600
<b>STORM/SANITARY SEWER</b>		<b>\$107,900</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$107,900</b>
		<b>Sub Total</b>									

# Detailed Cost Report

SITE SERVICES ASSESSMENT FOR LONG TERM  
FACILITY RENEWAL PLANNING,  
TORONTO ZOO  
Scarborough

Toronto Zoo  
Required Repairs

METROPOLITAN TORONTO ZOO

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal
<b>GAS SYSTEM</b>											
GSRR-003	General	\$5,000									\$5,000
		<b>Sub Total</b>									
		\$5,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,000
<b>Required Repairs</b>											
		<b>Sub Total</b>									
		\$338,150	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$338,150
<b>Toronto Zoo</b>											
		<b>Sub Total</b>									
		\$338,150	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$338,150
		<b>Total</b>									
		\$338,150	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$338,150

# Detailed Cost Report

Project Number 98820  
26-Oct-99  
Page: 1  
METROPOLITAN TORONTO ZOO

SITE SERVICES ASSESSMENT FOR LONG TERM  
FACILITY RENEWAL PLANNING,  
TORONTO ZOO  
Scarborough  
361A Old Finch Road,  
Toronto Zoo  
Capital Improvement

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal	
<b>ELECTRICAL</b>												
ELCA-004	Replace underground cable between North	\$50,000									\$50,000	
ELCA-005	Replace Light Standards - 6% every 5 years.			\$6,365			\$7,829		\$9,628	\$11,842	\$35,864	
ELCA-006	Repair Transformer Vault -20% every 10 yea							\$20,159			\$20,159	
ELCA-007	Replace 30% of elec. Panels every 5 years.			\$5,305			\$6,524		\$8,024	\$9,868	\$29,720	
ELCA-008	Replace transf. 4 every 2 years	\$25,000		\$26,523		\$28,138	\$61,521	\$107,057	\$82,878	\$143,875	\$474,791	
ELCA-009	Replace underground power cables between		\$103,000								\$103,000	
ELCA-010	Replace underground power cable between			\$39,784							\$39,784	
ELCA-011	Replace underground power cables between				\$68,295						\$68,295	
ELCA-012	Replace underground power cables between				\$56,275						\$56,275	
ELCA-013	Replace underground power cables between						\$96,946				\$96,946	
<b>ELECTRICAL</b>		<b>\$76,000</b>	<b>\$103,000</b>	<b>\$77,976</b>	<b>\$68,295</b>	<b>\$84,413</b>	<b>\$162,519</b>	<b>\$127,215</b>	<b>\$100,330</b>	<b>\$165,585</b>	<b>\$684,534</b>	
		<b>Sub Total</b>										

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal	
<b>WATER SYSTEM</b>												
WWSA-002	Replace 20% of water valves every 4 years.					\$90,041		\$114,061		\$144,489	\$348,590	
WWSA-003	Replace 20% Of drinking fountains every 5						\$1,391		\$1,870		\$3,261	
WWSA-004	Replace 30% Of manholes in 15 years								\$37,391		\$37,391	
WWSA-005	Replace pumping station in 5 years						\$34,778				\$34,778	
WWSA-006	Repairs to 20% water main chamber in 15 yr								\$15,560		\$15,560	
WWSA-007	Replace 100 feet of water mains every 2 yrs.			\$21,218			\$23,881	\$57,130	\$34,049	\$38,322	\$174,600	
<b>WATER SYSTEM</b>		<b>\$0</b>	<b>\$0</b>	<b>\$21,218</b>	<b>\$0</b>	<b>\$90,041</b>	<b>\$60,050</b>	<b>\$171,191</b>	<b>\$68,859</b>	<b>\$182,811</b>	<b>\$614,200</b>	
		<b>Sub Total</b>										

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal	
<b>STORM/SANITARY SEWER</b>												
SSCA-001	Replace pipes - 6 m every 5 yrs.						\$11,593		\$15,590		\$27,172	
SSCA-002	Replace pumping station in 10 yrs.							\$107,513			\$107,513	
SSCA-003	Repair 50% of manholes in 15 yrs.								\$77,898		\$77,898	
SSCA-005	Replace 100% of area drains in 13 yrs							\$10,280			\$10,280	
SSCA-007	Replace in 10 years.							\$107,513			\$107,513	
SSCA-008	Replace 50% Of manholes in 15 yrs								\$46,739		\$46,739	
SSCA-010	Replace 50% Of Catch Basins in 15 yrs								\$46,739		\$46,739	
<b>STORM/SANITARY SEWER</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$11,593</b>	<b>\$228,306</b>	<b>\$186,956</b>	<b>\$0</b>	<b>\$423,855</b>	
		<b>Sub Total</b>										

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal	
<b>COMMUNICATION SYSTEM</b>												
CSCA-002	Allowance for equip. technology upgrdae							\$20,159			\$20,159	
CSCA-004	Underground communication cables between	\$10,000									\$10,000	
CSCA-005	Underground communication cables between		\$12,360								\$12,360	
CSCA-006	Underground communication cables between			\$7,957							\$7,957	

# Detailed Cost Report

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING,  
 TORONTO ZOO  
 Scarborough

Project Number 98820  
 26-Oct-99  
 Page: 2

Toronto Zoo  
 Capital Improvement

METROPOLITAN TORONTO ZOO

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal
CSCA-007	Underground communication cables between				\$10,927						\$10,927
CSCA-008	Underground communication cables between					\$10,130					\$10,130
CSCA-009	Underground communication cables between						\$12,752				\$12,752
<b>COMMUNICATION SYSTEM</b>											
	<b>Sub Total</b>	\$10,000	\$12,960	\$7,957	\$10,927	\$10,130	\$12,752	\$20,159	\$0	\$0	\$84,264

## GAS SYSTEM

GSCA-001	Repair Gas system valves - 20% every 2 ye			\$1,081			\$1,194	\$2,857	\$1,702	\$1,916	\$8,730
GSCA-002	Repair gas/fittings - 6 m every two year		\$3,090			\$3,377	\$3,690	\$8,437	\$10,075	\$5,748	\$34,416
GSCA-003	Repair regulators/meimeters - 20% every 5 ye						\$13,911	\$16,127	\$18,696	\$21,873	\$70,407
<b>GAS SYSTEM</b>											
	<b>Sub Total</b>	\$0	\$3,090	\$1,081	\$0	\$3,377	\$18,795	\$27,421	\$30,473	\$29,338	\$113,664
<b>Capital Improvement</b>											
	<b>Sub Total</b>	\$85,000	\$118,450	\$108,212	\$79,223	\$187,960	\$286,009	\$671,292	\$408,648	\$377,733	\$2,200,627
<b>Toronto Zoo</b>											
	<b>Sub Total</b>	\$85,000	\$118,450	\$108,212	\$79,223	\$187,960	\$286,009	\$671,292	\$408,648	\$377,733	\$2,200,627
	<b>Total</b>	\$85,000	\$118,450	\$108,212	\$79,223	\$187,960	\$286,009	\$671,292	\$408,648	\$377,733	\$2,200,627

# Detailed Cost Report

Toronto Zoo  
 Preventive Maintenance

METROPOLITAN TORONTO ZOO

ID	Recommendation	2000	2001	2002	2003	2004	2005-2009	2010-2014	2015-2019	2020-2024	SubTotal
<b>WATER SYSTEM</b>											
WSPM-001	Fire Hydrants -Water System	\$5,500	\$5,665	\$5,835	\$6,010	\$6,190	\$33,851	\$39,243	\$45,483	\$52,739	\$200,526
WSPM-002	Fire Hydrants	\$5,800	\$5,974	\$6,153	\$6,338	\$6,528	\$35,698	\$41,363	\$47,874	\$55,616	\$211,464
WSPM-003	Fire Hydrants	\$5,800	\$5,974	\$6,153	\$6,338	\$6,528	\$35,698	\$41,363	\$47,874	\$55,616	\$211,464
WSPM-004	General	\$4,000	\$4,120	\$4,244	\$4,371	\$4,502	\$24,619	\$28,540	\$33,088	\$38,356	\$145,837
	<b>WATER SYSTEM</b>	<b>\$21,100</b>	<b>\$21,733</b>	<b>\$22,365</b>	<b>\$23,067</b>	<b>\$23,748</b>	<b>\$129,866</b>	<b>\$160,649</b>	<b>\$174,628</b>	<b>\$202,326</b>	<b>\$769,280</b>
<b>STORM/SANITARY SEWER</b>											
SSPM-001	Catch Basins, Manholes and Drains	\$12,000	\$12,360	\$12,731	\$13,113	\$13,508	\$75,957	\$85,620	\$99,258	\$115,087	\$437,511
SSPM-002	Storm/Sanitary sewers	\$10,000	\$10,300	\$10,609	\$10,927	\$11,255	\$61,547	\$71,350	\$82,715	\$96,889	\$364,593
SSPM-003	Buried Pipes	\$1,000	\$1,030	\$1,061	\$1,093	\$1,128	\$6,155	\$7,135	\$8,271	\$9,589	\$38,459
SSPM-004	Buried Pipes	\$1,500	\$1,545	\$1,591	\$1,639	\$1,688	\$9,232	\$10,703	\$12,407	\$14,383	\$54,889
	<b>STORM/SANITARY SEWER</b>	<b>\$24,500</b>	<b>\$25,235</b>	<b>\$25,992</b>	<b>\$26,772</b>	<b>\$27,576</b>	<b>\$160,791</b>	<b>\$174,808</b>	<b>\$202,651</b>	<b>\$234,926</b>	<b>\$893,262</b>
<b>GAS SYSTEM</b>											
GSPM-001	Gas Lines and Valves	\$10,000	\$10,300	\$10,609	\$10,927	\$11,255	\$61,547	\$71,350	\$82,715	\$96,889	\$364,593
	<b>GAS SYSTEM</b>	<b>\$10,000</b>	<b>\$10,300</b>	<b>\$10,609</b>	<b>\$10,927</b>	<b>\$11,255</b>	<b>\$61,547</b>	<b>\$71,350</b>	<b>\$82,715</b>	<b>\$96,889</b>	<b>\$364,593</b>
	<b>Preventive Maintenance</b>	<b>\$65,600</b>	<b>\$67,268</b>	<b>\$68,986</b>	<b>\$70,756</b>	<b>\$72,578</b>	<b>\$342,204</b>	<b>\$396,708</b>	<b>\$459,893</b>	<b>\$533,142</b>	<b>\$2,027,136</b>
	<b>Toronto Zoo</b>	<b>\$65,600</b>	<b>\$67,268</b>	<b>\$68,986</b>	<b>\$70,756</b>	<b>\$72,578</b>	<b>\$342,204</b>	<b>\$396,708</b>	<b>\$459,893</b>	<b>\$533,142</b>	<b>\$2,027,136</b>
	<b>Total</b>	<b>\$65,600</b>	<b>\$67,268</b>	<b>\$68,986</b>	<b>\$70,756</b>	<b>\$72,578</b>	<b>\$342,204</b>	<b>\$396,708</b>	<b>\$459,893</b>	<b>\$533,142</b>	<b>\$2,027,136</b>





**APPENDIX 3**

**RECOMMENDATION REPORT**

***REQUIRED REPAIRS***

***CAPITAL IMPROVEMENT***

***PREVENTIVE MAINTENANCE***



ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
ELRR-001	General General	6	Functional	Primary and secondary cables are haphazardly arranged in the vaults, often buried in the mud on the vault floor.	To avoid damage from the gravel and from workers stepping on the cables, and to lessen tripping hazards in the confined space, it is recommended that cable racks be installed and used in the transformer vaults.	\$20,000.00
ELRR-002	General General	4	Functional	On occasion, vaults and cable chambers are flooded by runoff or temporarily rising water tables. We understand that the drains or weeping tiles have been installed at locations where this is a continuing problem.	We recommend that these vaults be monitored frequently during the spring and after heavy rain. We understand that many cables are up to 25 years old. Although this age is much lower than the expected life of the cables, it would be prudent to expose them to as little abuse as possible and the use of cable racks is recommended for this purpose. The cost of this item is included in item ELRR-001 above.	\$0.00
ELRR-003	General General	3	Functional	The main outdoor switchgear was observed to suffer from rust and metal damage.	It is recommended that the entire assembly be examined, repainted and recaulked.	\$10,000.00
ELRR-004	General General	3	Functional	It was noted that ice formed inside all windows on the main outdoor switchgear. This indicates the presence of high humidity and condensation which can lead to insulation failure and reduction of electrical spacings.	It is recommended that condensation prevention measures be undertaken such as the installation of heaters or forced ventilation. The cost of this is included in item ELRR-003 above.	\$0.00
ELRR-005	General General	6	Functional	Some vaults were not numbered in the field. Vaults were not always numbered on the drawings.	It is recommended that all vaults be conspicuously numbered in the field to match the numbering system on the drawings. Un-numbered vaults on the drawings should be assigned numbers.	\$3,000.00

# Recommendation Report

Required Repairs Toronto Zoo

## ELECTRICAL

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
ELRR-006	General General	6	Functional	<p>Over the last 5 years, Toronto Zoo reported approximately seven breakdowns related to the 27.6 KV cable. For the most part, the breakdowns were rectified by simply removing and replacing the defective sections of the cable. From our review of the history of these problems and their correction, augmented with our site inspection, the most plausible cause of the cable failures appears to be manufacturing defects.</p>	<p>This problem could be caused by a combination of several factors such as age, environmental condition, loading and manufacturing defects. We did not find any evidence pointing to either environmental conditions or loading as causes of the reported cable failures. Cables are suitable for direct burial and there was no evidence of excessive heat or humidity or corrosive soil conditions. The most plausible cause of this problem is age and manufacturing defects. Given the length of the run of the service cables it is not unexpected to experience some cable failures. From theoretical considerations, it can be expected that up to 10 feet per 1000 feet of cable will fail and be replaced every 12 years. Based on this, there are two remedial options available. The first one is to replace the entire buried cable system with new cable. This option is not feasible because of cost considerations. The second option is to set aside an annual budget to repair and replace sections of the cable. This option appears to be the most viable under the circumstances and this has been recommended. The cost of this option is given in the section on Capital Improvement. It is further recommended that all occurrences of cable failure be properly documented, describing the cost of repair, nature and location of the problem and the type of repair conducted.</p>	\$0.00
ELRR-007	General General	6	Functional	<p>One transformer blow out was reported at the Lion House in 1996. One transformer blow out was reported at the African pad in 1996. Both occurrences were repaired. It was reported that repair workmen determined that these failures were the result of faulty installation by the contractor who installed the units.</p>	<p>This rate of failure can be anticipated. The theoretical life of a transformer is 30 years, however, repair of up to 10% is anticipated to a transformer every 10 years. Given the above facts, and the history of the transformers, it can be reasonably concluded that the transformers have performed within expectation. There is no required repair. Allowance for periodic replacements has been made in the section on Capital Improvement. We have allowed for replacing 4 transformers every two years. In addition, we recommend that all occurrences of transformer failures be documented, including repair cost and the nature and location of repair.</p>	\$0.00
ELRR-008	General General	2	Functional	<p>The High Voltage Maintenance Report completed by Black &amp; McDonald dated August 1999, Reference Number 6621 contained 23 deficiencies. These deficiencies should be rectified.</p>	<p>It is recommended that all the deficiencies listed in the Black &amp; McDonald Report be rectified. The cost indicated here does not include the cost of replacing the transformers which have been included in the Capital Improvement Schedule.</p>	\$45,000.00

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
WSRR-001	General General	6	Functional	<p>It was reported that on the 14" diameter main there were two leaks which were repaired to remedy the problem temporarily. Three sections of pipe were excavated and exposed for inspection. Approximately 7 feet of the pipes were exposed and at two locations the joints were also exposed. Our inspection of the exposed water mains revealed that the mains were made of ductile iron and that the original protective coatings are still on the pipes. The incidences reported appear to be isolated. There was no evidence of pipe deterioration.</p>	<p>There are two possible solutions to this immediate problem (1) Replace approximately 200 LM of the 14" Main at the vicinity of the leaks. This can be performed at a cost of approximately \$ 40,000.00 (2) Design and install an alternative incoming main adjacent to the existing main of approximately 8 inches PVC to be brought from the city main and tied to the 14" main upstream. The new adjacent line should be designed to have a valve at the point where it joins the existing main. We estimate that this line will be approximately 600 LM long and tied at a point sufficiently far away from the sections currently exhibiting leakage problems. In the event of a leak at the section of main between the city main and the point of intersection of the 8 inch line, the 14 inch main can be shut off and repaired while the 8 inch main continues to supply the Zoo's minimum water flow requirements. This is an outline specification which must be properly designed by a registered engineer. The budget for this work is (600 x \$175/lm) \$100,000. We recommend the second option because replacing any of the section of the 14" does not guarantee that there will not be any further leakage.</p>	\$100,000.00
WSRR-002	General General	4	Life Safety	<p>Hydrant: The Hydrant near the South end of the Indo-Malayan Pavilion has a minor leak at the ground flange.</p>	<p>Service and repair the hydrant to stop the leak.</p>	\$500.00
WSRR-003	General General	4	Life Safety	<p>Hydrant: The Hydrant outside the Gorilla exhibit doors, at the inside/outside holding area leaked when fully charged.</p>	<p>Service and repair the hydrant to stop the leak.</p>	\$500.00
WSRR-004	General General	4	Life Safety	<p>Hydrant: The Hydrant near the inside/outside holding reported marginal test pressure.</p>	<p>Retain a serviceman to service this hydrant.</p>	\$2,000.00
WSRR-005	General General	4	Life Safety	<p>Hydrant: The secondary valve of the Hydrant North of the North American Pavilion (Century make), seized when in the open position.</p>	<p>Service and repair valve on hydrant.</p>	\$600.00
WSRR-006	General General	3	Functional	<p>Hydrant: Leaks were noted at the operating nut packing on the Hydrant North of the Australasia McDonald's restaurant.</p>	<p>Service and repair. Replace packing.</p>	\$400.00

**Recommendation Report**  
**Required Repairs** Toronto Zoo  
**WATER SYSTEM**

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
WSRR-007	General General	5	Life Safety	Hydrant: The left 2-1/2" port cap is missing on the Hydrant South of the Greenhouse.	Replace missing 2-1/2" port cap.	\$150.00
WSRR-008	General General	5	Life Safety	Hydrant: The secondary valve box is broken and the lid is missing from the Hydrant at the East side of the garage. Although still operble, the box has mud in it and needs repair/replacement.	Replace the broken secondary valve box and the lid.	\$600.00
WSRR-009	General General	4	Life Safety	Hydrant: The Hydrant East of Society was flushed, but a flow test could not be done because of the existing site condition (walk ways) and the secondary valve was inoperable since the valve box was full of dirt.	Service and repair valve box.	\$500.00
WSRR-010	General General	6	Life Safety	Hydrant: Most of the Hydrants are not identifiable by number or area in the field. It is recommended that the Hydrants be conspicuously numbered in the field to match the numbering system on the drawings.	Provide and install identifying number tags to match the numbering system on the drawings. Complete the numbering system on the drawings.	\$2,000.00

**Recommendation Report**  
**Required Repairs** Toronto Zoo  
**WATER SYSTEM**

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
----	----------	-----	----------	-------------	------------	-----------------------

WSRR-011	General General	4	Life Safety	<p>The flow and pressure tests on the hydrants revealed that the static and residual pressures ranged from 35 psi upto 65 psi. All fire hydrants tested in excess of 600 gpm at 20 psi. The Ontario Fire Marshal's office design guideline for water supply specifies the minimum water supply flow rate to be 1800L/min for buildings that one storey in building height and does not exceed 600 cubic meter in building area. This recorded flow rates and pressures exceed this minimum requirement. The Ontario Building Code and Ontario Fire Code require that all existing and new fire protection systems meet the approval of local Fire chief i.e., the requirements of the Scarborough Fire Department. The City of Scarborough Fire Department require that fire hydrants be connected to the water main through a looped system. In addition, they require that the water main be 8" but that smaller sizes may be used if hydraulic calculations supporting required water supply were conducted. From our review of the drawings, there are two dead ends in the water system, mainly at the recently developed African Savannah complex. Based on the above observations, the existing water system is not in conformance with the City of Scarborough Fire Department requirement with respect to the lack of a complete looped system. As a result, the requirements of the City of Scarborough Fire Department, must be addressed.</p>	<p>Preliminary consultation with city official reveal that they require as a solution to this problem, that all dead ends be removed from the system and a loop be installed at all fire hydrants. The installation of the loop at each hydrant increases the reliability of water supply. The cost of design and construction of a loop at each hydrant increases the reliability of water supply. The cost of design and construction of a loop to each of the two hydrants will be approximately \$20000 per hydrant at a total cost of \$40,000. This cost is very high and the effectiveness is limited. Hence, we recommend that the Toronto Zoo meet with and negotiate appropriate variance from the city because of the cost prohibitive nature of the remedy. Consideration should be given to the cost of the remedy, the effectiveness of the remedies and the overall impact of the system.</p>	\$40,000.00
----------	--------------------	---	-------------	---	--	-------------

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
SSRR-001	General General	4	Functional	Storm Sewer: A camera inspection of the storm sewers was conducted at a representative sample of the storm sewer system. The camera inspection revealed various deficiencies in the sewer as listed below. Piping North of Indo pavilion has light debris 7m away from manhole 2.	conduct a complete flushing of the entire storm system piping, clean all manhole in the entire complex.	\$30,000.00
SSRR-002	General General	5	Functional	One extra manhole is not shown on the drawing.	Update the existing drawing to show one extra existing manhole.	\$300.00
SSRR-003	General General	4	Functional	Piping East of old elephant house had calcite at service connection. Calcite was also noted at other locations. Given that only 5% of the entire storm sewer system was inspected with the camera, it is suspected that these deficiencies do occur at other locations.	Conduct scrubbing an reaming of the sewer system at locations where calcite is identified. In order to determine the locations where calcite formation has occurred, a complete camera inspection of the entire storm sewer should be conducted. Scrubbing, reaming and possibly grouting techniques should be employed to rectify the calcite problem. This budget include the price of completing a 100% camera survey of the storm sewer and conducting necessary remedies as described above. The budget for this deficiency is included in the cost of item SSRR-008 shown below.	\$0.00
SSRR-004	General General	4	Functional	Storm Sewer: Piping east of Rouge River has light debris under the flow.	Conduct flushing of the system piping. The cost of this is included in item SSRR-001.	\$0.00
SSRR-005	General General	4	Functional	Storm Sewer: Piping under Rouge River has light debris under the flow.	Conduct flushing of the system piping. The cost of this is included in item SSRR-001.	\$0.00
SSRR-006	General General	4	Functional	Sewer backup has been experienced in the African Savannah area where 2 - 8" sanitary lines come together in 1 - 12".	Since camera inspection showed no blockage and only light deposits of debris, it is concluded that the problem arises from a system design deficiency. Retain the services of a qualified engineer to design corrective measures. The solution will involve excavation and replacement of the joints with new pipes to meet current design standard. The budget includes cost of design and construction.	\$10,000.00
SSRR-007	General General	5	Functional	Manholes were not clearly identified in the field.	Identify manholes in the field to match numbers on drawings. Add numbering to drawings.	\$2,000.00



**Recommendation Report**  
**Required Repairs** Toronto Zoo  
**STORM/SANITARY SEWER**

METROPOLITAN TORONTO ZOO

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
----	----------	-----	----------	-------------	------------	-----------------------

SSRR-008	General General	4	Functional	<p>A camera survey of the sanitary sewers was conducted covering approximately 5% of the sewer lines. The survey revealed a significant level of deficiencies including ponding, debris buildup. At one location, the camera was blocked as result of the debris. The following are specific observations as they are listed (a) The sewer lines between North of Gate D to South of Gate D - ponding and debris was observed in the line. Heavy calcite was also observed below a service connection. (b) The sewer lines between South of Gate D to 2nd Manhole South of Gate D - light ponding was noted in the lines. (c) Between 2nd Manhole South of Gate D to 3rd. Manhole South of Gate D - A manhole lid was noted in the manhole. Light ponding was noted. (d) Between 1st manhole west of Eurasia pavilion and north of North American Pavilion - light debris and moderate ponding was noted in the line. (e) Between 1st manhole west of Eurasia Pavilion and ending at Eurasia Pavilion - light ponding and moderate debris in the line. (f) Between south of the Savana Rest. And north east of manhole 10 -- the camera was blocked by heavy gravel. (g) Between south of the VAS Rest. And west of manhole 10 -- the camera was blocked by debris. Light ponding was also noted. (h) Between south east of the Africa Pav. And east entrance of Africa Pav. - camera was blocked by debris. (i) Between south east corner of the elephant house and south west corner of the African Pav. - camera was blocked by debris. (j) Between south west corner of the Africa Pavilion and south west corner of the Elephant House - debris and moderate ponding was noted in the line. (k) Between south west corner of the Africa Pav. And 1st manhole of the north manhole 16, the camera was blocked by debris (l) Between 1st manhole west of the Camel Pen. And 2nd manhole west of the Camel Pen. - Moderate debris in the line.</p>	<p>The deficiencies noted above revealed three major types of problems namely; heavy to moderate debris in the lines, ponding and calcite formation. Out of the 18 runs observed, only in 4 of the runs were the lines found to be in good condition. Fourteen of the eighteen runs indicated some form of deficiency. Given that only approximately 5% of the entire sanitary sewer lines were inspected, it can be reasonably concluded that the other lines which were not viewed will suffer from similar deficiencies to the same degree. In order to rectify these deficiencies, it is recommended that the camera survey be conducted throughout the sanitary lines at a cost of \$15000. Following the survey, all areas suffering from light, moderate to heavy debris should be flushed. We estimate the cost of flushing the entire system to be approximately \$30,000. The problem of ponding will partly be addressed after flushing where the ponding is the result of debris blockage. However, in some cases, the ponding may be the result of settlement of the pipe. The most appropriate solution to such deficiency will be to excavate the section suffering from his problem, raise the pipe and restore the subsoil structure. This solution is very costly and is of limited merit. For the most part, flushing is adequate to ensure proper flow. The third major deficiency was the formation of calcite in the lines. The solution to this problem is to conduct scrubbing, reaming and grouting the joints which are most prone to calcite. All locations where this problem occur will be shown in the camera survey. We estimate a cost of approximately \$20,000 for this solution.</p>	\$65,000.00
----------	--------------------	---	------------	--	---	-------------

SSRR-009	General General	5	Functional	<p>A camera survey of the sanitary sewers was conducted covering approximately 5% of the sewer lines. The survey revealed a significant level of deficiencies including ponding, debris buildup. At one location, the camera was blocked as result of the debris. The following are specific observations as they are listed (a) The sewer lines between 3rd manhole west of the Camel Pen and 4th manhole west of the Camel Pen - The drawing of the Sewer run is not correct. Sewer run does not run to manhole number 8 as shown.</p>	<p>Determine sewer run and termination and record on the drawings.</p>	\$600.00
----------	--------------------	---	------------	--	--	----------

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING,  
 TORONTO ZOO  
 Road, Scarborough

**Recommendation Report**  
 Required Repairs Toronto Zoo  
 COMMUNICATION SYSTEM

Project Number 98920  
 26-Oct-99  
 Page: 8  
 METROPOLITAN TORONTO ZOO

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
----	----------	-----	----------	-------------	------------	-----------------------

CSRR-001	General General	0	Functional	At the time of this inspection and audit, no failure of either equipment or service cables were observed or reported.	No action required.	\$0.00
----------	--------------------	---	------------	---	---------------------	--------

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING,  
 TORONTO ZOO  
 Road, Scarborough

**Recommendation Report**  
**Required Repairs** Toronto Zoo  
**GAS SYSTEM**

Project Number 98820  
 26-Oct-99  
 Page: 9  
 METROPOLITAN TORONTO ZOO

ID	Location	Pty	Category	Description	Correction	Base Year	Budget Cost
----	----------	-----	----------	-------------	------------	-----------	-------------

GSRR-003	General General	5	Functional	Random sampling of the gas regulators and valves revealed that they are not providing adequate pressure. It is concluded that the majority of the gas regulators will suffer similar deficiencies.	Retain a serviceman to check all the regulators, valves and accessories and adjust these components as required.		\$5,000.00
----------	--------------------	---	------------	--	--	--	------------

**\$338,150.00**

**Recommendation Report**  
**Capital Improvement Toronto Zoo**  
**ELECTRICAL**

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING,  
 TORONTO ZOO  
 Scarborough  
 361A Old Finch Road,

Project Number 98820  
 26-Oct-99  
 Page: 1

METROPOLITAN TORONTO ZOO

ID	Location	Pty	Category	Description	Action	Units	Quantity	Budget Cost	Norm Life	Age	Rem. Life	First Occ	Succ Occ
ELCA-004	General General	3	Functional	Underground Service Cable	Replace underground cable between North Service to Americas	LM	4000	\$50,000	50	27	0	2000	2050
ELCA-005	General General	6	Functional	Light Standards	Replace Light Standards - 6% every 5 years.	each	33	\$6,000	30	27	2	2002	2007
ELCA-006	General General	6	Functional	Transformer Vault	Repair Transformer Vault -20% every 10 years	each	27	\$15,000	75	27	10	2010	2020
ELCA-007	General General	6	Functional	Electrical Panels	Replace 30% of elec. Panels every 5 years.	each	3	\$5,000	20	27	2	2002	2007
ELCA-008	General General	6	Functional	Transformers	Replace transf. 4 every 2 years	each	49	\$25,000	30	27	0	2000	2002
ELCA-009	General General	6	Maintenance	Underground Power Cables	Replace underground power cables between Americas & Africa Pav.	LF	4000	\$100,000	50	30	1	2001	2051
ELCA-010	General General	6	Functional	Underground power cable	Replace underground power cable between Africa and Indo Pav.	LF	1500	\$37,500	50	30	2	2002	2052
ELCA-011	General General	6	Functional	Underground power cables	Replace underground power cables between Indo Pav. To Front Entrance	LF	2500	\$62,500	50	30	3	2003	2053
ELCA-012	General General	6	Functional	Underground power cables	Replace underground power cables between Front Entrance & Australasia Pav.	LF	2000	\$50,000	50	30	4	2004	2054
ELCA-013	General General	6	Functional	Underground power cables	Replace underground power cables between Australasia to North service Pav.	LF	3000	\$75,000	50	30	5	2005	2055

ID	Location	Pty	Category	Description	Action	Units	Quantity	Budget Cost	Norm Life	Age	Rem. Life	First Occ	Succ Occ
WSCA-002	General General	6	Functional	Valves -Water System	Replace 20% of water valves every 4 years.	each	199	\$80,000	10	27	4	2004	2008
WSCA-003	General General	6	Functional	Drinking Fountains-Water System	Replace 20%. Of drinking fountains every 5 years	each	18	\$1,200	10	20	5	2005	2010
WSCA-004	General General	6	Functional	Manholes - Water System.	Replace 30%. Of manholes in 15 years	each	5	\$24,000	50	27	15	2015	2030
WSCA-005	General General	6	Functional	Pumping Station	Replace pumping station in 5 years	each	1	\$30,000	20	27	5	2005	2025
WSCA-006	General General	6	Functional	Water Main Chamber	Repairs to 20% water main chamber in 15 yrs	each	1	\$10,000	50	27	15	2015	2035
WSCA-007	General General	6	Functional	Buried Water Pipe	Replace 100 feet of water mains every 2 yrs.	LM	12750	\$20,000	50	27	2	2002	2004

**Recommendation Renort**  
**Capital Improvement Toronto Zoo**  
**STORM/SANITARY SEWER**

ID	Location	Pty	Category	Description	Action	Units	Quantity	Budget Cost	Norm Life	Age	Rem. Life	First Occ	Succ Occ
SSCA-001	General General	6	Functional	Pipe & Fittings	Replace pipes - 6 m every 5 yrs.	LM	19500	\$10,000	75	27	5	2005	2010
SSCA-002	General General	6	Functional	Pumping Station	Replace pumping station in 10 yrs.	Each	329	\$80,000	20	27	10	2010	2030
SSCA-003	General General	6	Functional	Manholes - Sewer System	Repair 50% of manholes in 15 yrs.	Each	329	\$50,000	50	27	15	2015	2065
SSCA-005	General General	6	Functional	General	Replace 100% of area drains in 13 yrs	Each	7	\$7,000	40	27	13	2013	2000
SSCA-007	General General	6	Functional	Pumping Station	Replace in 10 years.	each	329	\$80,000	20	27	10	2010	2020
SSCA-008	General General	6	Functional	Manholes - Storm System.	Replace 50%. Of manholes in 15 yrs	each	329	\$30,000	50	27	15	2015	2030
SSCA-010	General General	6	Functional	Catch Basins - Storm System.	Replace 50%. Of Catch Basins in 15 yrs	each	275	\$30,000	50	27	15	2015	2065

ID	Location	Pty	Category	Description	Action	Units	Quantity	Budget Cost	Norm Life	Age	Rem. Life	First Occ	Succ Occ
CSCA-002	General General	6	Functional	General	Allowance for equip. technology upgrade	LM	1	\$15,000	15	4	10	2010	2030
CSCA-003	General General	6	Functional	General	Replace undergrd cable	LM	12000	\$7,500	50	27	23	2023	2050
CSCA-004	General General	6	Functional	Underground Cables	Underground communication cables between North Service to Americas Pavilions.	LF	2000	\$10,000	50	30	0	2000	2050
CSCA-005	General General	6	Functional	Underground Communication Cables	Underground communication cables between Americas to Africa Pavilions.	LF	4000	\$12,000	50	30	1	2001	2051
CSCA-006	General General	6	Functional	Underground Communication Cables	Underground communication cables between Africa to Indo Pavilions.	LF	1500	\$7,500	50	30	2	2002	2052
CSCA-007	General General	6	Functional	Underground Communication Cables	Underground communication cables between Indo Pavilion to Front Entrance.	LF	2500	\$10,000	50	30	3	2003	2053
CSCA-008	General General	6	Functional	Underground Communication Cables	Underground communication cables between Front Entrance to Australasia Pavilions.	LF	2000	\$9,000	50	30	4	2004	2054
CSCA-009	General General	6	Functional	Underground Communication Cables	Underground communication cables between Australasia to North Service Pavilions.	LF	3000	\$11,000	50	30	5	2005	2055

ID	Location	Pty	Category	Description	Action	Units	Quantity	Budget Cost	Norm Life	Age	Rem. Life	First Occ	Succ Occ
GSCA-001	General General	6	Functional	Valves	Repair Gas system valves - 20% every 2 years	each	4	\$1,000	20	20	2	2002	2004
GSCA-002	General General	6	Functional	Gas pipes and fittings	Repair gas/fittings - 6 m every two year	LM	4150	\$3,000	75	27	1	2001	2003
GSCA-003	General General	6	Functional	Regulators and Meters	Repair regulators/meters - 20% every 5 years	each	30	\$12,000	25	20	5	2005	2005



ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
WSPM-001	General General	4	Life Safety	Fire Hydrants -Overhauling Servicing	The fire hydrants require overhauling and servicing to maintain all operating parts. Allow for the servicing and overhauling of the fire hydrants once every 5 years at an annual cost of \$ 1100.00	\$5,500.00
WSPM-002	General General	4	Life Safety	Fire Hydrants: Fire Flow tests	Conduct annual flow test to check the water pressure and performance of the hydrants on site. Allow an annual budget of \$5800.	\$5,800.00
WSPM-003	General General	4	Life Safety	Fire Hydrants: Leak Detection Tests	The fire hydrants on site require a leak detection test to be performed on them to determine if there are any defective parts in its assembly. Allow an annual budget of \$5800.	\$5,800.00
WSPM-004	General General	6	Maintenance	Manholes, valve and meter chambers. All site services including manholes, valve chambers and meters require annual cleaning and inspection.	Conduct annual inspection and cleaning of all these components on site. Allow an annual budget of \$4000.	\$4,000.00

**Recommendation Report**  
 Preventive Maintenance Toronto Zoo  
 STORM/SANITARY SEWER

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
SSPM-001	General General	6	Maintenance	Catch Basins, Manholes and Area Drains. These site services components require annual cleaning to clear them of dirt and debris.	Flush these services components once every year. Allow annual budget of \$12000.	\$12,000.00
SSPM-002	General General	6	Maintenance	Manholes. These site services components require annual cleaning to clear them of dirt and debris.	Flush these services components once every year. Allow annual budget of \$10000.	\$10,000.00
SSPM-003	General General	6	Maintenance	Buried Pipes. A camera survey is required in order to check the integrity of the underground pipes. This survey is recommended to be performed every 10 years.	Conduct a camera survey of the storm sewer lines every 10 years. Allow an annual budget of \$ 1000.00	\$1,000.00
SSPM-004	General General	6	Maintenance	Buried Pipes. A camera survey is required in order to check the integrity of the underground pipes. This survey is recommended to be performed every 10 years.	Conduct a camera survey of the sanitary sewer lines every 10 years. Allow an annual budget of \$ 1500.00	\$1,500.00

SITE SERVICES ASSESSMENT FOR LONG TERM  
 FACILITY RENEWAL PLANNING,  
 TORONTO ZOO  
 Road, Scarborough

**Recommendation Report**  
 Preventive Maintenance  
**GAS SYSTEM**

Toronto Zoo

Project Number 98820  
 26-Oct-99  
 Page: 3  
 METROPOLITAN TORONTO ZOO

ID	Location	Pty	Category	Description	Correction	Base Year Budget Cost
GSPM-001	General General	6	Maintenance	Gas Lines and Valves. Gas lines, meters, and valves require to be inspected periodically to check for signs of leaks, corrosion etc.	Retain the services of Consumer Gas or its approved contractor to inspect the gas lines and associated components annually. All equipment on site using gas should be included in this annual inspection. All such appliances should be cleaned to ensure proper gas supply. Allow an annual budget of \$ 1000.00.	\$10,000.00

**\$55,600.00**



**APPENDIX 4**

**1997 ENERGY REPORT**



**TORONTO**

---

**1997 Energy Report**

---

**Toronto Zoo**

---

**All Facilities**

---

**Corporate Services  
Energy Management Office, 392-8954**

---

CITY OF TORONTO  
**1997 Energy Report**

TORONTO ZOO

**CONTENTS**

Group Title

**I. ENERGY SAVINGS**

EXECUTIVE SUMMARY

ENERGY CONSUMPTION vs Adjusted Baseline

ENERGY COST vs Adjusted Baseline

**II. MULTI-YEAR ENERGY**

QUARTERLY Energy Consumption

ANNUAL Energy Consumption & Cost



CITY OF TORONTO  
TORONTO ZOO

ALL FACILITIES  
1997 Actual Energy CONSUMPTION & COST vs Adjusted Baseline  
EXECUTIVE SUMMARY


ENERGY TYPE	ENERGY CONSUMPTION				ENERGY COST			
	Name & Unit	Adj.Base 1995	Actual 1997	Energy Change	Percent Change	Adj.Base 1995	Actual 1997	Cost Change
Electricity kWh	10,206,299	10,171,317	(34,982)	-0.3%	\$732,724	\$727,829	(\$4,895)	-0.7%
Natural Gas m <sup>3</sup>	1,802,733	2,011,432	208,699	11.6%	\$263,690	\$296,334	\$32,644	12.4%
Heating Oil litre	13,458	9,228	(4,230)	-31.4%	\$4,433	\$3,058	(\$1,376)	-31.0%
Gasoline litre	61,427	59,577	(1,850)	-3.0%	\$34,107	\$33,120	(\$988)	-2.9%
Diesel litre	22,362	28,759	6,397	28.6%	\$10,132	\$13,077	\$2,946	29.1%
Propane litre	50,973	61,645	10,671	20.9%	\$17,988	\$21,650	\$3,663	20.4%
Water m <sup>3</sup>	28,849,623	30,972,943	2,123,321	7.4%	\$220,768	\$260,329	\$39,561	17.9%
<b>Total</b>	<b>30,208,091</b>	<b>32,417,110</b>	<b>2,209,019</b>	<b>7.3%</b>	<b>\$1,283,842</b>	<b>\$1,355,396</b>	<b>\$71,554</b>	<b>5.6%</b>

NOTE:

- 1) Adj.Base - The 1995 energy consumption and cost are adjusted to the 1997 billing periods, weather conditions and energy costs.
- 2) Actual - The current year (1997) actual energy consumption and cost.
- 3) ekWh - equivalent kilowatt-hour; water consumption is not included in total energy.


ALL FACILITIES  
1997 Actual ENERGY CONSUMPTION & COST

### Energy Consumption



Total 32,417.1 equivalent megawatt hours  
Total 7,375 tonnes CO2

### Energy Cost



Total \$1,355.4 millions

NOTE: Htg Energy includes natural gas & heating oil; Veh. Fuel includes gasoline, diesel and propane.

Prepared By: Metro Corporate & Human Resources Dept., Energy Management Office ..... Date: 9/3/97 ..... File: E:\energy\mstrveff\mstrveff.mxd

CITY OF TORONTO  
TORONTO ZOO

**MASTER METERS**  
**1997 Actual ENERGY CONSUMPTION VS Adjusted Baseline**

FACILITIES Facility ID and Name	ELECTRICITY (kWh)			NATURAL GAS (m <sup>3</sup> )			WATER (m <sup>3</sup> )			TOTAL (ekWh)		
	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change
DR Domain Ride & Garage Bldg	188,060	152,460	-18.9%	—	—	—	—	—	—	188,060	152,460	-18.9%
FB Finch Barn	52,079	9,120	-82.5%	—	—	—	—	—	—	52,079	9,120	-82.5%
GHS Gate House	14,867	9,068	-39.0%	—	—	—	—	—	—	14,867	9,068	-39.0%
MB Main Barn	227,027	207,600	-8.6%	—	—	—	—	—	—	227,027	207,600	-8.6%
ZMM Zoo Main Meter	9,664,589	9,730,005	0.7%	1,802,733	2,011,432	11.6%	273,371	330,480	20.9%	28,307,913	30,531,631	7.9%
VH Valley Halla	25,828	19,096	-26.1%	—	—	—	—	—	—	25,828	19,096	-26.1%
ZPS Zoo Police Stable	33,849	43,968	29.9%	—	—	—	—	—	—	33,849	43,968	29.9%
<b>Total</b>	<b>10,206,299</b>	<b>10,171,317</b>	<b>-0.3%</b>	<b>1,802,733</b>	<b>2,011,432</b>	<b>11.6%</b>	<b>273,371</b>	<b>330,480</b>	<b>20.9%</b>	<b>28,849,623</b>	<b>30,972,943</b>	<b>7.4%</b>

**MASTER METERS**  
**1997 Actual ENERGY COST VS Adjusted Baseline**

FACILITIES Facility ID and Name	ELECTRICITY COST			NATURAL GAS COST			WATER COST			TOTAL COST		
	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change
DR Domain Ride & Garage Bldg	\$15,094	\$12,342	-18.2%	—	—	—	—	—	—	\$15,094	\$12,342	-18.2%
FB Finch Barn	\$4,965	\$833	-83.2%	—	—	—	—	—	—	\$4,965	\$833	-83.2%
GHS Gate House	\$1,387	\$850	-38.8%	—	—	—	—	—	—	\$1,387	\$850	-38.8%
MB Main Barn	\$18,617	\$16,130	-13.4%	—	—	—	—	—	—	\$18,617	\$16,130	-13.4%
ZMM Zoo Main Meter	\$687,572	\$692,323	0.7%	\$263,690	\$296,334	12.4%	\$220,768	\$260,329	17.9%	\$1,172,030	\$1,248,986	6.6%
VH Valley Halla	\$2,245	\$1,684	-25.0%	—	—	—	—	—	—	\$2,245	\$1,684	-25.0%
ZPS Zoo Police Stable	\$2,844	\$3,667	28.9%	—	—	—	—	—	—	\$2,844	\$3,667	28.9%
<b>Total</b>	<b>\$732,724</b>	<b>\$727,829</b>	<b>-0.7%</b>	<b>\$263,690</b>	<b>\$296,334</b>	<b>12.4%</b>	<b>\$220,768</b>	<b>\$260,329</b>	<b>17.9%</b>	<b>\$1,217,182</b>	<b>\$1,284,492</b>	<b>5.5%</b>

NOTE: Adj.Base - The 1995 energy consumption and cost are adjusted to the 1997 billing periods, weather conditions and energy costs.  
Actual - The current year (1997) actual energy consumption and cost.  
ekWh - Equivalent kilowatt-hour (1 cubic metre of Natural Gas = 10.3417 ekWh).

CITY OF TORONTO  
TORONTO ZOO

**MCDONALD RESTAURANTS**  
**1997 Actual ENERGY CONSUMPTION VS Adjusted Baseline**

FACILITIES Facility ID and Name	ELECTRICITY (kWh)			NATURAL GAS (m <sup>3</sup> )			WATER (m <sup>3</sup> )			TOTAL (ekWh)		
	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change
AR Africa Restaurant	517,885	529,200	2.2%	82,097	73,153	-10.9%	6,979	5,008	-28.2%	1,366,905	1,285,723	-5.9%
ESB Eurasia Snack Bar	28,586	45,360	58.7%	—	—	—	899	469	-47.8%	28,586	45,360	58.7%
MGSB Main Gate Snack Bar	—	2,800	—	—	—	—	1,152	1,269	10.2%	—	2,800	—
MSB Madagascar Snack Bar	72,275	73,440	1.6%	—	—	—	928	700	-24.6%	72,275	73,440	1.6%
NAR North America Restaurant	290,282	321,200	10.7%	32,612	43,743	34.1%	7,917	7,649	-3.4%	627,548	773,579	23.3%
<b>Total</b>		972,000		116,896			15,095			2,180,902		
<b>Total (excl. energy added after 1995)</b>	909,028	969,200	6.6%	114,709	116,896	1.9%	17,875	15,095	-15.6%	2,095,314	2,178,102	4.0%

**MCDONALD RESTAURANTS**  
**1997 Actual ENERGY COST VS Adjusted Baseline**

FACILITIES Facility ID and Name	ELECTRICITY COST			NATURAL GAS COST			WATER COST			TOTAL COST		
	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change
AR Africa Restaurant	\$37,661	\$37,911	0.7%	\$11,967	\$10,570	-11.7%	\$5,400	\$3,888	-28.0%	\$55,028	\$52,370	-4.8%
ESB Eurasia Snack Bar	\$1,839	\$3,222	75.2%	—	—	—	\$707	\$368	-48.0%	\$2,546	\$3,590	41.0%
MGSB Main Gate Snack Bar	—	\$213	—	—	—	—	\$896	\$987	10.2%	—	\$1,201	—
MSB Madagascar Snack Bar	\$5,049	\$5,169	2.4%	—	—	—	\$721	\$553	-23.3%	\$5,770	\$5,722	-0.8%
NAR North America Restaurant	\$21,021	\$22,863	8.8%	\$4,648	\$6,395	37.6%	\$6,148	\$5,899	-4.0%	\$31,817	\$35,157	10.5%
<b>Total</b>		\$69,379		\$16,965			\$11,695			\$98,039		
<b>Total (excl. energy added after 1995)</b>	\$65,570	\$69,166	5.5%	\$16,615	\$16,965	2.1%	\$13,871	\$11,695	-15.7%	\$95,161	\$96,839	1.8%

NOTE: Adj.Base - The 1995 energy consumption and cost are adjusted to the 1997 billing periods, weather conditions and energy costs.

Actual - The current year (1997) actual energy consumption and cost.

ekWh - Equivalent kilowatt-hour (1 cubic metre of Natural Gas = 10.3417 ekWh).

CITY OF TORONTO  
TORONTO ZOO

**SUBMETERS**  
**1997 Actual ENERGY CONSUMPTION VS Adjusted Baseline**

FACILITIES	ELECTRICITY (kWh)			NATURAL GAS (m <sup>3</sup> )			WATER (m <sup>3</sup> )			TOTAL (ekWh)		
	Adj. Base 1995	Actual 1997	Percent Change	Adj. Base 1995	Actual 1997	Percent Change	Adj. Base 1995	Actual 1997	Percent Change	Adj. Base 1995	Actual 1997	Percent Change
AFP African Pavilion	—	1,225,207	—	434,394	487,994	12.3%	—	—	—	—	6,271,892	—
AFR Africa Rhino / Mixed Hoofstock	—	—	—	—	3,038	—	—	—	—	—	31,418	—
AMP Americas Pavilion	—	519,028	—	112,177	130,520	16.4%	—	—	—	26,898	1,868,824	—
APN Australasian Pavilion Nocturnal	—	—	—	2,601	2,355	-9.5%	—	—	—	—	24,351	-9.5%
AUP Australasian Pavilion	—	395,717	—	122,204	143,968	17.8%	—	—	—	—	1,884,589	—
BBH Baboon House	—	—	—	—	2,029	—	—	—	—	—	20,983	—
CHH Cheetah House	—	—	—	—	1,011	—	—	—	—	—	10,455	—
CL Caracal Lynx	—	—	—	—	2,207	—	—	—	—	—	22,824	—
DR Domain Ride & Garage Bldg	—	—	—	43,209	34,753	-19.6%	—	—	—	446,849	359,400	-19.6%
EH Elephants House	—	—	—	17,159	33,737	96.6%	—	—	—	177,456	348,902	96.6%
FC Family Centre	—	—	—	4,778	4,568	-4.4%	—	—	—	49,410	47,237	-4.4%
GGG Greenhouse Gift Shop	—	—	—	—	16,507	—	—	—	—	—	170,710	—
GH Giraffe House	—	—	—	9,789	10,876	11.1%	—	—	—	101,234	112,473	11.1%
GHG Gorilla Holding	—	—	—	14,984	9,219	-38.5%	—	—	—	154,958	95,340	-38.5%
GKB Groundskeeping Building	—	—	—	52,521	68,884	31.2%	—	813	—	543,151	712,374	31.2%
HPH Hippo House	—	—	—	58,434	74,902	28.2%	—	—	—	604,305	774,610	28.2%
IMP Indo-Malayan Pavilion	—	643,067	—	242,524	253,206	4.4%	—	—	—	695,691	519,293	-25.4%
IRB Indian Rhino Building	—	—	—	67,270	50,214	-25.4%	—	—	—	—	10,910	—
LH Lion House	—	—	—	—	1,055	—	—	—	—	—	81,038	—
LHH Lion House (Hyena)	—	—	—	—	7,836	—	—	—	—	—	110,863	—
MHS Mixed Hoofstock	—	—	—	—	10,720	—	—	—	—	—	185,509	—
MT Mayan Temple	—	—	—	—	17,938	—	—	—	—	—	417,119	1.6%
MW Malaysian Wood (Village Edge)	—	—	—	39,680	40,334	1.6%	—	—	—	410,364	417,119	1.6%
NSB North Services Building	—	—	—	396,110	410,429	6.3%	—	9,330	—	—	4,244,537	—
OAB Old Administrative Building	—	258,174	—	24,578	27,474	11.8%	—	—	—	—	542,298	—
OH Orangutan Holding	—	—	—	15,911	17,874	12.3%	—	—	—	164,551	184,851	12.3%
PBH Polar Bear Holding	—	—	—	—	4,696	—	—	—	—	—	48,565	—
ZSB Zoological Society Building	275,229	279,597	1.6%	7,280	4,912	-32.5%	2,225	1,459	-34.5%	350,516	330,397	-5.7%
Total	3,320,790	3,320,790	—	1,873,253	1,873,253	—	2,225	11,602	—	3,725,384	22,693,406	—
Total (excl. energy added after 1995)	275,229	279,597	1.6%	1,655,603	1,806,216	9.1%	2,225	1,459	-34.5%	3,725,384	3,926,346	5.4%

NOTE: Adj. Base - The 1995 energy consumption and cost are adjusted to the 1997 billing periods, weather conditions and energy costs.  
Actual - The current year (1997) actual energy consumption and cost.  
ekWh - Equivalent kilowatt-hour (1 cubic metre of Natural Gas = 10.3417 ekWh).

CITY OF TORONTO  
TORONTO ZOO

**SUBMETERS**  
**1997 Actual ENERGY COST VS Adjusted Baseline**

FACILITIES	ELECTRICITY COST			NATURAL GAS COST			WATER COST			TOTAL COST		
	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change	Adj.Base 1995	Actual 1997	Percent Change
AFP African Pavilion	---	\$87,411	---	\$64,607	\$72,869	12.8%	---	---	---	---	\$160,280	---
AFR Africa Rhino / Mixed Hoofstock	---	---	---	---	\$439	---	---	---	---	---	\$439	---
AMP Americas Pavilion	---	\$36,876	---	\$16,748	\$19,526	16.6%	---	---	---	---	\$56,401	---
APN Australasian Pavilion Nocturnal	---	---	---	\$390	\$356	-8.6%	---	---	---	\$390	\$356	-8.6%
AUP Australasian Pavilion	---	\$28,071	---	\$18,244	\$21,676	18.8%	---	---	---	---	\$49,747	---
BBH Baboon House	---	---	---	---	\$313	---	---	---	---	---	\$313	---
CHH Cheetah House	---	---	---	---	\$146	---	---	---	---	---	\$146	---
CL Caracal Lynx	---	---	---	---	\$329	---	---	---	---	---	\$329	---
DR Domain Ride & Garage Bldg	---	---	---	\$6,496	\$5,221	-19.6%	---	---	---	\$6,496	\$5,221	-19.6%
EH Elephants House	---	---	---	\$2,552	\$5,057	98.2%	---	---	---	\$2,552	\$5,057	98.2%
FC Family Centre	---	---	---	\$713	\$684	-4.1%	---	---	---	\$713	\$684	-4.1%
GGG Greenhouse Gift Shop	---	---	---	---	\$2,481	---	---	---	---	---	\$2,481	---
GH Giraffe House	---	---	---	\$1,469	\$1,639	11.6%	---	---	---	\$1,469	\$1,639	11.6%
GHG Gorilla Holding	---	---	---	\$2,205	\$1,346	-39.0%	---	---	---	\$2,205	\$1,346	-39.0%
GKB Groundskeeping Building	---	---	---	\$7,882	\$10,297	30.6%	---	\$662	---	\$7,882	\$10,297	30.6%
HPH Hippo House	---	---	---	\$8,740	\$11,246	28.7%	---	---	---	\$8,740	\$11,246	28.7%
IMP Indo-Malayan Pavilion	---	\$45,721	---	\$36,171	\$37,955	4.9%	---	---	---	---	\$83,676	---
IRB Indian Rhino Building	---	---	---	\$10,062	\$7,539	-25.1%	---	---	---	\$10,062	\$7,539	-25.1%
LH Lion House	---	---	---	---	\$155	---	---	---	---	---	\$155	---
LHH Lion House (Hyena)	---	---	---	---	\$1,166	---	---	---	---	---	\$1,166	---
MHS Mixed Hoofstock	---	---	---	---	\$1,594	---	---	---	---	---	\$1,594	---
MT Mayan Temple	---	---	---	---	\$2,669	---	---	---	---	---	\$2,669	---
MW Malayan Wood (Village Edge)	---	---	---	\$5,915	\$6,021	1.8%	---	---	---	\$5,915	\$6,021	1.8%
NSB North Services Building	---	---	---	\$57,653	\$61,302	6.3%	---	\$7,383	---	---	\$61,302	---
OAB Old Administrative Building	---	\$18,448	---	\$3,682	\$4,114	11.7%	---	---	---	---	\$22,563	---
OH Orangutan Holding	---	---	---	\$2,358	\$2,676	13.5%	---	---	---	\$2,358	\$2,676	13.5%
PBH Polar Bear Holding	---	---	---	---	\$707	---	---	---	---	---	\$707	---
ZSB Zoological Society Building	\$19,506	\$19,935	2.2%	\$1,105	\$744	-32.7%	---	\$1,186	-34.5%	\$22,423	\$22,491	0.3%
Total		\$236,462		\$280,269				\$9,231			\$518,543	
Total (excl. energy added after 1995)	\$19,506	\$19,935	2.2%	\$246,993	\$270,269	9.4%	\$1,811	\$1,186	-34.5%	\$71,206	\$74,574	4.7%

NOTE: Adj.Base - The 1995 energy consumption and cost are adjusted to the 1997 billing periods, weather conditions and energy costs.

Actual - The current year (1997) actual energy consumption and cost.

ekWh - Equivalent kilowatt-hour (1 cubic metre of Natural Gas = 10.3417 ekWh).

**II. MULTI-YEAR ENERGY**

**QUARTERLY Energy Consumption**

**ANNUAL Energy Consumption & Cost**

CITY OF TORONTO  
TORONTO ZOO

MULTI-YEAR QUARTERLY ENERGY CONSUMPTION  
(Excluding McDonalds)

ENERGY TYPE		1st QTR	2nd QTR	3rd QTR	4th QTR	TOTAL	Tonnes CO2
<b>1997 ACTUAL CONSUMPTION</b>							
Electricity	kWh	2,690,350	2,109,088	1,929,473	2,470,406	9,199,317	2,451
Natural Gas	m <sup>3</sup>	878,934	332,633	99,944	583,025	1,894,536	4,038
Heating Oil	Litre	6,263	1,186	—	1,780	9,229	29
Gasoline	Litre	10,323	21,799	15,442	12,013	59,577	158
Diesel Oil	Litre	6,195	—	10,976	11,588	28,759	84
Propane	Litre	13,520	14,065	23,846	10,213	61,644	88
Water	m <sup>3</sup>	31,001	71,204	62,328	150,851	315,384	—
<b>Total</b>	<b>ekWh</b>	<b>12,114,729</b>	<b>5,877,212</b>	<b>3,408,673</b>	<b>8,835,589</b>	<b>30,236,204</b>	<b>6,848</b>
<b>Tonnes of CO2</b>		<b>2,674</b>	<b>1,353</b>	<b>834</b>	<b>1,987</b>	<b>6,848</b>	<b>6,848</b>

<b>1996 ACTUAL CONSUMPTION</b>							
Electricity	kWh	3,067,791	2,054,795	1,755,495	2,267,879	9,145,960	2,436
Natural Gas	m <sup>3</sup>	838,667	340,400	81,583	545,239	1,805,889	3,849
Heating Oil	Litre	17,992	4,467	—	4,723	27,182	85
Gasoline	Litre	15,894	15,481	16,869	15,702	63,946	170
Diesel Oil	Litre	6,263	3,922	5,841	4,993	21,019	62
Propane	Litre	16,309	13,028	17,639	10,613	57,589	83
Water	m <sup>3</sup>	45,737	15,462	164,268	70,351	295,818	—
<b>Total</b>	<b>ekWh</b>	<b>12,277,030</b>	<b>5,912,019</b>	<b>2,956,743</b>	<b>8,241,665</b>	<b>29,387,456</b>	<b>6,684</b>
<b>Tonnes of CO2</b>		<b>2,745</b>	<b>1,358</b>	<b>729</b>	<b>1,853</b>	<b>6,684</b>	<b>6,684</b>

<b>1995 ACTUAL CONSUMPTION</b>							
Electricity	kWh	2,780,268	2,103,835	2,004,690	2,394,446	9,283,239	2,473
Natural Gas	m <sup>3</sup>	706,538	325,526	92,599	496,452	1,621,115	3,455
Heating Oil	Litre	15,155	5,943	—	—	21,098	66
Gasoline	Litre	15,502	15,781	15,325	14,819	61,427	163
Diesel Oil	Litre	3,584	6,761	6,132	5,885	22,362	66
Propane	Litre	13,874	12,555	13,980	10,564	50,973	73
Water	m <sup>3</sup>	45,009	122,815	119,911	63,195	350,929	—
<b>Total</b>	<b>ekWh</b>	<b>10,541,764</b>	<b>5,852,858</b>	<b>3,280,598</b>	<b>7,813,654</b>	<b>27,488,875</b>	<b>6,296</b>
<b>Tonnes of CO2</b>		<b>2,365</b>	<b>1,353</b>	<b>810</b>	<b>1,768</b>	<b>6,296</b>	<b>6,296</b>

<b>1994 ACTUAL CONSUMPTION</b>							
Electricity	kWh	2,635,799	1,751,056	1,552,095	2,173,911	8,112,861	2,161
Natural Gas	m <sup>3</sup>	676,728	243,540	87,864	418,476	1,426,608	3,040
Heating Oil	Litre	12,075	5,180	1,126	6,947	25,328	79
Gasoline	Litre	—	22,998	11,000	18,003	52,001	138
Diesel Oil	Litre	—	7,993	—	9,000	16,993	50
Propane	Litre	17,402	19,829	25,001	21,501	83,733	120
Water	m <sup>3</sup>	38,327	59,814	36,391	133,259	267,791	—
<b>Total</b>	<b>ekWh</b>	<b>9,895,054</b>	<b>4,781,337</b>	<b>2,766,781</b>	<b>7,007,689</b>	<b>24,450,862</b>	<b>5,589</b>
<b>Tonnes of CO2</b>		<b>2,207</b>	<b>1,115</b>	<b>669</b>	<b>1,598</b>	<b>5,589</b>	<b>5,589</b>

NOTE: Energy data has not been normalized to billing period nor weather conditions. Water is not included in total energy and CO2.



02-26-1998

FASER ENERGY ACCOUNTING SYSTEM  
CITY OF TORONTO

TORONTO ZOO  
Cost Centre: ZOO FACILITIES  
Energy: ALL ENERGY TYPES  
Program: MULTIYEAR - ACTUAL ENERGY  
Report: COST CENTRE SUMMARY

FACILITY ENERGY TYPE NAME	-----1995-----		-----1996-----		-----1997-----	
	USE	COST	USE	COST	USE	COST
ALL FACILITIES						
ELECTRICITY (KWH )	10,256,879	\$769,549	10,109,360	\$750,680	10,171,317	\$727,829
DEMAND (KW )	20,183		19,143		19,031	
NATURAL GAS (M3 )	1,732,519	\$260,243	1,938,654	\$287,390	2,011,432	\$296,334
HEATING OIL (L )	21,099	\$4,947	27,182	\$7,208	9,228	\$3,058
GASOLINE (L )	61,427	\$31,758	63,946	\$33,060	59,577	\$33,120
DIESEL OIL (L )	22,362	\$9,750	21,018	\$9,164	28,759	\$13,070
PROPANE (L )	50,973	\$15,751	57,589	\$20,924	61,645	\$21,650
WATER (M3 )	368,635	\$274,177	306,823	\$245,629	330,480	\$260,320
TOTAL (EKWH )	29,614,634	\$1,366,175	31,723,864	\$1,354,054	32,417,110	\$1,355,390

NOTE: Energy data has not been normalized to billing period nor weather conditions.

02-26-1998

FASER ENERGY ACCOUNTING SYSTEM  
CITY OF TORONTO

TORONTO ZOO  
Cost Centre: MCDONALDS RESTAURANT  
Energy: ALL ENERGY TYPES  
Program: MULTIYEAR - ACTUAL ENERGY  
Report: COST CENTRE SUMMARY

FACILITY ENERGY TYPE NAME	-----1995-----		-----1996-----		-----1997-----	
	USE	COST	USE	COST	USE	COST
ALL FACILITIES						
ELECTRICITY (KWH )	973,640	\$81,680	963,400	\$78,635	972,000	\$69,379
DEMAND (KW )	3,256		2,952		3,345	
NATURAL GAS (M3 )	111,404	\$16,795	134,331	\$19,703	116,896	\$16,965
WATER (M3 )	17,683	\$13,534	11,102	\$8,691	15,095	\$11,695
TOTAL (EKWH )	2,125,746	\$112,009	2,352,612	\$107,028	2,180,903	\$98,039

NOTE: Energy data has not been normalized to billing period nor weather conditions.

**APPENDIX 5**

**GT WOOD – HIGH VOLTAGE  
MAINTENANCE REPORT  
DATED 1995**





3354 Mavis Rd. Mississauga, Ont. L5C 1T8  
TEL: (905) 272-1696 Fax: (905) 272-1425

February 28, 1995

METRO TORONTO ZOO  
P.O. Box 280,  
West Hill, Ontario,  
M1E 4R5

ATTN: Mr. Dean Evans

**RE: Your PO #12124  
Our Ref #9951**

Dear Sir;

In accordance with your request, we have completed the Inspection and Testing of the substation and associated electrical equipment at the above location.

Please find enclosed our test report for your reference.

Thank you for the favour of this business.

Yours very truly,

G.T. WOOD COMPANY LIMITED

A handwritten signature in black ink, appearing to be 'L.A. Snow', written over a horizontal line.

L.A. Snow  
LAS/jn

Encl.  
RSCL/1





METRO TORONTO ZOO  
WEST HILL  
ATTN: MR. DEAN EVANS

REFERENCE NO.: 9951  
DECEMBER 1994

### GENERAL SHEET

#### MAIN OUTDOOR SUBSTATION - SHEETS #1 - #3

~~The substation fence requires replacement.~~

- The primary switchgear is showing signs of rust. The entire enclosure requires repainting and recaulking.
- The insulation resistance of the lighting arrestors on the entrance pole was found as follows:

Red Phase - 32 Megohms

Yellow Phase - 45 Megohms

Blue Phase - 40 Megohms

The above values show internal deterioration. Replacement units are required.

#### SHEET #1

- The interphase barriers are showing signs of deterioration. Replacements are required.
- Two (2) of three (3) interrupting units are defective. Replacements are required.
- ~~Two (2) potential indicators were found defective. Replacements were supplied and installed.~~

#### SHEET #2

- The arc blades are missing from this switch. New units are required.
- The interphase barriers are showing signs of deterioration. Replacements are required.
- One (1) potential indicator was found defective. A new unit was supplied and installed.
- ~~A new heater was installed.~~

#### SHEET #3

- The interphase barriers are showing signs of deterioration. Replacements are required.
- ~~A new heater was installed.~~

continued



METRO TORONTO ZOO  
YOUR PO #12124  
OUR REF #9951

A B B  
A BROWN OBARAZ -2-

SOCIETY BUILDING

- All equipment was found to be satisfactory.

INDO-MALAYA PAVILION - SHEETS #11 & #12

- The overload devices on both air circuit breakers are leaking fluid. We recommend replacing these liquid filled overload devices with solid state units.
- ✓ The base of the secondary switchboard is rusting. Repainting is required. ?

EURASIA PAVILION - SHEET #18

- The switch handle for this feeder is defective. Replacement is required.

AFRICA PAVILION - SHEETS #30 & #31

- The overload devices on both air circuit breakers are leaking fluid. We recommend replacing these liquid filled overload devices with solid state units.
- A draw-out handle is required for the breakers

NORTH AMERICA PAVILION

- All electrical equipment was found to be satisfactory.

ENT. FACILITIES - SHEET #43

- The interrupter units for this switch require replacement.

VAULT TYPE TRANSFORMERS

- All transformers and vaults were serviced and left in satisfactory condition. The liquid from each transformer was analyzed for 4 part standard test. Please see the attached test report for results.





STANDARD OIL TEST SHEET

CUSTOMER: TORONTO METRO ZOO

REF NO.: 9951

LOCATION: WEST HILL, ONTARIO

\*\*\*\*\*
The following standards are applicable for transformer oil tests.
It is recommended a sample be tested every 12 months.

- DIELECTRIC: (Kilo Volt breakdown A. S. T. M. Standard) For safe and satisfactory operation, this should not be below 25 Kilo Volts.
ACID: Neutralization Number mg. KOH/g. New oil has a Neutralization Number of approximately .03. As this value increases, oxidation and final sludging is progressively indicated.
INTERFACIAL TENSION: (I.F.T. Dynes/CM) New oil has an I.F.T. of 35 - 40 Dynes. This drops very rapidly in early stages of contamination, but serious contamination is not indicated until a value of approximately 14 - 17 dynes is reached.
COLOR: New oil has a colour value of approximately No. 1. A change in colour indicates contamination and has value in final evaluation of oil condition.

TEST RESULTS WERE AS FOLLOWS;

Table with 5 columns: SERIAL NO., NEUT NO., COLOUR, IFT, DIELECTRIC. Rows include Vault #28, #1, #26, #33, #29, #21, #20 with corresponding test results.

//



STANDARD OIL TEST SHEET

CUSTOMER: TORONTO METRO ZOO

REF NO.: 9951

LOCATION: WEST HILL, ONTARIO

\*\*\*\*\*
The following standards are applicable for transformer oil tests.
It is recommended a sample be tested every 12 months.

DIELECTRIC: (Kilo Volt breakdown A. S. T. M. Standard) For safe and satisfactory operation, this should not be below 25 Kilo Volts.

ACID: Neutralization Number mg. KOH/g. New oil has a Neutralization Number of approximately .03. As this value increases, oxidation and final sludging is progressively indicated.

INTERFACIAL TENSION: (I.F.T. Dynes/Cm) New oil has an I.F.T. of 35 - 40 Dynes. This drops very rapidly in early stages of contamination, but serious contamination is not indicated until a value of approximately 14 - 17 dynes is reached.

COLOUR: New oil has a colour value of approximately No. 1. A change in colour indicates contamination and has value in final evaluation of oil condition.

TEST RESULTS WERE AS FOLLOWS;

Table with 5 columns: SERIAL NO., NEUT NO., COLOUR, IFT, DIELECTRIC. Rows include Vault #22, Vault #6, Vault #34, Vault #13, and Vault #13A.

18



STANDARD OIL TEST SHEET

CUSTOMER: TORONTO METRO ZOO

REF NO.: 9951

LOCATION: WEST HILL, ONTARIO

\*\*\*\*\*
The following standards are applicable for transformer oil tests.
It is recommended a sample be tested every 12 months.

- DIELECTRIC: (Kilo Volt breakdown A. S. T. M. Standard) For safe and satisfactory operation, this should not be below 25 Kilo Volts.
ACID: Neutralization Number mg. KOH/g. New oil has a Neutralization Number of approximately .03. As this value increases, oxidation and final sludging is progressively indicated.
INTERFACIAL TENSION: (I.F.T. Dynes/CM) New oil has an I.F.T. of 35 - 40 Dynes. This drops very rapidly in early stages of contamination, but serious contamination is not indicated until a value of approximately 14 - 17 dynes is reached.
COLOUR: New oil has a colour value of approximately No. 1. A change in colour indicates contamination and has value in final evaluation of oil condition.

TEST RESULTS WERE AS FOLLOWS;

Table with 5 columns: SERIAL NO., NEUT NO., COLOUR, IFT, DIELECTRIC. Rows include Vault #12, #35, #11, #8, #10, and N/A vaults with corresponding test results.

Handwritten mark resembling the number 17.



STANDARD OIL TEST SHEET

CUSTOMER: TORONTO METRO ZOO

REF NO.: 9951

LOCATION: WEST HILL, ONTARIO

\*\*\*\*\*
The following standards are applicable for transformer oil tests.

It is recommended a sample be tested every 12 months.

DIELECTRIC: (Kilo Volt breakdown A. S. T. M. Standard) For safe and satisfactory operation, this should not be below 25 Kilo Volts.

ACID: Neutralization Number mg. KOH/g. New oil has a Neutralization Number of approximately .03. As this value increases, oxidation and final sludging is progressively indicated.

INTERFACIAL TENSION: (I.F.T. Dynes/cm) New oil has an I.F.T. of 35 - 40 Dynes. This drops very rapidly in early stages of contamination, but serious contamination is not indicated until a value of approximately 14 - 17 dynes is reached.

COLOUR: New oil has a colour value of approximately No. 1. A change in colour indicates contamination and has value in final evaluation of oil condition.

TEST RESULTS WERE AS FOLLOWS;

Table with 5 columns: SERIAL NO., NEUT NO., COLOUR, IPT, DIELECTRIC. Rows include Vault N/A LG37991, Vault N/A 861965, Vault N/A 861965, Vault N/A #1-861941, #2-861940, #3-861943, and No #.

7

Ref. # 9951

METRO ZOO

1995

SHEET No. 1

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR  
MAIN OUTDOOR SUBSTATION

MAIN INCOMING

Interrupter Switch Specifications: Manuf. SFC ELECTRIC Amps 600

Cat. # 34K2 K.V. 27.6

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #/  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. C.O.B. Type DYNAGAP

Cat. # 46615-5061 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200+ 2. 200+ 3. 200+ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # - K.V. - Amp - Type -

Holders: Cat. # - K.V. - Amp - Type -

Refills: Cat. # - K.V. - Amp - Type -

Resistance Test: 1. - 2. - 3. - microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 2

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

FEEDER TO EURASIA PAVILION

Interrupter Switch Specifications: Manuf. S?C ELECTRIC Amps 600

Cat. # 3456304-72 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE # 2.  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. C.O.B Type DYNAGAP

Cat. # 46615-2061 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>+</sup> 2. 200<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S?C ELECTRIC

Mountings: Cat. # - K.V. - Amp - Type -

Holders: Cat. # 86644R-1 K.V. 34.5 Amp 300 Type SM-5

Refills: Cat. # B34250R4 K.V. 34.5 Amp 150 <sup>ICC</sup>Type 153-4

Resistance Test: 1. 725 2. 790 3. 755 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 3

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

FREDDO TO SERVICE BUILDING

Interrupter Switch Specifications: Manuf. SIC ELECTRIC Amps 600  
Cat. # 34503R4-T2 K.V. 29

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. G.E. Type DYNAGAP  
Cat. # 26644K-1 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200+ 2. 200+ 3. 200+ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. SIC ELECTRIC

Mountings: Cat. # - K.V. - Amp - Type -

Holders: Cat. # 86644R4 K.V. 34.5 Amp 300 Type SM-5

Refills: Cat. # 134250R-4 K.V. 34.5 Amp 150 Type JSC 153.4

Resistance Test: 1. 710 2. 760 3. 760 microhms

The above values are satisfactory.

All associated insulation was intact and thoroughly cleaned.

Contact surfaces were cleaned, conditioned and sealed against oxidation.

A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 4

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

SOCIETY BUILDING

Interrupter Switch Specifications: Manuf. S & C ELECTRIC Amps 600

Cat. # 234533K4-1 K.V. 29

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. O.B. Type LV

Cat. # 217117 K.V. 17 M.C.O.V

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>+</sup> 2. 200<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S & C ELECTRIC

Mountings: Cat. # - K.V. - Amp - Type -

Holders: Cat. # 86644R-2 K.V. 345 Amp 300 Type SM 5

Refills: Cat. # - K.V. 345 Amp 15 Type TCR 153-V

Resistance Test: 1. 2270 2. 2200 3. 2275 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.



TRANSFORMER INSPECTION & TEST SHEET No. 1

SOCIETY BUILDING

Manufacturer CARTE Serial No. NO7090-1

Type ONAN H.V. 27.6/16.0 L.V. 20FY 1120 Taps 4.2 1/2 %

Oil 877 K.V.A. 300

% Impedance 4.58 VECTOR WYE / WYE

Liquid Sample

Serial No.	Neut. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
------------	-----------	--------	--------	------------	---------------

N.T

The above results are satisfactory.

Insulation Resistance Test

Test Voltage D.C.

H.V. to Ground 5/7 megohms 1000

L.V. to Ground 200 megohms

H.V. to L.V. 200 megohms

The above results are satisfactory.

Station Grounding System: 2.50 Ohm

**TRANSFORMER INSPECTION & TEST SHEET No. 2**

**GENERAL CONDITIONS**

Serial No. NO 7090-1

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY  
 SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY  
 SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY  
 SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY  
 SEE GENERAL SHEET. NOTE  
MAXIMUM TEMPERATURE WAS 48 ° C

Cooling System:

- CLEAR  
 SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY  
 SEE GENERAL SHEET. NOTE  
 NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position C for 100% volts

Ref. # 9951

SHEET No. 5

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

INDO-MALAYA PAVILION

Interrupter Switch Specifications: Manuf. SSE ELECTRIC Amps 600  
CELL #1 - FEEDER TO  
ENTRANCE TRANSFORMERS Cat. # 34003 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRIDES Type GP  
Cat. # 46157 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200+ 2. 200+ 3. 200+ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # - K.V. - Amp - Type -

Holder: Cat. # - K.V. - Amp - Type -

Refills: Cat. # - K.V. - Amp - Type -

Resistance Test: 1. - 2. - 3. - microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 6

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

FEEDER TO AFRICA PAVILION.

Interrupter Switch Specifications: Manuf. SEC ELECTRIC Amps 600  
Cat. # 34002 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  
 SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type G.P.  
Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>f</sup> 2. 200<sup>m</sup> 3. 200<sup>l</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 7

**INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR**

FEEDER TO T2

Interrupter Switch Specifications: Manuf. S.E. ELECTRIC Amps 600  
Cat. # 34563R4-T2 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. O.B. Type G.P.  
Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. 200<sup>t</sup> 2. 200<sup>t</sup> 3. 200<sup>t</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. SIC ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 86644R1 K.V. 345 Amp 300E Type SM-5

Refills: Cat. # 134040R4 K.V. 345 Amp 25 Type TCC 153.4

Resistance Test: 1. 1980 2. 1980 3. 19.5 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 8

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

Interrupter Switch Specifications: Manuf. SIC ELECTRIC Amps 600  
PADLOCK FEETLOCK Cat. # 346024-1 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO PIPES Type GI  
Cat. # 46615 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. 1000 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. SIC ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holder: Cat. # 86644E1 K.V. 34.5 Amp 300 Type SM-5

Refills: Cat. # 134125K4 K.V. 34.5 Amp 80 Type 153.4

Resistance Test: 1. \_\_\_\_\_ 2. 1170 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

TRANSFORMER INSPECTION & TEST SHEET No. 1

INDO-MALAYA PAVILLION TRANSFORMER T-2

Manufacturer: WESTINGHOUSE Serial No. 795156

Ratio: 0 LWAN H.V. 27600Y/16000 L.V. 208Y/1120 Taps 4-2 1/2 % ±2

Oil: Liquid 200 K.V.A. 500/560

Impedance: 7.1 VECTOR WYE, WYE CSA

Liquid Sample

Oil No.	Neul. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
---------	-----------	--------	--------	------------	---------------

The above results are satisfactory.

Insulation Resistance Test

Test Voltage D.C.

H.V. to Ground	519	megohms	1000
L.V. to Ground	50	megohms	"
H.V. to L.V.	50	megohms	"

The above results are satisfactory.

Station Grounding System: 1.50 Ohm

# TRANSFORMER INSPECTION & TEST SHEET No. 2

## GENERAL CONDITIONS

Serial No. 795156

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 40 ° C

Cooling System:

- CLEAR
- SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position 3 for 271600 volts



Ref. # 9951

Sheet # 11

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: INDO-MALAYA TRV. - MAIN.

**SPECIFICATION:**

Manufacturer : F.P.E  
 Interrupt. Cap : 50KA  
 Frame Size : 1600 AMP  
 Elect. Operated: NA  
 Manul. Operated: ✓

Serial # : TH-4142-72  
 Volts : 600  
 Type : SOH2  
 Poles : 3  
 Fixed: \_\_\_\_\_ / Draw Out: ✓

**TRIPPING DEVICE:**

Type: P.A.  
 Longtime P/U : 1600 amps  
 Shorttime P/U: 6400 amps  
 Grd Fault P/U: NA amps  
 Instant. P/U : NA amps  
 Fused Rating & Manufacturer: \_\_\_\_\_

Coil/C.T. Rating 1600 amps  
 Delay MIN T/B seconds  
 Delay 15 CYCLE seconds  
 Delay NA seconds

**CONTACT RESISTANCE:**

Phase I 32 Phase II 30 Phase III 32 microhms

**INSULATION RESISTANCE:**

Phase I 200<sup>+</sup> Phase II 200<sup>+</sup> Phase III 200<sup>+</sup> megohms

**GENERAL:**

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition		✓	16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter	✓	
7. Manual Tripping Operation	✓		18. Ammeter	✓	
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators		
11. Breaker Drawout Clusters	✓		22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

\_\_\_\_\_ Moulded Case Breakers  
20 Fused Switches

Ref. # 9951

Sheet # 12

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: INDO-MALAYA PAU - DP-ME

SPECIFICATION:

Manufacturer : F.P.E  
 Interrupt. Cap : 50KA  
 Frame Size : 1600AMP  
 Elect. Operated: —  
 Manul. Operated: ✓

Serial # : TH-4124/72  
 Volts : 600  
 Type : 50H-2  
 Poles : 3  
 Fixed:  / Draw Out: \_\_\_\_\_

TRIPPING DEVICE:

Type: PA  
 Longtime P/U : 1000 amps  
 Shorttime P/U: NA amps  
 Grd Fault P/U: NA amps  
 Instant. P/U : 4000 amps  
 Fused Rating & Manufacturer: \_\_\_\_\_

Coil/C.T. Rating 1000 amps  
 Delay MIN T/B seconds  
 Delay NA seconds  
 Delay NA seconds  
 \_\_\_\_\_ NA

CONTACT RESISTANCE:

Phase I 41 Phase II 42 Phase III 45 microhms

INSULATION RESISTANCE:

Phase I 200<sup>t</sup> Phase II 200<sup>t</sup> Phase III 200<sup>t</sup> megohms

GENERAL:

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition		✓	16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter		
7. Manual Tripping Operation	✓		18. Ammeter		
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts			21. Single Phase Indicators		
11. Breaker Drawout Clusters			22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

- \_\_\_\_\_ Moulded Case Breakers
- \_\_\_\_\_ Fused Switches

Ref. # 9951

SHEET No. 13

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

SERVICE BUILDING,

Interrupter Switch Specifications: Manuf. 330 ELECTRIC Amps 600

FEDER TO MAIN OUTDOOR SWITCHGEAR Cat. # 34063 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type G.P.  
Cat. # 466159 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>+</sup> 2. 200<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA.

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holder: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 14

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

SERVICE BLDG  
Interrupter Switch Specifications: Manuf. SIC ELECTRIC Amps 600  
PADDOCK FELLER WEST Cat. # 34563.R4-75 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type G.F.  
Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. 200<sup>1</sup> 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. SIC ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holder: Cat. # 80044K1 K.V. 34.5 Amp 300 Type SM5

Refills: Cat. # 124125.R4 K.V. 54 Amp 200 Type 1/2" d

Resistance Test: 1. \_\_\_\_\_ 2. 1160 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9151

SHEET No. 15

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

SERVICE BUILDING  
Interrupter Switch Specifications: Manuf. S.E. ELECTRIC Amps 600  
PADLOCK FEEDER BUS  
Cat. # 34303L4-T5 K.V. 29

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. CHIC PAISON Type GI  
Cat. # 43119 K.V. 20

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. 200<sup>+</sup> 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S.E. ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 26644R1 K.V. 20 Amp 200 Type TYPE

Refills: Cat. # 124125L4 K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. 963 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 16

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

Service Building  
Interrupter Switch Specifications: Manuf. SEC ELECTRIC Amps 600  
F007 10/10/83  
Cat. # 24062 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. CHIO BRASS Type G1  
Cat. # 46159 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. 200<sup>+</sup> 2. 200<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. SEC ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 8640K1 K.V. 34.5 Amp 300 Type same

Refills: Cat. # 13400KV K.V. 34.5 Amp 65 Type 7cc 155-1

Resistance Test: 1. 1170 2. 1185 3. 1180 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 17

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

EURASIA DIVISION

Interrupter Switch Specifications: Manuf. SIEMENS Amps 600

Cat. # 3AH1-100 K.V. 25

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type GP

Cat. # 40109 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200+ 2. 200+ 3. 200+ megohms

The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.

All associated insulation was intact and thoroughly cleaned.

Contact surfaces were cleaned, conditioned and sealed against oxidation.

A spare set of refills should be stored in a convenient location at all times.

Ref. # 947

SHEET No. 18

### INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

*EUCALPTA TRAIL*  
 Interrupter Switch Specifications: Manuf. SACELECTRIC Amps 600  
*14110 11/20/83*  
 Cat. # 34563-75 K.V. 27  
 4 SOUTH

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary. *SEE GENERAL*

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  
 SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO PAPER Type G1  
 Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. \_\_\_\_\_ 2. 200+ 3. 200+ megohms  
 The above values are satisfactory.

Fuse Specifications Manuf. SACELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 86644/1 K.V. 24 Amp 300 Type SMF

Refills: Cat. # 134125 K11 K.V. 24 Amp 200 Type 100

Resistance Test: 1. \_\_\_\_\_ 2. 1000 3. 1200 microhms

The above values are satisfactory.  
 All associated insulation was intact and thoroughly cleaned.  
 Contact surfaces were cleaned, conditioned and sealed against oxidation.  
 A spare set of refills should be stored in a convenient location at all times.



Ref. # 9951

SHEET No. 19

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

*EURASIA TRAVILION*  
Interrupter Switch Specifications: Manuf. SEE GENERAL SHEET Amps 600  
*FEEDER TO OUTSIDE SUR.* Cat. # 3401-43 K.V. 29

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type GP.  
Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. 200<sup>+</sup> 2. 500<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA  
Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 20

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

*EURASIA 140*  
Interrupter Switch Specifications: Manuf. S&C ELECTRIC Amps 600  
*TEST TO TEST*  
Cat. # 3456314-72 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. NA Type \_\_\_\_\_  
Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S&C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 8161021 K.V. 34.5 Amp 300 Type SM-5

Refills: Cat. # 12475KV K.V. 34.5 Amp 15 Type 152-4

Resistance Test: 1. 2200 2. 2200 3. 2170 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

### TRANSFORMER INSPECTION & TEST SHEET No. 1

WASIA PAVILION TRANSFORMER-1

Manufacturer: WESTINGHOUSE Serial No. 249380

Oil: LIAN H.V. 27600/11000 L.V. 208Y 1120 Taps 4-2 1/2% 12

Oil Liquid: 200 K.V.A. 500/500

Impedance: 5.9 VECTOR WYE / WYE CSA

#### Oil Sample

Oil No.	Neut. No.	Colour	I.F.T.	Dielectric	Spec. Gravity

The above results are satisfactory.

#### Insulation Resistance Test

Test Voltage D.C.

H.V. to Ground	<u>5/3</u> megohms	<u>100</u>
L.V. to Ground	<u>60</u> megohms	"
H.V. to L.V.	<u>60</u> megohms	"

The above results are satisfactory.

Station Grounding System: 2.50 Ohm

TRANSFORMER INSPECTION & TEST SHEET No. 2

GENERAL CONDITIONS

Serial No. 849380

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 28 ° C

Cooling System:

- CLEAR
- SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position 3 for 27000 volts

Ref. # 9951

Sheet # 23

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: EUKASIA DIVISION

**IDENTIFICATION:**

Manufacturer : V.T.E.  
 Interrupt. Cap : 50KA  
 Frame Size : 1600 AMP  
 Elect. Operated: —  
 Manul. Operated: ✓

Serial # : 98013  
 Volts : (600 / 208 / 120)  
 Type : K-1600  
 Poles : 3  
 Fixed: \_\_\_\_\_ / Draw Out: ✓

**TRIPPING DEVICE:**

Type: over  
 Longtime P/U : 800 amps  
 Shorttime P/U: 3200 amps  
 Grd Fault P/U: 4A amps  
 Instant. P/U : 4A amps  
 Fused Rating & Manufacturer: NA

Coil/C.T. Rating 800 amps  
 Delay MIN 1/A seconds  
 Delay MIN 1/B seconds  
 Delay — seconds

**CONTACT RESISTANCE:**

Phase I 20 Phase II 20 Phase III 20 microhms

**INSULATION RESISTANCE:**

Phase I 1000 Phase II 1000 Phase III 1000 megohms

**GENERAL:**

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition	✓		16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter	✓	
7. Manual Tripping Operation	✓		18. Ammeter	✓	
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators		
11. Breaker Drawout Clusters	✓		22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

- \_\_\_\_\_ Moulded Case Breakers
- 2 Fused Switches

Ref. # 9951

SHEET No. 24

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

AFRICA PAVILION

Interrupter Switch Specifications: Manuf. S.I. ELECTRIC Amps 600

TRANSFORMER T-6

Cat. # 3456244-T2 K.V. 22

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. NA Type -  
Cat. # - K.V. -

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S.I. ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 2004461 K.V. 22 Amp 300 Type SP-5

Refills: Cat. # 1240004 K.V. 22 Amp 40 Type SP-5

Resistance Test: 1. 1010 2. 1025 3. 1025 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 25

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

AFRICA DIVISION

Interrupter Switch Specifications: Manuf. SIEMENS Amps 600

FEEDER TO NORTH DIVISION

Cat. # 34013 K.V. 29

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type DYNA-GAR

Cat. # 46615-2061 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>1</sup> 2. 200<sup>1</sup> 3. 200<sup>1</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 26

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

ARRIVE TRAILION  
Interrupter Switch Specifications: Manuf. SIEMENS Amps 600  
FEEDER TO INDO-MALAYA TRV  
Cat. # 4002 K.V. 22

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. Ohio Electric Type Dynaf-GAF  
Cat. # 4005 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>+</sup> 2. 200<sup>+</sup> 3. 200<sup>+</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. NA

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.



Ref. # 9951

SHEET No. 27

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

AFRICA PAVILION

Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600

PADLOCK - FEEDER

Cat. # 34563477 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. \_\_\_\_\_ Type \_\_\_\_\_

Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S/C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 82640E1 K.V. 34.5 Amp 300 Type SM-5

Refills: Cat. # 13412-R1 K.V. 24 Amp 75 Type TRC 153-V

Resistance Test: 1. \_\_\_\_\_ 2. 1200 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

# TRANSFORMER INSPECTION & TEST SHEET No. 1

Location EXHIBIT PAVILION Transformer T-6  
 Manufacturer WESTINGHOUSE Serial No. 790150  
 No. 1-NAN H.V. 27500Y/11000 L.V. 208-110 Taps 4-3 1/2  
 Oil Liquid 350 K.V.A. 750/1000  
 Impedance 6.0 VECTOR WYE / WYE ISA

### Oil Sample

Oil No.	Neut. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
---------	-----------	--------	--------	------------	---------------

The above results are satisfactory.

### Insulation Resistance Test

Test	Resistance (megohms)	Test Voltage D.C.
H.V. to Ground	<u>519</u>	<u>1000</u>
L.V. to Ground	<u>100</u>	<u>"</u>
H.V. to L.V.	<u>100</u>	<u>"</u>

The above results are satisfactory.

Station Grounding System: 4.50 Ohm

**TRANSFORMER INSPECTION & TEST SHEET No. 2**

**GENERAL CONDITIONS**

Serial No. 795154

**Bushings:**

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

**Gaskets:**

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

**Paint:**

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

**Liquid Level:**

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

**Thermometer:**

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 65 ° C

**Cooling System:**

- CLEAR
- SEE GENERAL SHEET. NOTE

**Gas Detector Relay:**

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

**Terminal Board  
and/or Tap Switch:**

located in position 3 for 27600 volts

Ref. # 9951

Sheet # 30

LOW VOLTAGE BREAKER / / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: AFRICA VAVILION - MAIN

SPECIFICATION:

Manufacturer :	<u>F.P.F.</u>	Serial # :	<u>TH 4126-7?</u>
Interrupt. Cap :	<u>7500</u>	Volts :	<u>600 (120/208)</u>
Frame Size :	<u>2000 AMP</u>	Type :	<u>7500</u>
Elect. Operated:	<u>✓</u>	Poles :	<u>3</u>
Manul. Operated:	<u>✓</u>	Fixed: _____ / Draw Out: <u>✓</u>	

TRIPPING DEVICE:

Type: <u>PA</u>	Coil/C.T. Rating <u>2000</u> amps
Longtime P/U : <u>2000</u> amps	Delay <u>10.7/16</u> seconds
Shorttime P/U: <u>8000</u> amps	Delay <u>15 cycle</u> seconds
Grd Fault P/U: <u>-</u> amps	Delay <u>-</u> seconds
Instant. P/U : <u>-</u> amps	
Fused Rating & Manufacturer: _____	

CONTACT RESISTANCE:

Phase I 29 Phase II 30 Phase III 27 microhms

INSULATION RESISTANCE:

Phase I 200 Phase II 200 Phase III 200 megohms

GENERAL:

O.K. | NOTE#

O.K. | NOTE#

1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition		✓	16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter	✓	
7. Manual Tripping Operation	✓		18. Ammeter	✓	
8. Electrical Closing Operation	✓		19. Arc Chute Condition	✓	
9. Electrical Tripping Operation	✓		20. Barrier Condition	✓	
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators		
11. Breaker Drawout Clusters	✓		22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

\_\_\_\_\_ Moulded Case Breakers  
 \_\_\_\_\_ Fused Switches

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: ARKICIA PAULION - MCC-A1

IDENTIFICATION:

Manufacturer : F.P.E.  
 Interrupt. Cap : 50kA  
 Frame Size : 1600 AMP  
 Elect. Operated: -  
 Manul. Operated: ✓

Serial # : TH 4125-92  
 Volts : 600  
 Type : FDH-2  
 Poles : 3  
 Fixed:  / Draw Out: \_\_\_\_\_

TRIPPING DEVICE:

Type: PA  
 Longtime P/U : 1000 amps  
 Shorttime P/U: - amps  
 Grd Fault P/U: - amps  
 Instant. P/U : 4000 amps  
 Fused Rating & Manufacturer: \_\_\_\_\_

Coil/C.T. Rating 1000 amps  
 Delay MIN T/R seconds  
 Delay - seconds  
 Delay - seconds  
NA

CONTACT RESISTANCE:

Phase I 35 Phase II 42 Phase III 45 microhms

ISOLATION RESISTANCE:

Phase I 200 Phase II 200 Phase III 200 megohms

GENERAL:

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition		✓	16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter		
7. Manual Tripping Operation	✓		18. Ammeter		
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts			21. Single Phase Indicators		
11. Breaker Drawout Clusters			22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

21 Moulded Case Breakers

Fused Switches

Ref. # 9901

SHEET No. 32

### INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

NORTH AMERICA TRAILLION  
 Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600  
 FEEDER TO AREA 11110 Cat. # 3461-43 K.V. 27

Insulation: Intact and thoroughly cleaned.  
 Alignment & Mechanism: Operated normally. Lubricated where necessary.  
 Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRASS Type S.P  
 Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.  
 Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>T</sup> 2. 200<sup>T</sup> 3. 200<sup>T</sup> megohms  
 The above values are satisfactory.

Fuse Specifications Manuf. \_\_\_\_\_

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
 All associated insulation was intact and thoroughly cleaned.  
 Contact surfaces were cleaned, conditioned and sealed against oxidation.  
 A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 33

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

North America Inv.  
Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600  
TRANSFORMER T-5  
Cat. # 3456324-72 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. NA Type \_\_\_\_\_  
Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S/C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holder: Cat. # 8664421 K.V. 34.5 Amp 300 Type SM 5

Refills: Cat. # 13402524 K.V. 34.5 Amp 15 Type TCC 152.4

Resistance Test: 1. 2280 2. 2287 3. 2300 microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 1951

SHEET No. 34

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

NORTH AMERICA PAVILION  
Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600  
FEEDER TO SERVICE BLDG. Cat. # 210000 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. CELCO Type SP  
Cat. # 46-109 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. 200+ 2. 200.1 3. 200+ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. \_\_\_\_\_  
Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_  
Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.



Ref. # 1-1-1

SHEET No. 35

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

North American Insulation  
Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600  
PADDOCK ELECTRIC Cat. # 34563R4-T2 K.V. 29

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO Type GP  
Cat. # 46159 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. \_\_\_\_\_ 2. 200 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. \_\_\_\_\_

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

HOLDERS: Cat. # 8664421 K.V. 34.5 Amp 300 Type JNS

Refills: Cat. # 26412514 K.V. 34.5 Amp 20 Type TCC 119-4

Resistance Test: 1. \_\_\_\_\_ 2. 1100 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

# TRANSFORMER INSPECTION & TEST SHEET No. 1

Name North Hill Hill  
 Manufacturer WESTINGHOUSE Serial No. \_\_\_\_\_  
 No. LNAN H.V. 27600Y/16000 L.V. 20871/120 Taps 4-2 1/2 %  
 Liquid 200 K.V.A. 500/500  
 Impedance 7.1 VECTOR WYE / WYE

### Oil Sample

Oil No.	Neul. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
---------	-----------	--------	--------	------------	---------------

The above results are satisfactory.

### Insulation Resistance Test

Test	Resistance (megohms)	Test Voltage D.C.
H.V. to Ground	<u>5.9</u>	<u>1000</u>
L.V. to Ground	<u>100</u>	"
H.V. to L.V.	<u>100</u>	"

The above results are satisfactory.

Station Grounding System: 2.50 Ohm

TRANSFORMER INSPECTION & TEST SHEET No. 2

GENERAL CONDITIONS

Serial No. ....

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 52 ° C

Cooling System:

- CLEAR
- SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position 3 for 22000 volts

ef. # 4951

Sheet # 38

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: NORTH AMERICA PAV. MAIN

PECIFICATION:

Manufacturer	: <u>ITE</u>	Serial #	: <u>78012</u>
Interrupt. Cap	: <u>50KA</u>	Volts	: <u>600-120/208?</u>
Frame Size	: <u>1600 AMP</u>	Type	: <u>K-1000</u>
Elect. Operated:	<u>-</u>	Poles	: <u>3</u>
Manul. Operated:	<u>✓</u>	Fixed:	<u>1 Draw Out: ✓</u>

TRIPPING DEVICE:

Type:	<u>MD-4</u>	Coil/C.T. Rating	<u>1200</u> amps
Longtime P/U:	<u>1100</u> amps	Delay	<u>MIN 1/5</u> seconds
Shorttime P/U:	<u>4000</u> amps	Delay	<u>MIN 1/5</u> seconds
Grd Fault P/U:	<u>-</u> amps	Delay	<u>-</u> seconds
Instant. P/U:	<u>-</u> amps		
Fused Rating & Manufacturer:	<u>-</u>		

CONTACT RESISTANCE:

Phase I 82 Phase II 30 Phase III 80 microhms

INSULATION RESISTANCE:

Phase I 700 Phase II 700 Phase III 200 megohms

GENERAL:

GENERAL:	O.K.	NOTE#	O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓
2. Arcing Contacts	✓		13. Breaker Cleaned	✓
3. Main Contacts	✓		14. Enclosure Cleaned	✓
4. Exterior Breaker Condition	✓		15. Bus Connections	✓
5. Tripping Device Condition	✓		16. Cable Connections	✓
6. Manual Closing Operation	✓		17. Voltmeter	✓
7. Manual Tripping Operation	✓		18. Ammeter	✓
8. Electrical Closing Operation			19. Arc Chute Condition	✓
9. Electrical Tripping Operation			20. Barrier Condition	✓
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators	
11. Breaker Drawout Clusters	✓		22. Others	

The secondary equipment was serviced and left in satisfactory condition and consisted of

\_\_\_\_\_ Moulded Case Breakers  
 \_\_\_\_\_ Fused Switches

Ref. # 99E1

SHEET No.39

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

ENT. FACILITIES

Interrupter Switch Specifications: Manuf. 5/0211057010 Amps 600

Feeder To IND. MALYA PAV. Cat. # 34102 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO BRUNES Type GIP  
Cat. # 46197 K.V. 24

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. 200<sup>t</sup> 2. 500<sup>t</sup> 3. 200<sup>t</sup> megohms  
The above values are satisfactory.

Fuse Specifications Manuf. \_\_\_\_\_

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 40

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

ENT. FACILITIES:  
Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600  
FEEDER TO VILLAGE EDGE SOUTH  
Cat. # 3456224-77 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.  
Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO D. & S. Type SI  
Cat. # 4019 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. \_\_\_\_\_ 2. 200<sup>+</sup> 3. \_\_\_\_\_ megohms  
The above values are satisfactory.

Fuse Specifications Manuf. S/C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 86641R1 K.V. 24.5 Amp 100 Type AMS

Refills: Cat. # 124125-RV K.V. 24.5 Amp 20 Type 153-4

Resistance Test: 1. \_\_\_\_\_ 2. 1170 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.

Ref. # 9951

SHEET No. 41

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

ENT. FACILITIES

Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600

TRANSFORMER T-8

Cat. # 3456304-72 K.V. 27

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. S/C Type \_\_\_\_\_  
 Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms  
 The above values are satisfactory.

Fuse Specifications Manuf. S/C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 8004481 K.V. 24.5 Amp 300 Type SM 5

Refills: Cat. # 1340404 K.V. 24.5 Amp 25 Type 153-4

Resistance Test: 1. 1900 2. 1910 3. 1900 microhms

The above values are satisfactory.  
 All associated insulation was intact and thoroughly cleaned.  
 Contact surfaces were cleaned, conditioned and sealed against oxidation.  
 A spare set of refills should be stored in a convenient location at all times.

Ref. # 9931

SHEET No. 42

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

EST FACILITY:

Interrupter Switch Specifications: Manuf. 3/c EVERETT Amps 100

FEEDER TO LUGANSA PAV Cat. # 3915661 K.V. 27

Insulation: Intact and thoroughly cleaned.  
Alignment & Mechanism: Operated normally. Lubricated where necessary.  
Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. OHIO STATE Type GI  
Cat. # 41119 K.V. 24

Insulation: Intact and thoroughly cleaned.  
Cementing: Free from deterioration.  
Insulation Resistance Test: 1. 300 2. 300 3. 300 megohms  
The above values are satisfactory.

Fuse Specifications Manuf. \_\_\_\_\_

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Refills: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ microhms

The above values are satisfactory.  
All associated insulation was intact and thoroughly cleaned.  
Contact surfaces were cleaned, conditioned and sealed against oxidation.  
A spare set of refills should be stored in a convenient location at all times.



Ref. # 9951

SHEET No. 43

INSPECTION & TEST REPORT FOR SERVICE ENTRANCE POLE & METALCLAD SWITCHGEAR

ENT FACILITIES.

Interrupter Switch Specifications: Manuf. S/C ELECTRIC Amps 600

TRANSFORMER T-7

Cat. # 24624-73 K.V. 07

Insulation: Intact and thoroughly cleaned.

Alignment & Mechanism: Operated normally. Lubricated where necessary.

Contacts: Cleaned, conditioned and sealed against oxidation.

Interrupting Units:  SATISFACTORY  
 SEE GENERAL SHEET. NOTE #  
 NOT APPLICABLE

Lightning Arrester Specification Manuf. \_\_\_\_\_ Type \_\_\_\_\_

Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_

Insulation: Intact and thoroughly cleaned.

Cementing: Free from deterioration.

Insulation Resistance Test: 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_ megohms

The above values are satisfactory.

Fuse Specifications Manuf. S/C ELECTRIC

Mountings: Cat. # \_\_\_\_\_ K.V. \_\_\_\_\_ Amp \_\_\_\_\_ Type \_\_\_\_\_

Holders: Cat. # 8664421 K.V. 24.5 Amp 300 Type SM-5

Refills: Cat. # 1342514 K.V. 24.5 Amp 15 Type 153.4

Resistance Test: 1. 2180 2. 219.5 3. 2220 microhms

The above values are satisfactory.

All associated insulation was intact and thoroughly cleaned.

Contact surfaces were cleaned, conditioned and sealed against oxidation.

A spare set of refills should be stored in a convenient location at all times.

# TRANSFORMER INSPECTION & TEST SHEET No. 1

ENT: FACILITIES T-7

Manufacturer WESTING HOUSE Serial No. 827694

to L.N.N H.V. 29600 / 16000 L.V. 2087 / 126 Taps 4-2 1/2 /

Oil Liquid ISO K.V.A. 225 / 250

Impedance 1.9 VECTOR WYE / WYE

### Liquid Sample

Oil No.	Neut. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
---------	-----------	--------	--------	------------	---------------

The above results are satisfactory.

### Insulation Resistance Test

Test Voltage D.C.

H.V. to Ground	<u>5/9</u> megohms	<u>1000</u>
L.V. to Ground	<u>55</u> megohms	"
H.V. to L.V.	<u>55</u> megohms	"

The above results are satisfactory.

Station Grounding System: 2.50 Ohm

TRANSFORMER INSPECTION & TEST SHEET No. 2

GENERAL CONDITIONS

Serial No. 827694

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 32 ° C

Cooling System:

- CLEAR
- SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position 3 for 27600 volts

# TRANSFORMER INSPECTION & TEST SHEET No. 1

ENT. FACILITIES T-8

Manufacturer WESTING HOUSE Serial No. 750412

Model LWAW H.V. 27600 Y / 16000 L.V. 600 Y 1347 Taps 4-2 1/2

Oil Liquid 310 K.V.A. 500/560

Impedance 6.7 VECTOR wye / wye

## Liquid Sample

Oil No.	Neut. No.	Colour	I.F.T.	Dielectric	Spec. Gravity
---------	-----------	--------	--------	------------	---------------

The above results are satisfactory.

## Insulation Resistance Test

Test Voltage D.C.

H.V. to Ground 5/9 megohms 1000

L.V. to Ground 65 megohms

H.V. to L.V. 65 megohms

The above results are satisfactory.

Station Grounding System: 2.50 Ohm

TRANSFORMER INSPECTION & TEST SHEET No. 2

GENERAL CONDITIONS

Serial No. 850912

Bushings:

Insulation was intact and thoroughly cleaned.  
Cementing was free from deterioration.

Gaskets:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Paint:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Liquid Level:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE

Thermometer:

- SATISFACTORY
  - SEE GENERAL SHEET. NOTE
- MAXIMUM TEMPERATURE WAS 45 ° C

Cooling System:

- CLEAR
- SEE GENERAL SHEET. NOTE

Gas Detector Relay:

- SATISFACTORY
- SEE GENERAL SHEET. NOTE
- NOT APPLICABLE

Terminal Board  
and/or Tap Switch:

located in position 3 for 27600 volts

Ref. # 9951

Sheet # 48

LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: ENT. FACILITIES - MAIN T.F

**SPECIFICATION:**

Manufacturer : WESTINGHOUSE  
 Interrupt. Cap : 50KA  
 Frame Size : 1600 AMP  
 Elect. Operated: -  
 Manul. Operated: ✓

Serial # : CP21379-02-A1  
 Volts : 600  
 Type : DB-50  
 Poles : 3  
 Fixed: \_\_\_\_\_ / Draw Out: ✓

**TRIPPING DEVICE:**

Type: DB  
 Longtime P/U : 640 amps  
 Shorttime P/U: 4000 amps  
 Grd Fault P/U: - amps  
 Instant. P/U : - amps  
 Fused Rating & Manufacturer: \_\_\_\_\_

Coil/C.T. Rating 1000 amp s  
 Delay 20 seconds  
 Delay 30 CYCLE seconds  
 Delay - seconds

**CONTACT RESISTANCE:**

Phase I 39 Phase II 42 Phase III 40 microhms

**INSULATION RESISTANCE:**

Phase I 200 Phase II 200 Phase III 200 megohms

**GENERAL:**

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition	✓		16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter	✓	
7. Manual Tripping Operation	✓		18. Ammeter	✓	
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators		
11. Breaker Drawout Clusters	✓		22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

\_\_\_\_\_ Moulded Case Breakers

6 Fused Switches

# 9951 LOW VOLTAGE BREAKER  / DISCONNECT DEVICE \_\_\_\_\_ & ENCLOSURES

Designation: ENT. FACILITIES T-8

IDENTIFICATION:

Manufacturer : WESTING HOUSE  
 Interrupt. Cap : 25KA  
 Frame Size : 600 A  
 Elect. Operated: —  
 Manul. Operated: ✓

Serial # : CP21379-01-A1  
 Volts : 600  
 Type : DR-25  
 Poles : 3  
 Fixed: \_\_\_\_\_ / Draw Out: ✓

TRIPPING DEVICE:

Type: DR  
 Longtime P/U : 600 amps  
 Shorttime P/U: 3000 amps  
 Grd Fault P/U: — amps  
 Instant. P/U : — amps  
 Fused Rating & Manufacturer: \_\_\_\_\_

Coil/C.T. Rating 600 amps  
 Delay 20 seconds  
 Delay 6 cycle seconds  
 Delay — seconds

CONTACT RESISTANCE:

Phase I 45 Phase II 51 Phase III 45 microhms

INSULATION RESISTANCE:

Phase I 200 Phase II 200 Phase III 200 megohms

GENERAL:

	O.K.	NOTE#		O.K.	NOTE#
1. Exterior Enclosure Condition	✓		12. Lubricated	✓	
2. Arcing Contacts	✓		13. Breaker Cleaned	✓	
3. Main Contacts	✓		14. Enclosure Cleaned	✓	
4. Exterior Breaker Condition	✓		15. Bus Connections	✓	
5. Tripping Device Condition	✓		16. Cable Connections	✓	
6. Manual Closing Operation	✓		17. Voltmeter	✓	
7. Manual Tripping Operation	✓		18. Ammeter	✓	
8. Electrical Closing Operation			19. Arc Chute Condition	✓	
9. Electrical Tripping Operation			20. Barrier Condition	✓	
10. Secondary Auxillary Contacts	✓		21. Single Phase Indicators		
Breaker Drawout Clusters	✓		22. Others		

The secondary equipment was serviced and left in satisfactory condition and consisted of

- \_\_\_\_\_ Moulded Case Breakers
- \_\_\_\_\_ Fused Switches



3354 Mavis Rd. Mississauga, Ont. L5C 1T8  
TEL: (905) 272-1696 Fax: (905) 272-1425

February 28, 1995

METRO TORONTO ZOO  
P.O. Box 280,  
West Hill, Ontario,  
M1E 4R5

ATTN: Mr. Dean Evans

**RE: Your PO #12124  
Our Ref #9951**

Dear Sir;

In accordance with your request, we have completed the Inspection and Testing of the substation and associated electrical equipment at the above location.

Please find enclosed our test report for your reference.

Thank you for the favour of this business.

Yours very truly,

G.T. WOOD COMPANY LIMITED

A handwritten signature in black ink, appearing to be 'L.A. Snow', written over a horizontal line.

L.A. Snow  
LAS/jn

Encl.  
RSCL/1



**APPENDIX 6**


**LIST OF GAS-FIRED EQUIPMENT**



**APPENDIX 7**

**FIRE HYDRANT TEST RESULTS**





# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

①

CUSTOMER NAME: Toronto Metro 200 HYDRANT LOCATION: West of Indian Point  
 SERVICE ADDRESS: 361A Old Finch Ave HYDRANT MAKE: M167  
Scarborough DATE: Dec 21 1998

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE  LOCATED  NOT VISIBLE  CLOSED  OPERABLE  INOPERABLE

2. HYDRANT OPERATION  OK  DIFFICULT  LEAKING   OK  INOPERABLE

3. CHECK BARREL FOR WATER  WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS  OK  REPLACED

5. CHECK NOZZLES & THREADS  OK  LEAKING   R/B  LOOSE   LEADED  DAMAGED

6. LUBRICATE HYDRANT  YES  NOT REQUIRED

7. LUBE SCREW  OK  MISSING  REPLACED

8. FLOW TEST 30 PITOT 109 USGPM

9. PRESSURE TEST @ 100 PSIG  PASSED  FAILED

10. COLOUR CODED  YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED  YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT  YES  NO

13. GROUND FLANGE  SAFETY  SOLID  BURIED  NA  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE  YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION  OK  IMPROPER

17. TRAFFIC BOLLARDS  OK  DAMAGED  NA


SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_

### ADDITIONAL WORK

18. BONNET COVER	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
19. BONNET BOLTS	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
20. BONNET	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
21. BONNET SEAL	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
22. OPERATING NUT	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
23. OPERATING NUT O-RING(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPACK
24. STUFFING BOX	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
25. THRUST BEARING	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
26. BEARING HOUSING	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
27. BEARING HOUSING BOLTS	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
28. HOUSING COVER	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
29. HOUSING COVER BOLTS	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
30. BEARING HOUSING SEAL(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
31. UPPER OPERATING ROD	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
32. LOWER OPERATING ROD	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
33. ROD COUPLING	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
34. COUPLING BOLTS	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
35. LOWER ROD NUT(S)	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
36. LOWER ROD STOP PIN/PLATE	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
37. VALVE BALL SEAL(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
38. VALVE BALL BOTTOM	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
39. VALVE BALL RUBBER	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
40. VALVE BALL TOP	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
41. MAIN VALVE BEAT	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
42. MAIN VALVE BEAT SEAL(S)	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
43. DRAIN VALVE	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
44. DRAIN VALVE SEAL(S)	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
45. DRAIN VALVE PORT(S)	<input type="checkbox"/> OK	<input type="checkbox"/> CLEARED	<input type="checkbox"/> REPLACED
46. DRAIN VALVE COTTER PIN(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
47. LOWER BARREL	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
48. LOWER BARREL FLANGE(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
49. UPPER BARREL	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
50. UPPER BARREL FLANGE(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
51. BARREL EXTENTION(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
52. FLANGE GASKET(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
53. FLANGE BOLTS	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
54. BOOT	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
55. NOZZLE(S)	<input type="checkbox"/> OK	<input type="checkbox"/> RECALKED	<input type="checkbox"/> REPLACED
56. NOZZLE CAP(S)	<input type="checkbox"/> OK		<input type="checkbox"/> REPLACED
57. NOZZLE RETAINER(S)	<input type="checkbox"/> OK	<input type="checkbox"/> N/A	<input type="checkbox"/> REPLACED
58. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>
59. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>
60. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>
61. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>
62. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>
63. OTHER	<input type="checkbox"/> OK		<input type="checkbox"/>



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

2

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3614 Old Finch Ave  
Scarborough

HYDRANT LOCATION: South of Indo Pavilion  
HYDRANT MAKE: B5013  
DATE: Dec 2/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)


## ADDITIONAL WORK

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	CLOSED <input type="checkbox"/>
			INOPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OPR <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	
	OL <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER		
	DRY <input checked="" type="checkbox"/>			
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>	
	LEAKING <input type="checkbox"/>	LEADED <input checked="" type="checkbox"/>	DAMAGED <input type="checkbox"/>	
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
8. FLOW TEST	<u>36</u> FITOT	<u>1116</u>	USGPM	
9. PRESSURE TEST	<u>100</u> PSIG	PASSED <input type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR		
	NO <input checked="" type="checkbox"/>			
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR		
	NO <input checked="" type="checkbox"/>			
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>		NO <input type="checkbox"/>	
	N/A <input type="checkbox"/>			
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURNED <input type="checkbox"/>	LEAKING <input type="checkbox"/>	
	SOLID <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	
14. REQUIRES BARREL EXTENSION			N/A <input type="checkbox"/>	
15. PUMPER NOZZLE	YES <input type="checkbox"/>		TYPE	
	NO <input checked="" type="checkbox"/>			
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>	
	DAMAGED <input type="checkbox"/>			

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]  
CUSTOMER REPRESENTATIVE:

COMMENTS: Hydrant has minor leak at ground flange.



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

3

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3614 Old Finch Ave  
Scarborough

HYDRANT LOCATION: South of Africa (near Elephant)  
HYDRANT MAKE: Century  
DATE: Dec 21/95


ANNUAL PREVENTATIVE MAINTENANCE (APM)			
1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OK <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input checked="" type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>20</u>	PITOT <u>8.32</u>	USGPM
9. PRESSURE TEST	<u>44</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>	
	NA <input type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input checked="" type="checkbox"/>	NA <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	NA <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

ADDITIONAL WORK			
18. BONNET COVER	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

4

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: Outside gorilla door  
HYDRANT MAKE: B5013  
DATE: Dec 21/98

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input checked="" type="checkbox"/>	NOT OPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	DIFFICULT <input type="checkbox"/>	NOT OPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED <input type="checkbox"/>
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input checked="" type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED <input type="checkbox"/>
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>27</u>	FTOT <u>91.5/12</u>	USGPM
9. PRESSURE TEST	<u>51</u> PSIG	PASSED <input type="checkbox"/>	FAILED <input checked="" type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>		NO <input type="checkbox"/>
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER <input type="checkbox"/>
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

SERVICED BY: [Signature]


CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: Hydrant leaks when fully charged.

### ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		





# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

5

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: West side of African Par  
HYDRANT MAKE: Centurus  
DATE: Dec 21/98

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

### ADDITIONAL WORK


1. SECONDARY VALVE	<u>2" size</u> LOCATED <input checked="" type="checkbox"/> NOT VISIBLE <input type="checkbox"/>	OK <input checked="" type="checkbox"/> CLOTTED <input type="checkbox"/> INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/> LEAKING <input type="checkbox"/> OL <input type="checkbox"/> DIFFICULT <input type="checkbox"/> INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/> AMT. OF WATER _____ DRY <input checked="" type="checkbox"/>	
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/> R/S <input type="checkbox"/> LOOSE <input type="checkbox"/> LEAKING <input type="checkbox"/> LEADED <input checked="" type="checkbox"/> DAMAGED <input type="checkbox"/>	
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>
7. LUBE SCREW	OK <input checked="" type="checkbox"/> MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>24</u> PITOT <u>911</u> USGPM	
9. PRESSURE TEST	<u>40</u> PSIG PASSED <input checked="" type="checkbox"/> FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/> COLOUR _____ NO <input checked="" type="checkbox"/>	
11. HYDRANT PAINTED	YES <input type="checkbox"/> COLOUR _____ NO <input checked="" type="checkbox"/>	
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/> NO <input type="checkbox"/> NA <input checked="" type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input type="checkbox"/> BURIED <input type="checkbox"/> LEAKING <input type="checkbox"/> SOLID <input checked="" type="checkbox"/> N/A <input type="checkbox"/> DAMAGED <input type="checkbox"/>	
14. REQUIRES BARREL EXTENTION		NA <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/> TYPE _____ NO <input checked="" type="checkbox"/>	
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/> TOO CLOSE <input type="checkbox"/> DAMAGED <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	

18. BONNET COVER	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	NA <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE:

COMMENTS:



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

6

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3161A Old Finch Ave  
Scarborough

HYDRANT LOCATION: South of African M<sup>c</sup>Dona  
HYDRANT MAKE: M67  
DATE: Dec 21/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK


1. SECONDARY VALVE	LOCATED <input type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	CLOSED <input type="checkbox"/>
			INOPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OL <input type="checkbox"/>		INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____		
	DRY <input checked="" type="checkbox"/>			
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>		
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	RVS <input type="checkbox"/>	LOOSE _____	
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED _____	
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>		
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
8. FLOW TEST	<u>Flowed</u>	PITOT _____	USGPM _____	
9. PRESSURE TEST	<u>35</u> P&IG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____		
	NO <input checked="" type="checkbox"/>			
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____		
	NO <input checked="" type="checkbox"/>			
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>		
	N/A <input checked="" type="checkbox"/>			
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING _____	
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED _____	
14. REQUIRES BARREL EXTENTION	_____			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____		
	NO <input checked="" type="checkbox"/>			
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>		
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>	
	DAMAGED <input type="checkbox"/>			

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
36. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE CUTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS:  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

# A-1 HYDRANT SERVICES LTD.


550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

7

CUSTOMER NAME: <u>Toronto Metro Zoo</u>	HYDRANT LOCATION: <u>N/W of African M<sup>c</sup>Dono</u>
SERVICE ADDRESS: <u>361A Old Finch Ave</u> <u>Scarborough</u>	HYDRANT MAKE: <u>AVK</u>
	DATE: <u>Dec 21/98</u>

ANNUAL PREVENTATIVE MAINTENANCE (APM)			
1. SECONDARY VALVE	<u>2' STE</u> LOCATED <input checked="" type="checkbox"/> NOT VISIBLE <input type="checkbox"/>	OK <input checked="" type="checkbox"/> CLOSED <input type="checkbox"/> NOT OPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/> DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/> INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/> DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____	
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/> LEAKING <input type="checkbox"/>	RVS <input checked="" type="checkbox"/> LEADED <input type="checkbox"/>	LOOSE <input type="checkbox"/> DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input type="checkbox"/>	NOT REQUIRED <input checked="" type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/> MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
8. FLOW TEST	<u>32</u> PITOT <u>1052</u>	USGPM	
9. PRESSURE TEST	<u>41</u> PSIG	PASSED <input checked="" type="checkbox"/> FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	CLOUR _____	
11. HYDRANT PAINTED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	CLOUR _____	
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/> SOLID <input type="checkbox"/>	BURIED <input type="checkbox"/> N/A <input type="checkbox"/>	LEAKING <input type="checkbox"/> DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENSION		N/A <input type="checkbox"/>	
15. PUMPER NOZZLE	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	TYPE <u>ST</u>	
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/> DAMAGED <input type="checkbox"/>	N/A <input type="checkbox"/> TOO CLOSE <input type="checkbox"/>	
SERVICED BY: <u>[Signature]</u>			
CUSTOMER REPRESENTATIVE: _____			
COMMENTS: _____			

ADDITIONAL WORK			
18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

80

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3614 Old Finch Ave  
Scarborough

HYDRANT LOCATION: South end of main escape  
HYDRANT MAKE: MJ7  
DATE: Dec 2/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK


1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	OK <input type="checkbox"/>	CLOSED <input type="checkbox"/>
2. HYDRANT OPERATION	OPR <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____	
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>		
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>		
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
8. FLOW TEST	<u>30</u>	PITOT	<u>1019</u>	USGPM
9. PRESSURE TEST	<u>56</u>	P8IG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____	
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____	
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	SOLID <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	_____			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	TYPE _____	
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>		
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAUKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

9

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: Inside/Outside holding  
HYDRANT MAKE: 23501  
DATE: Dec 21/98

**ANNUAL PREVENTATIVE MAINTENANCE (APM)**

1. SECONDARY VALVE  LOCATED  NOT VISIBLE  OK  CLOSED  INOPERABLE

2. HYDRANT OPERATION  OK  DIFFICULT  LEAKING  INOPERABLE

3. CHECK BARREL FOR WATER  WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS  OK  REPLACED

5. CHECK NOZZLES & THREADS  OK  LEAKING  R/S  LOOSE  LEADED  DAMAGED

6. LUBRICATE HYDRANT  YES  NOT REQUIRED

7. LUBE SCREW  OK  MISSING  REPLACED

8. FLOW TEST 5 PITOT 416 USGPM

9. PRESSURE TEST @ 79 PSIG  PASSED  FAILED

10. COLOUR CODED  YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED  YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT  YES  NO  N/A

13. GROUND FLANGE  SAFETY  BOLD  BUFFED  N/A  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE  YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION  OK  IMPROPER

17. TRAFFIC BOLLARDS  OK  N/A  TOO CLOSE  DAMAGED

**ADDITIONAL WORK**

18. BONNET COVER  OK  N/A  REPLACED

19. BONNET BOLTS  OK  N/A  REPLACED

20. BONNET  OK  REPLACED

21. BONNET SEAL  OK  REPLACED

22. OPERATING NUT  OK  REPLACED

23. OPERATING NUT O-RING(S)  OK  N/A  REPACK

24. STUFFING BOX  OK  N/A  REPLACED

25. THRUST BEARING  OK  N/A  REPLACED

26. BEARING HOUSING  OK  N/A  REPLACED

27. BEARING HOUSING BOLTS  OK  N/A  REPLACED

28. HOUSING COVER  OK  N/A  REPLACED

29. HOUSING COVER BOLTS  OK  N/A  REPLACED

30. BEARING HOUSING SEAL(S)  OK  N/A  REPLACED

31. UPPER OPERATING ROD  OK  REPLACED

32. LOWER OPERATING ROD  OK  REPLACED

33. ROD COUPLING  OK  N/A  REPLACED

34. COUPLING BOLTS  OK  N/A  REPLACED

35. LOWER ROD NUT(S)  OK  REPLACED

36. LOWER ROD STOP PIN/PLATE  OK  N/A  REPLACED

37. VALVE BALL SEAL(S)  OK  N/A  REPLACED

38. VALVE BALL BOTTOM  OK  REPLACED

39. VALVE BALL RUBBER  OK  REPLACED

40. VALVE BALL TOP  OK  N/A  REPLACED

41. MAIN VALVE BEAT  OK  REPLACED

42. MAIN VALVE SEAT SEAL(S)  OK  REPLACED

43. DRAIN VALVE  OK  REPLACED

44. DRAIN VALVE SEAL(S)  OK  REPLACED

45. DRAIN VALVE PORT(S)  OK  CLEARED  REPLACED

46. DRAIN VALVE COTTER PIN(S)  OK  N/A  REPLACED

47. LOWER BARREL  OK  REPLACED

48. LOWER BARREL FLANGE(S)  OK  N/A  REPLACED

49. UPPER BARREL  OK  REPLACED

50. UPPER BARREL FLANGE(S)  OK  N/A  REPLACED

51. BARREL EXTENSION(S)  OK  N/A  REPLACED

52. FLANGE GASKET(S)  OK  N/A  REPLACED

53. FLANGE BOLTS  OK  N/A  REPLACED

54. BOOT  OK  N/A  REPLACED

55. NOZZLE(S)  OK  RECALKED  REPLACED

56. NOZZLE CAP(S)  OK  REPLACED

57. NOZZLE RETAINER(S)  OK  N/A  REPLACED

58. OTHER  OK

59. OTHER  OK

60. OTHER  OK


61. OTHER  OK

62. OTHER  OK

63. OTHER  OK

SERVICED BY: [Signature]  
CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: Hydrant leaks when  
fully charged secondary  
valve not visible.



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

10  
North American

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: West of ~~Finch~~ McDown  
HYDRANT MAKE: M47  
DATE: Dec 21/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK

1. SECONDARY VALVE  LOCATED  NOT VISIBLE  OK  CLOSED  INOPERABLE

2. HYDRANT OPERATION  OK  DIFFICULT  LEAKING  OPERABLE

3. CHECK BARREL FOR WATER  WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS  OK  REPLACED

5. CHECK NOZZLES & THREADS  OK  LEAKING  R/S  LEADED  LOOSE  DAMAGED

6. LUBRICATE HYDRANT  YES  NOT REQUIRED

7. LUBE SCREW  OK  MISSING  REPLACED

8. FLOW TEST 46 FTOT 1261 USGPM

9. PRESSURE TEST 57 PSIG  PASSED  FAILED

10. COLOUR CODED  YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED  YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT  YES  NO  N/A

13. GROUND FLANGE  SAFETY  SOLID  BURIED  N/A  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE  YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION  OK  IMPROPER

17. TRAFFIC BOLLARDS  OK  DAMAGED  N/A  TOO CLOSE

18. BONNET COVER  OK  N/A  REPLACED

19. BONNET BOLTS  OK  N/A  REPLACED

20. BONNET  OK  REPLACED

21. BONNET SEAL  OK  REPLACED

22. OPERATING NUT  OK  REPLACED

23. OPERATING NUT O-RING(S)  OK  N/A  REPACK

24. STUFFING BOX  OK  N/A  REPLACED

25. THRUST BEARING  OK  N/A  REPLACED

26. BEARING HOUSING  OK  N/A  REPLACED

27. BEARING HOUSING BOLTS  OK  N/A  REPLACED

28. HOUSING COVER  OK  N/A  REPLACED

29. HOUSING COVER BOLTS  OK  N/A  REPLACED

30. BEARING HOUSING SEAL(S)  OK  N/A  REPLACED

31. UPPER OPERATING ROD  OK  REPLACED

32. LOWER OPERATING ROD  OK  REPLACED

33. ROD COUPLING  OK  N/A  REPLACED

34. COUPLING BOLTS  OK  N/A  REPLACED

35. LOWER ROD NUT(S)  OK  REPLACED

36. LOWER ROD STOP PIN/PLATE  OK  N/A  REPLACED

37. VALVE BALL SEAL(S)  OK  N/A  REPLACED

38. VALVE BALL BOTTOM  OK  REPLACED

39. VALVE BALL RUBBER  OK  REPLACED

40. VALVE BALL TOP  OK  N/A  REPLACED

41. MAIN VALVE SEAT  OK  REPLACED

42. MAIN VALVE SEAT SEAL(S)  OK  REPLACED

43. DRAIN VALVE  OK  REPLACED

44. DRAIN VALVE SEAL(S)  OK  REPLACED

45. DRAIN VALVE PORT(S)  OK  CLEARED  REPLACED

46. DRAIN VALVE COTTER PIN(S)  OK  N/A  REPLACED

47. LOWER BARREL  OK  REPLACED

48. LOWER BARREL FLANGE(S)  OK  N/A  REPLACED

49. UPPER BARREL  OK  REPLACED

50. UPPER BARREL FLANGE(S)  OK  N/A  REPLACED

51. BARREL EXTENTION(S)  OK  N/A  REPLACED

52. FLANGE GASKET(S)  OK  N/A  REPLACED

53. FLANGE BOLTS  OK  N/A  REPLACED

54. BOOT  OK  N/A  REPLACED

55. NOZZLE(S)  OK  RECALKED  REPLACED

56. NOZZLE CAP(S)  OK  REPLACED

57. NOZZLE RETAINER(S)  OK  N/A  REPLACED

58. OTHER  OK

59. OTHER  OK

60. OTHER  OK

61. OTHER  OK


62. OTHER  OK

63. OTHER  OK

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



HYDRANT OPERATION SATISFACTORY   
 HYDRANT OPERATION DEFICIENCY


# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
 Scarborough, On. M1E 4V1  
 (416) 282-1665  
 1-888-349-2493

11

CUSTOMER NAME: Toronto Metro Zoo  
 SERVICE ADDRESS: 3161A Old Finch Ave  
Scarborough  
 HYDRANT LOCATION: North of North American Rd  
 HYDRANT MAKE: Century  
 DATE: Dec 21/98

ANNUAL PREVENTATIVE MAINTENANCE (APM)		ADDITIONAL WORK	
1. SECONDARY VALVE	<u>Locally</u> LOCATED <input checked="" type="checkbox"/> NOT VISIBLE <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/> INOPERABLE <input checked="" type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/> OR CAL <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/> INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/> DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____	
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/> OR LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/> LEADED <input type="checkbox"/>	LOOSE <input type="checkbox"/> DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>Flowed</u>	PITOT _____	USGPM _____
9. PRESSURE TEST	@ <u>55</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	COLOUR _____	
11. HYDRANT PAINTED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	COLOUR _____	
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input type="checkbox"/> SOLID <input checked="" type="checkbox"/>	BURNED <input type="checkbox"/> N/A <input type="checkbox"/>	LEAKING <input type="checkbox"/> DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	N/A <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	TYPE _____	
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/> DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
SERVICED BY: <u>[Signature]</u>			
CUSTOMER REPRESENTATIVE: _____			
COMMENTS: <u>Secondary valve seized</u> <u>in open position</u>			
18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
21. BONNET SEAL	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
22. OPERATING NUT	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
32. LOWER OPERATING ROD	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
39. VALVE BALL RUBBER	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
43. DRAIN VALVE	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>	REPLACED <input type="checkbox"/>	
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

17

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: N/E of Special Events Te  
HYDRANT MAKE: B50B  
DATE: Dec 21/96

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

### ADDITIONAL WORK

1. SECONDARY VALVE	<u>2' east</u> LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
		NOT VISIBLE <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OR <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>40</u>	PITOT <u>1176</u>	USGPM
9. PRESSURE TEST	<u>50</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>	
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	BOLD <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	N/A <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		


18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_





HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

**A-1 HYDRANT SERVICES LTD.**  
550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

13

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: North of Australasia  
HYDRANT MAKE: Mcf  
DATE: Dec 21/98

**ANNUAL PREVENTATIVE MAINTENANCE (APM)**

**ADDITIONAL WORK**

1. SECONDARY VALVE Least LOCATED  NOT VISIBLE  OK  CLOSED  INOPERABLE

2. HYDRANT OPERATION OVR  OL  OK  DIFFICULT  LEAKING  INOPERABLE

3. CHECK BARREL FOR WATER WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS OK  REPLACED

5. CHECK NOZZLES & THREADS OK  LEAKING  R/S  LEADED  LOOSE  DAMAGED

6. LUBRICATE HYDRANT YES  NOT REQUIRED

7. LUBE SCREW OK  MISSING  REPLACED

8. FLOW TEST 46 PITOT 1261 USGPM

9. PRESSURE TEST 56 PSIG PASSED  FAILED

10. COLOUR CODED YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT YES  NO

13. GROUND FLANGE SAFETY  SOLID  BURIED  N/A  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENSION \_\_\_\_\_ N/A

15. PUMPER NOZZLE YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION OK  IMPROPER


17. TRAFFIC BOLLARDS OK  DAMAGED  N/A  TOO CLOSE

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PINS(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

14

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3101A Old Finch Ave  
Scarborough

HYDRANT LOCATION: North of Australasia M Zoo  
HYDRANT MAKE: MUT  
DATE: Dec 21/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK

1. SECONDARY VALVE 4' east LOCATED  NOT VISIBLE  OK  CLOSED  INOPERABLE

2. HYDRANT OPERATION OR  OL  OK  DIFFICULT  LEAKING  INOPERABLE

3. CHECK BARREL FOR WATER WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS OK  REPLACED

5. CHECK NOZZLES & THREADS OK  LEAKING  R/S  LEADED  LOOSE  DAMAGED

6. LUBRICATE HYDRANT YES  NOT REQUIRED

7. LUBE SCREW OK  MISSING  REPLACED

8. FLOW TEST 26 RTOT 948 USGPM

9. PRESSURE TEST 56 PSIG PASSED  FAILED

10. COLOUR CODED YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT YES  N/A  NO

13. GROUND FLANGE SAFETY  SOLID  BURIED  N/A  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION OK  IMPROPER

17. TRAFFIC BOLLARDS OK  DAMAGED  N/A  TOO CLOSE

18. BONNET COVER OK  N/A  REPLACED

19. BONNET BOLTS OK  N/A  REPLACED

20. BONNET OK  REPLACED

21. BONNET SEAL OK  REPLACED

22. OPERATING NUT OK  REPLACED

23. OPERATING NUT O-RING(S) OK  N/A  REPACK

24. STUFFING BOX OK  N/A  REPLACED

25. THRUST BEARING OK  N/A  REPLACED

26. BEARING HOUSING OK  N/A  REPLACED

27. BEARING HOUSING BOLTS OK  N/A  REPLACED

28. HOUSING COVER OK  N/A  REPLACED

29. HOUSING COVER BOLTS OK  N/A  REPLACED

30. BEARING HOUSING SEAL(S) OK  N/A  REPLACED

31. UPPER OPERATING ROD OK  REPLACED

32. LOWER OPERATING ROD OK  REPLACED

33. ROD COUPLING OK  N/A  REPLACED

34. COUPLING BOLTS OK  N/A  REPLACED

35. LOWER ROD NUT(S) OK  REPLACED

36. LOWER ROD STOP PIN/PLATE OK  N/A  REPLACED

37. VALVE BALL SEAL(S) OK  N/A  REPLACED

38. VALVE BALL BOTTOM OK  REPLACED

39. VALVE BALL RUBBER OK  REPLACED

40. VALVE BALL TOP OK  N/A  REPLACED

41. MAIN VALVE SEAT OK  REPLACED

42. MAIN VALVE SEAT SEAL(S) OK  REPLACED

43. DRAIN VALVE OK  REPLACED

44. DRAIN VALVE SEAL(S) OK  REPLACED

45. DRAIN VALVE PORT(S) OK  CLEARED  REPLACED

46. DRAIN VALVE COTTER PIN(S) OK  N/A  REPLACED

47. LOWER BARREL OK  REPLACED

48. LOWER BARREL FLANGE(S) OK  N/A  REPLACED

49. UPPER BARREL OK  REPLACED

50. UPPER BARREL FLANGE(S) OK  N/A  REPLACED

51. BARREL EXTENTION(S) OK  N/A  REPLACED

52. FLANGE GASKET(S) OK  N/A  REPLACED

53. FLANGE BOLTS OK  N/A  REPLACED

54. BOOT OK  N/A  REPLACED

55. NOZZLE(S) OK  RECALKED  REPLACED

56. NOZZLE CAP(S) OK  REPLACED

57. NOZZLE RETAINER(S) OK  N/A  REPLACED

58. OTHER OK

59. OTHER OK

60. OTHER OK

61. OTHER OK


62. OTHER OK

63. OTHER OK

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: Leaks at operating nut  
packing.



HYDRANT OPERATION SATISFACTORY   
 HYDRANT OPERATION DEFICIENCY

# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
 Scarborough, On. M1E 4V1  
 (416) 282-1665  
 1-888-349-2493

15

CUSTOMER NAME: Toronto Metro Zoo HYDRANT LOCATION: South of Greenhouse  
 SERVICE ADDRESS: 3161 & Old Finch Ave HYDRANT MAKE: MCF  
Scarborough DATE: Dec 21/98

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE 2 used LOCATED  NOT VISIBLE  OK  CLOSED  OPERABLE

2. HYDRANT OPERATION OR  OL  OK  DIFFICULT  LEAKING  INOPERABLE

3. CHECK BARREL FOR WATER WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS OK  REPLACED

5. CHECK NOZZLES & THREADS OK  LEAKING  R/B  LOOSE  LEADED  DAMAGED

6. LUBRICATE HYDRANT YES  NOT REQUIRED

7. LUBE SCREW OK  MISSING  REPLACED

8. FLOW TEST 34 PITOT 108.5 USGPM

9. PRESSURE TEST 50 PSIG PASSED  FAILED

10. COLOUR CODED YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT YES  NO

13. GROUND FLANGE SAFETY  SOLID  BURIED  NA  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENSION \_\_\_\_\_ NA

15. PUMPER NOZZLE YES  NO  TYPE ST

16. NOZZLE ORIENTATION OK  IMPROPER

17. TRAFFIC BOLLARDS OK  DAMAGED  NA  TOO CLOSE


SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: Left 2 1/2 inch port cap missing.

### ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL BEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
59. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
60. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
61. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
62. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
63. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

16

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: S/E of north service  
HYDRANT MAKE: M1E7  
DATE: Dec 21/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK

1. SECONDARY VALVE 3' west LOCATED  NOT VISIBLE  OK  CLOSED  INCOPERABLE

2. HYDRANT OPERATION O/R  OL  OK  DIFFICULT  LEAKING  INCOPERABLE

3. CHECK BARREL FOR WATER WET  DRY  AMT. OF WATER \_\_\_\_\_

4. CHECK CAP GASKETS OK  REPLACED

5. CHECK NOZZLES & THREADS OK  LEAKING  P/B  LOOSE  LEADED  DAMAGED

6. LUBRICATE HYDRANT YES  NOT REQUIRED

7. LUBE SCREW OK  MISSING  REPLACED

8. FLOW TEST 30 PITOT 10M USGPM

9. PRESSURE TEST 50 PSIG PASSED  FAILED

10. COLOUR CODED YES  NO  COLOUR \_\_\_\_\_

11. HYDRANT PAINTED YES  NO  COLOUR \_\_\_\_\_

12. HYDRANT PUMPED OUT YES  NO

13. GROUND FLANGE SAFETY  SOLID  BURIED  N/A  LEAKING  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE YES  NO  TYPE \_\_\_\_\_

16. NOZZLE ORIENTATION OK  IMPROPER

17. TRAFFIC BOLLARDS OK  DAMAGED  N/A  TOO CLOSE

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. _____	OK <input type="checkbox"/>		<input type="checkbox"/>
59. _____	OK <input type="checkbox"/>		<input type="checkbox"/>
60. _____	OK <input type="checkbox"/>		<input type="checkbox"/>
61. _____	OK <input type="checkbox"/>		<input type="checkbox"/>
62. _____	OK <input type="checkbox"/>		<input type="checkbox"/>
63. _____	OK <input type="checkbox"/>		<input type="checkbox"/>


SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

see not operated.

HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY



**A-1 HYDRANT SERVICES LTD.**  
550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

17

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361 A Old Finch Ave  
Scarborough

HYDRANT LOCATION: N/E of north service  
HYDRANT MAKE: MU7  
DATE: Dec 21 1998

**ANNUAL PREVENTATIVE MAINTENANCE (APM)**

**ADDITIONAL WORK**


1. SECONDARY VALVE	<u>2' west</u> LOCATED	OK <input checked="" type="checkbox"/>	NOT VISIBLE <input type="checkbox"/>	CLOSED <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED	<input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED	<input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED	<input type="checkbox"/>	
8. FLOW TEST	<u>34</u>	PTOT <u>1085</u>	USGPM		
9. PRESSURE TEST	<u>50</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>		
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	NO	<input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	SOLID <input checked="" type="checkbox"/>	BURED <input type="checkbox"/>	LEAKING <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION			N/A	<input type="checkbox"/>	
15. PUMPER NOZZLE	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	TYPE		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER	<input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input type="checkbox"/>	TOO CLOSE	<input type="checkbox"/>

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE:

COMMENTS: Secondary unable to  
cycle due to depth.



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

18

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: East side of garage  
HYDRANT MAKE: Cannon  
DATE: Dec 21/98


ANNUAL PREVENTATIVE MAINTENANCE (APM)			
1. SECONDARY VALVE	<u>2' south</u> LOCATED	OK <input checked="" type="checkbox"/> NOT VISIBLE <input type="checkbox"/>	CLOSED <input type="checkbox"/> INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/> OL <input type="checkbox"/>	OK <input checked="" type="checkbox"/> DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/> INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/> DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____	
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input checked="" type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/> LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/> LEADED <input type="checkbox"/>	LOOSE <input type="checkbox"/> DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>23</u>	PI TOT <u>892</u>	USQPM _____
9. PRESSURE TEST	<u>48</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	COLOUR _____	
11. HYDRANT PAINTED	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	COLOUR _____	
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/> SOLID <input type="checkbox"/>	BURIED <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/> DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENSION	N/A <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	TYPE _____	
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/> DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>

ADDITIONAL WORK			
18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: Alex M

CUSTOMER REPRESENTATIVE:

COMMENTS: Secondary valve box  
broken & lid missing (4SL)  
Also, box has mud, but  
still operable. N/A



HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

19

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: West end of North service  
HYDRANT MAKE: Century  
DATE: Dec 21/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE	<u>2 months</u> LOCATED	OK <input checked="" type="checkbox"/>	NOT VISIBLE <input type="checkbox"/>	CLOSED <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/>	NO PERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED	<input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input type="checkbox"/>		NOT REQUIRED	<input checked="" type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>		MISSING <input type="checkbox"/>	REPLACED	<input type="checkbox"/>
8. FLOW TEST	<u>26</u>	PTOT	<u>948</u>	USGPM	
9. PRESSURE TEST	@ <u>50</u>	PSIG	PASSED <input type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>		NO <input type="checkbox"/>	
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	SOLID <input checked="" type="checkbox"/>	BURIED <input type="checkbox"/>	N/A <input type="checkbox"/>	LEAKING <input type="checkbox"/>
					DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENSION				N/A	<input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	TYPE		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER	<input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TCC CLOSE	<input type="checkbox"/>


SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE:

COMMENTS:

## ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

20

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3161/2 Old Finch Ave  
Scarborough

HYDRANT LOCATION: East of New Lion Holding  
HYDRANT MAKE: AVK  
DATE: Dec 23/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>			
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>			
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>		
8. FLOW TEST	<u>22</u>	PITOT	<u>872</u>	USGPM	
9. PRESSURE TEST	<u>33</u>	PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BOLID <input type="checkbox"/>	BURIED <input type="checkbox"/>	LEAKING <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	_____				N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	TYPE <u>ST</u>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>			
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>	


18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEANED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_





HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

21

CUSTOMER NAME: Toronto Metro Zoo HYDRANT LOCATION: Old Matagaska Restau  
 SERVICE ADDRESS: 361A Old Finch Ave HYDRANT MAKE: M167  
Scarborough DATE: Dec 23/98

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE 4' south OK  CLOSED   
 LOCATED  NOT VISIBLE  INOPERABLE

2. HYDRANT OPERATION O/R  OK  LEAKING   
 O/L  DIFFICULT  INOPERABLE

3. CHECK BARREL FOR WATER WET  AMT. OF WATER \_\_\_\_\_  
 DRY

4. CHECK CAP GASKETS OK  REPLACED

5. CHECK NOZZLES & THREADS OK  R/S  LOOSE   
 LEAKING  LEADED  DAMAGED

6. LUBRICATE HYDRANT YES  NOT REQUIRED

7. LUBE SCREW OK  MISSING  REPLACED

8. FLOW TEST 14 PITOT 696 USGPM

9. PRESSURE TEST 46 PSIG PASSED  FAILED

10. COLOUR CODED YES  COLOUR \_\_\_\_\_  
 NO

11. HYDRANT PAINTED YES  COLOUR \_\_\_\_\_  
 NO

12. HYDRANT PUMPED OUT YES  NO   
 N/A

13. GROUND FLANGE SAFETY  BURIED  LEAKING   
 SOLID  N/A  DAMAGED

14. REQUIRES BARREL EXTENTION \_\_\_\_\_ N/A

15. PUMPER NOZZLE YES  TYPE \_\_\_\_\_  
 NO

16. NOZZLE ORIENTATION OK  IMPROPER

17. TRAFFIC BOLLARDS OK  N/A  TOO CLOSE   
 DAMAGED


### ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINERS(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

22

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361A Old Finch Ave  
Scarborough

HYDRANT LOCATION: North American Domain  
HYDRANT MAKE: MU7  
DATE: Dec 23/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK


1. SECONDARY VALVE	<u>4' north</u> LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input type="checkbox"/>	NOT OPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OL <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>12</u>	PTOT <u>644</u>	USGPM
9. PRESSURE TEST	<u>93</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>	
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	N/A <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

23

CUSTOMER NAME: <u>Toronto Metro Zoo</u>	HYDRANT LOCATION: <u>New Havana Restaura</u>
SERVICE ADDRESS: <u>3161+ Old Finch Ave Scarborough</u>	HYDRANT MAKE: <u>AVK</u>
	DATE: <u>Dec 23/98</u>

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	DIFFICULT <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED <input type="checkbox"/>
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED <input type="checkbox"/>
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>20</u> USGPM	PTDT <u>8.32</u>	
9. PRESSURE TEST	<u>38</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>		NO <input type="checkbox"/>
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/>	BURNED <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input checked="" type="checkbox"/>	TYPE <u>ST</u>	
	NO <input type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER <input type="checkbox"/>
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		


SERVED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_

### ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

24

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3601A Old Finch Ave  
Scarborough

HYDRANT LOCATION: North of Chetah Building  
HYDRANT MAKE: AVK  
DATE: Dec 23 1998

## ANNUAL PREVENTATIVE MAINTENANCE (APM)


## ADDITIONAL WORK

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input checked="" type="checkbox"/>	NOT OPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	DIFFICULT <input type="checkbox"/>	NOT OPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED <input type="checkbox"/>
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED <input type="checkbox"/>
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>14</u>	PITOT <u>696</u>	USGPM
9. PRESSURE TEST	<u>34</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>		NO <input type="checkbox"/>
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/>	BURIED <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input checked="" type="checkbox"/>	TYPE <u>ST</u>	
	NO <input type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		W/PROPER <input type="checkbox"/>
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]  
CUSTOMER REPRESENTATIVE:

COMMENTS:



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY [ ]  
HYDRANT OPERATION DEFICIENCY [ ]

25

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3614 Old Finch Ave  
Scarborough

HYDRANT LOCATION: East of African Pavilion  
HYDRANT MAKE: Century  
DATE: Dec 23 1998

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK


1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	NOT VISIBLE <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>	OPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OR <input checked="" type="checkbox"/>	OL <input type="checkbox"/>	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/> OPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>			
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>			
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>		
8. FLOW TEST	<u>18</u>	PI TOT	<u>789</u>	USGPM	
9. PRESSURE TEST	<u>32</u>	PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NA <input checked="" type="checkbox"/>	NO <input type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	SOLID <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	LEAKING <input type="checkbox"/> DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENSION	_____				NA <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	TYPE _____		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>			
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>	

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
59. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
60. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
61. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
62. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>
63. OTHER	OK <input type="checkbox"/>		<input type="checkbox"/>

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

26

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 361 x Old Finch Ave  
Scarborough

HYDRANT LOCATION: East of Society  
HYDRANT MAKE: M127  
DATE: Dec 23 1998


ANNUAL PREVENTATIVE MAINTENANCE (APM)			
1. SECONDARY VALVE	<u>3rd</u> LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
		NOT VISIBLE <input type="checkbox"/>	INOPERABLE <input checked="" type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OL <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>Flushed</u>	RTOT _____	USGPM _____
9. PRESSURE TEST	<u>4.0</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>	
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/>	BURIED <input type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENSION	N/A <input type="checkbox"/>		
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

ADDITIONAL WORK			
18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENSION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECALKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: Hydrant unable to flow  
test due to walkways.  
Secondary inoperable due  
to valve box full of dirt.



HYDRANT OPERATION SATISFACTORY  
HYDRANT OPERATION DEFICIENCY

# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

27

CUSTOMER NAME: Toronto Metro Zoo HYDRANT LOCATION: South of Society  
 SERVICE ADDRESS: 3614 Old Finch Ave HYDRANT MAKE: M117  
Scarborough DATE: Dec 23/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	NOT VISIBLE <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	O/R <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	DIFFICULT <input type="checkbox"/>	LEAKING <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	AMT. OF WATER _____		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>			
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/B <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>	LOOSE <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>			
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>		
8. FLOW TEST	<u>54</u>	PTOT <u>1367</u>	USGPM		
9. PRESSURE TEST	<u>58</u>	PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>	
10. COLOUR CODED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	COLOUR _____		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	NO <input type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input checked="" type="checkbox"/>	SOLID <input type="checkbox"/>	BURPED <input type="checkbox"/>	N/A <input type="checkbox"/>	LEAKING <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	_____				N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>	TYPE _____		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>			
17. TRAFFIC BOLLARDS	OK <input checked="" type="checkbox"/>	DAMAGED <input type="checkbox"/>	N/A <input type="checkbox"/>	TOO CLOSE <input type="checkbox"/>	


SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE: \_\_\_\_\_

COMMENTS: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

## ADDITIONAL WORK

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY   
HYDRANT OPERATION DEFICIENCY

28

CUSTOMER NAME: *Toronto Metro Zoo*  
SERVICE ADDRESS: *301A Old Finch Ave  
Scarborough*

HYDRANT LOCATION:  
HYDRANT MAKE: *M67*  
DATE: *Dec 23/98*

### ANNUAL PREVENTATIVE MAINTENANCE (APM)

1. SECONDARY VALVE	<i>DONE</i>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
	LOCATED	NOT VISIBLE <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	OK <input type="checkbox"/>	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>	REPLACED <input type="checkbox"/>	
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	R/S <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>	NOT REQUIRED <input type="checkbox"/>	
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<i>Flowed</i>	PI TOT _____	USGPM _____
9. PRESSURE TEST	<i>600</i>	PSIG	PASSED <input checked="" type="checkbox"/> FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>	NO <input type="checkbox"/>	
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION	_____		N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>	TYPE _____	
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>	IMPROPER <input type="checkbox"/>	
17. TRAFFIC BOLLARDS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

### ADDITIONAL WORK


18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE SEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE SEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		

SERVICED BY: *[Signature]*

CUSTOMER REPRESENTATIVE:

COMMENTS: *Hydrant unable to flow  
test due temperature & walk-  
ways*





# A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
(416) 282-1665  
1-888-349-2493

HYDRANT OPERATION SATISFACTORY [ ]  
HYDRANT OPERATION DEFICIENCY [ ]

29

CUSTOMER NAME: Toronto Metro Zoo  
SERVICE ADDRESS: 3614 Old Finch Ave  
Scarborough

HYDRANT LOCATION: West of Harriet Lane  
HYDRANT MAKE: M617  
DATE: Dec 23/98

## ANNUAL PREVENTATIVE MAINTENANCE (APM)

## ADDITIONAL WORK

1. SECONDARY VALVE	LOCATED <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	CLOSED <input type="checkbox"/>
	NOT VISIBLE <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>	
2. HYDRANT OPERATION	OK <input checked="" type="checkbox"/>	OK <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	DIFFICULT <input type="checkbox"/>	INOPERABLE <input type="checkbox"/>	
3. CHECK BARREL FOR WATER	WET <input type="checkbox"/>	AMT. OF WATER _____	
	DRY <input checked="" type="checkbox"/>		
4. CHECK CAP GASKETS	OK <input checked="" type="checkbox"/>		REPLACED <input type="checkbox"/>
5. CHECK NOZZLES & THREADS	OK <input checked="" type="checkbox"/>	RVS <input checked="" type="checkbox"/>	LOOSE <input type="checkbox"/>
	LEAKING <input type="checkbox"/>	LEADED <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
6. LUBRICATE HYDRANT	YES <input checked="" type="checkbox"/>		NOT REQUIRED <input type="checkbox"/>
7. LUBE SCREW	OK <input checked="" type="checkbox"/>	MISSING <input type="checkbox"/>	REPLACED <input type="checkbox"/>
8. FLOW TEST	<u>30</u> PITOT	<u>1019</u>	USGPM
9. PRESSURE TEST	<u>44</u> PSIG	PASSED <input checked="" type="checkbox"/>	FAILED <input type="checkbox"/>
10. COLOUR CODED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
11. HYDRANT PAINTED	YES <input type="checkbox"/>	COLOUR _____	
	NO <input checked="" type="checkbox"/>		
12. HYDRANT PUMPED OUT	YES <input type="checkbox"/>		NO <input type="checkbox"/>
	N/A <input checked="" type="checkbox"/>		
13. GROUND FLANGE	SAFETY <input type="checkbox"/>	BURIED <input checked="" type="checkbox"/>	LEAKING <input type="checkbox"/>
	SOLID <input type="checkbox"/>	N/A <input type="checkbox"/>	DAMAGED <input type="checkbox"/>
14. REQUIRES BARREL EXTENTION			N/A <input type="checkbox"/>
15. PUMPER NOZZLE	YES <input type="checkbox"/>		TYPE _____
	NO <input checked="" type="checkbox"/>		
16. NOZZLE ORIENTATION	OK <input checked="" type="checkbox"/>		IMPROPER <input type="checkbox"/>
17. TRAFFIC BOLTS	OK <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	TOO CLOSE <input type="checkbox"/>
	DAMAGED <input type="checkbox"/>		

SERVICED BY: [Signature]

CUSTOMER REPRESENTATIVE:

COMMENTS:

18. BONNET COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
19. BONNET BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
20. BONNET	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
21. BONNET SEAL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
22. OPERATING NUT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
23. OPERATING NUT O-RING(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPACK <input type="checkbox"/>
24. STUFFING BOX	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
25. THRUST BEARING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
26. BEARING HOUSING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
27. BEARING HOUSING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
28. HOUSING COVER	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
29. HOUSING COVER BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
30. BEARING HOUSING SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
31. UPPER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
32. LOWER OPERATING ROD	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
33. ROD COUPLING	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
34. COUPLING BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
35. LOWER ROD NUT(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
36. LOWER ROD STOP PIN/PLATE	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
37. VALVE BALL SEAL(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
38. VALVE BALL BOTTOM	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
39. VALVE BALL RUBBER	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
40. VALVE BALL TOP	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
41. MAIN VALVE BEAT	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
42. MAIN VALVE BEAT SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
43. DRAIN VALVE	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
44. DRAIN VALVE SEAL(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
45. DRAIN VALVE PORT(S)	OK <input type="checkbox"/>	CLEARED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
46. DRAIN VALVE COTTER PIN(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
47. LOWER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
48. LOWER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
49. UPPER BARREL	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
50. UPPER BARREL FLANGE(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
51. BARREL EXTENTION(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
52. FLANGE GASKET(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
53. FLANGE BOLTS	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
54. BOOT	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
55. NOZZLE(S)	OK <input type="checkbox"/>	RECAULKED <input type="checkbox"/>	REPLACED <input type="checkbox"/>
56. NOZZLE CAP(S)	OK <input type="checkbox"/>		REPLACED <input type="checkbox"/>
57. NOZZLE RETAINER(S)	OK <input type="checkbox"/>	N/A <input type="checkbox"/>	REPLACED <input type="checkbox"/>
58. OTHER	OK <input type="checkbox"/>		
59. OTHER	OK <input type="checkbox"/>		
60. OTHER	OK <input type="checkbox"/>		
61. OTHER	OK <input type="checkbox"/>		
62. OTHER	OK <input type="checkbox"/>		
63. OTHER	OK <input type="checkbox"/>		



A-1 HYDRANT SERVICES LTD. 550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 21/98


LOCATION 3601A Old Finch Ave

TEST DATA

TIME OF TEST 10:15am  
 LOCATION OF TEST: (FLOW) Hydrant (Australasia McDonald's) #14  
 (RESIDUAL) Hydrant (North end of Australasia Building) #1  
 MAIN SIZE 4" & 8" inch  
 STATIC PRESSURE 56 psi

NUMBER OF OUTLETS & ORIFICE SIZE PITOT PRESSURE FLOW (U.S.G.P.M.) RESIDUAL PRESSURE

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	41	525	46
#2	1 X 2 1/2"	26	852	40
#3	2 X 2 1/2"	16	1336	36
#4				



COMMENTS FLOW TEST - BLUE

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo

DATE Dec 21/98

LOCATION 3101A Old Finch Ave

TEST DATA

TIME OF TEST 9:00am


LOCATION OF TEST: (FLOW) Hydrant (East side of garage) #18

(RESIDUAL) Hydrant (West end of north service) #19

MAIN SIZE 6 inch

STATIC PRESSURE 50 psi

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 x 1 3/4"	40	518	45
#2	1 x 2 1/2"	23	800	28
#3	2 x 2 1/2"	11	1108	25
#4				



COMMENTS Flow test - GREEN

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]




A-1 HYDRANT SERVICES LTD. 550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 21/98  
LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST 11:00am  
LOCATION OF TEST (FLOW) Hydrant (N/E of Special Events Tent) #12  
(RESIDUAL) 3/4 hose bib (Siberian Tiger building) ♀  
MAIN SIZE 4" inch  
STATIC PRESSURE 50 psi

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S G P M)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	44	544	47
#2	1 X 2 1/2"	40	1056	45
#3	2 X 2 1/2"	26	1703	42
#4				



COMMENTS FLOW TEST - BLUE

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo

DATE Dec 21/98

LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST: 11:30 am


LOCATION OF TEST: (FLOW) Hydrant (West of ~~North American~~ McDonald's) #10  
(RESIDUAL) Hydrant (North of North American Pavilion) #11

MAIN SIZE: 8" inch

STATIC PRESSURE: 55 psi

NUMBER OF OUTLETS & ORIFICE SIZE    PITOT PRESSURE    FLOW (U.S.G.P.M.)    RESIDUAL PRESSURE

NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1 1 X 1 3/4"	52	591	50
#2 1 X 2 1/2"	46	1133	40
#3			
#4			



COMMENTS: Unable to flow 2 X 2 1/2" inch due to surroundings. - FLOW TEST - [Signature]

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD. 550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665


SITE NAME Toronto Metro Zoo DATE Dec 21/98  
LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST 12:00 pm  
LOCATION OF TEST: (FLOW) Hydrant (Outside holding area) #9  
(RESIDUAL) Hydrant (South end of main temple) #8  
MAIN SIZE 6" x 4" inch  
STATIC PRESSURE 56 psi

NUMBER OF OUTLETS & ORIFICE SIZE PITOT PRESSURE FLOW (U.S.G.P.M.) RESIDUAL PRESSURE

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	9	246	50
#2	1 X 2 1/2"	5	373	48
#3	2 X 2 1/2"	3	578	46
#4				



COMMENTS FLOW TEST - FLOW HYDRANT - RED  
RES. HYDRANT - BLUE OR GREEN

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 21/98

LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST 1:00 pm


LOCATION OF TEST: (FLOW) Hydrant (NW of Africom M<sup>o</sup>Donald's) #7  
(RESIDUAL) Hydrant (South of Africom M<sup>o</sup>Donald's) #6

MAIN SIZE 6 inch

STATIC PRESSURE: 35 psi

NUMBER OF OUTLETS & ORIFICE SIZE    PITOT PRESSURE    FLOW (U.S.G.P.M.)    RESIDUAL PRESSURE

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	34	478	28
#2	1 X 2 1/2"	32	945	25
#3	2 X 2 1/2"	20	1494	20
#4				



COMMENTS Flow TEST - OK

Authorized Signature \_\_\_\_\_

A-1 HYDRANT Signature \_\_\_\_\_




A-1 HYDRANT SERVICES LTD. 550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 21/98  
LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST: 1:45 pm  
LOCATION OF TEST: (FLOW) Hydrant (Outside gorilla door) #4  
(RESIDUAL) Hydrant (West side of African Pavilion) #5  
MAIN SIZE 10" inch  
STATIC PRESSURE: 40

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	32	46.3	32
#2	1 X 2 1/2"	27	86.8	20
#3	2 X 2 1/2"	15	129.4	28
#4				



COMMENTS FLOW TEST - CR. 106 / CRP. 10

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]





A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo

DATE Dec 21/98

LOCATION 3614 Old Finch Ave

TEST DATA

TIME OF TEST 3:50 pm


LOCATION OF TEST: (FLOW) Hydrant (West of Indian Pines building) #1

(RESIDUAL) 3/4" hose bib (Inside Indian Pines building) #4

MAIN SIZE 6" inch

STATIC PRESSURE 60 psi

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	46	556	47
#2	1 X 2 1/2"	30	914	30
#3				
#4				



COMMENTS Flow TEST - GREEN!

Authorized Signature \_\_\_\_\_ A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME

Toronto Metro Zoo

DATE

Dec 23/98

LOCATION

361A Old Finch Ave

TEST DATA

TIME OF TEST

10:30am

LOCATION OF TEST (FLOW)

Hydrant (North American Domain) #22

(RESIDUAL)

Hydrant (South of Old Metagaska Restaurant) #21

MAIN SIZE


4" inch

STATIC PRESSURE

46 psi

NUMBER OF OUTLETS & ORIFICE SIZE    PITOT PRESSURE    FLOW (U.S.G.P.M.)    RESIDUAL PRESSURE

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	33	471	44
#2	1 X 2 1/2"	12	580	40
#3	2 X 2 1/2"	6	820	38
#4				



COMMENTS

FLOW TEST - FLOW HYD - ORANGE

RES HYD - GREEN BUVE

Authorized Signature

A-1 HYDRANT Signature



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 23/98

LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST 8:45am


LOCATION OF TEST (FLOW) Hydrant (East of Society) # 26

(RESIDUAL) Hydrant (South of Society) # 27

MAIN SIZE 6" inch

STATIC PRESSURE 60 psi

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	54	602	52
#2	1 X 2 1/2"	54	1230	42
#3				
#4				



COMMENTS FLOW TEST - BLUE.

Authorized Signature \_\_\_\_\_

A-1 HYDRANT Signature \_\_\_\_\_



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 23/98

LOCATION 361A Old Finch Ave

TEST DATA

TIME OF TEST 10:00am


LOCATION OF TEST: (FLOW) Hydrant (North of Cheetah Building) #24

(RESIDUAL) Hydrant (New Savana Restaurant) #23

MAIN SIZE 4" inch

STATIC PRESSURE 38 psi

	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U S G P M)	RESIDUAL PRESSURE
#1	1 X 1 3/4"	26	417	30
#2	1 X 2 1/2"	14	626	24
#3	2 X 2 1/2"	9	1004	29
#4				



FLOW U.S. G.P.M.

COMMENTS FLOW TEST - FLOW HYD - ORANGE

Authorized Signature \_\_\_\_\_

A-1 HYDRANT Signature [Signature]



A-1 HYDRANT SERVICES LTD.

550 Coronation Dr., Unit #18  
Scarborough, Ont. M1E 4V1  
282-1665

SITE NAME Toronto Metro Zoo DATE Dec 21/98

LOCATION 3161A Old Finch Ave

TEST DATA

TIME OF TEST 9:20 am


LOCATION OF TEST (FLOW) Hydrant (N/E of north service) #17

(RESIDUAL) Hydrant (S/E of north service) #16

MAIN SIZE 8" inch

STATIC PRESSURE 50 psi


	NUMBER OF OUTLETS & ORIFICE SIZE	PITOT PRESSURE	FLOW (U.S.G.P.M.)	RESIDUAL PRESSURE
#1	1 x 1 3/4"	41	525	46
#2	1 x 2 1/2"	34	974	36
#3	2 x 2 1/2"	28	1767	30
#4				



COMMENTS Flow Test - BLUE

Authorized Signature \_\_\_\_\_

A-1 HYDRANT Signature \_\_\_\_\_



**A-1 HYDRANT SERVICES LTD.**

550 Coronation Dr., Unit # 18  
Scarborough, On. M1E 4V1  
TEL: (416) 282-1665  
FAX: (416) 282-7702  
1-888-FIX-A-HYD

Metro Toronto Zoo c/o  
Paradigm Engineering Ltd.  
1300 Don Mills Road, Suite 235,  
North York, ON  
M3B 2W6

Attention: Mr. Doug Shields  
416-444-5211  
416-444-9222

INVOICE#: H9159-1  
DATE: December 30/98  
Customers#: D.Shields  
OUR JOB#: H9159  
G.S.T. #: R100371152  
P.S.T.#: 85685569  
TERMS: NET 15 DAYS

DESCRIPTION	AMOUNT	TOTAL
-------------	--------	-------

LOCATION: Metro Toronto Zoo

To bill for the following:

12 flow tests at \$75.00 each	900.00	
29 hydrant a.p.m.'s at \$40.00 each	<u>1,160.00</u>	
	2,060.00	
	G.S.T.	144.20
<b>TOTAL AMOUNT DUE:</b>		<b>\$ 2,204.20</b>

**APPENDIX 8**

**GAS TEST RESULTS**





**Trade Gas Services (Toronto) Ltd.**  
 29 Golden Gate Court  
 SCARBOROUGH, ONTARIO M1P 3A4



**INVOICE**

4204

(416) 293-6742 Fax (416) 293-6765  
 GST #R105339410

TO

PARADIGM ENGINEERING GROUP INC.  
 1300 Don Mills Road, Suite 235  
 North York, Ont. M3B 2W6

DATE Jan 5, 1999 JOB NO. \_\_\_\_\_  
 JOB NAME Metro Zoo  
 JOB LOCATION \_\_\_\_\_

QUANTITY	DESCRIPTION	PRICE	AMOUNT
	Test checked gas supply lines as requested by Paradigm Engineering Group Inc.		
	<u>Indo-Malaya Pavilion #1 Test</u>		
	To determin the static pressure and working pressure at three points (branch lines) of the gas service.		
	11 M meter with Fisher Type 133L-3 Reg.		
	Max inlet 60 P.S.I.		
	Max outlet 2 P.S.I.		
	2 - National Champion Furnaces 4,350,000 each.		
	1 - Pool heater Hayward H-250 250,000 BTU each		
	1 - DHW Aerco heater 1,000,000 BTU each		
	1 - Pool heater Hayward H-150 150,000 BTU each		
	Shut off each appliance, shut gas valve at meter and tested pressure + 43 P.S.I.		
	Shut off appliances, shut gas, removed gage and started appliances again.		
	<u>North Main Service Bldg. #2 Test.</u>		
	7 M meter with Fisher type S203 Reg. 3/4" Orf.		
	1 - Eng. Air HE40 (Paint Shop) 250,000 BTU each		
	2 - Teledyne Laars HB-3000 3,000,000 BTU each		
	2 - Teledyne Laars HB-3500 3,500,000 BTU each		
	4 - Rheem Ruud RF76-Z50C (DHW) 250,000 BTU each		
	2 - Rheem Ruud PV40-36M (DHW) 36,000 BTU each		
	Shut off each appliance, shut off gas valve at meter		
TERMS:		SUBTOTAL	
Cont.....		GST	
		PST	
		TOTAL	

THANK YOU

**Grade Gas Services (Toronto) Ltd.**

29 Golden Gate Court  
SCARBOROUGH, ONTARIO M1P 3A4

**INVOICE**

~~110555~~

(416) 293-6742 Fax (416) 293-6765  
GST #R105339410

INVOICE # 4204

TO

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

DATE \_\_\_\_\_ JOB NO. \_\_\_\_\_  
JOB NAME \_\_\_\_\_  
JOB LOCATION \_\_\_\_\_

QUANTITY	DESCRIPTION	PRICE	AMOUNT
	and tested static pressure = 44 P.S.I.		
	Started appliances and tested working pressure = 40 P.S.I.		
	Shut off appliances, shut gas at meter and removed gage.		
	Opened gas at meter and relit pilots.		
	Started appliances up again.		
	<u>Consumers Gas Main Station #3 Test.</u>		
	Removed plug on test point at station.		
	Installed gage and checked pressure = 44 P.S.I.		
	Removed gage and installed plug.		

**APPENDIX 9**

**WATER TEST RESULTS**



**APPENDIX 10**

**SANITARY SEWER TEST RESULTS  
(PRINT)**



Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: NONE GIVEN


DATE: Jan 26 1999  
TIME: 09:11:07

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 375mm  
FLOW DIR: North

REF. AREA: WO #1685  
FILE NAME: TVI91773.RPT  
TAPE COUNT: 00:00:00  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: Against Flow

=====

STARTING LOCATION: 3RD MH N OF THE INDO PAVILLION PIPE DEPTH:4.0m	ENDING LOCATION: 2ND MH N OF THE INDO PAVILLION PIPE DEPTH:N/A-NO ACCESS
---	--



=====

Summary Comments

LIGHT DEBRIS UNDER THE FLOW.

Distance	Inspection Comments
At        To	
0.0	Starting manhole - 03
1.5	Moderate steam hampering inspection
32.0	Ending manhole - 02
32.0	End of inspection

Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: NONE GIVEN


DATE: Jan 26 1999  
TIME: 09:40:11

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 375mm  
FLOW DIR: North

REF. AREA: WO #1685  
FILE NAME: TVI91774.RPT  
TAPE COUNT: 00:02:25  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: Against Flow

=====

STARTING LOCATION: 2ND MH N OF THE INDO PAVILLION PIPE DEPTH:N/A-NO ACCESS	ENDING LOCATION: 1ST MH N OF THE INDO PAVILLION PIPE DEPTH:N/A-NO ACCESS
--	--



=====

Summary Comments

EXTRA MH NOT SHOWN ON THE MAP.LIGHT  
DEBRIS IN THE LINE.

Distance			Inspection Comments
At	To		
0.0			Starting manhole - 02
0.0	7.0		Light debris in line - Invert
7.0			Extra manhole not shown
63.6			Ending manhole - 01
63.5			Ending manhole - 01
63.5			End of inspection



Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: NONE GIVEN

DATE: Jan 26 1999  
TIME: 10:14:35

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 200mm  
FLOW DIR: West

REF. AREA: WO #1685  
FILE NAME: TVI91775.RPT  
TAPE COUNT: 00:06:50  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: Against Flow

=====  
STARTING LOCATION: EAST OF THE OLD ELEPHANT HOUSE  
PIPE DEPTH: 3.4m  
ENDING LOCATION: FENCE LINE OF OLD ELELPHNT HOUSE  
PIPE DEPTH: N/A-NO ACCESS  
=====

STARTING MANHOLE	CAMERA DIRECTION >	ENDING MANHOLE
04	TOTAL: 51.0 Metres	05
	FLOW DIRECTION <	

=====  
Summary Comments

LIGHT CALCITE AT A SERVICE CONNECTION.

Distance	Inspection Comments
At	To
0.0	Starting manhole - 04
3.4	Light calcite at service connection - 2 O'clock
51.0	Ending manhole - 05
51.0	End of inspection

Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT


CLIENT: METRO TORONTO ZOO.  
STREET: NONE GIVEN

DATE: Jan 26 1999  
TIME: 10:36:17

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 200mm  
FLOW DIR: West

REF. AREA: WO #1685  
FILE NAME: TVI91776.RPT  
TAPE COUNT: 00:12:55  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: Against Flow

=====  
STARTING LOCATION: FENCE LINE OF OLD ELEPHANT HOUSE  
ENDING LOCATION: ELEPHANT WATERING HOLE  
PIPE DEPTH:N/A-NO ACCESS PIPE DEPTH:N/A-NO ACCESS  
=====



=====  
Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance	Inspection Comments
At	To
0.0	Starting manhole - 05
66.0	Ending manhole - 06
66.0	End of inspection

Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: NONE GIVEN


DATE: Jan 26 1999  
TIME: 10:43:06

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 200mm  
FLOW DIR: West

REF. AREA: WO #1685  
FILE NAME: TVI91777.RPT  
TAPE COUNT: 00:17:10  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: Against Flow

STARTING LOCATION:  
ELEPHANT WATERING HOLE  
PIPE DEPTH:N/A-NO ACCESS

ENDING LOCATION:  
BUSH CAMP  
PIPE DEPTH:N/A-NO ACCESS



Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance	Inspection Comments
At	To
0.0	Starting manhole - 06
70.0	Ending manhole - 07
70.0	End of inspection

Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: MAIN PARKING LOT "P" SECTION


DATE: Jan 26 1999  
TIME: 11:50:34

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 525mm  
FLOW DIR: East

REF. AREA: WO #1685  
FILE NAME: TVI91778.RPT  
TAPE COUNT: 00:21:55  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: With Flow

STARTING LOCATION:  
2ND MH E OF THE RIVER  
PIPE DEPTH:5.3m

ENDING LOCATION:  
1ST MH E OF THE RIVER  
PIPE DEPTH:N/A-NO ACCESS



Summary Comments

LIGHT DEBRIS UNDER THE FLOW.

Distance	Inspection Comments
At	To
0.0	Starting manhole - 08
92.5	Ending manhole - 09
92.5	End of inspection

Trans-Video Inspection Limited  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: MAIN PARKING LOT "P" SECTION

DATE: Jan 26 1999  
TIME: 12:26:58

INSP. BY: F.H.  
DISK No: 01FH  
TAPE No: 01FH  
PIPE SIZE: 525mm  
FLOW DIR: East

REF. AREA: WO #1685  
FILE NAME: TVI91779.RPT  
TAPE COUNT: 00:26:05  
PIPE TYPE: SANITARY/AC  
CAMERA DIR: With Flow

STARTING LOCATION:  
1ST MH E OF THE RIVER  
PIPE DEPTH:N/A-NO ACCESS

ENDING LOCATION:  
1ST MH W OF THE RIVER  
PIPE DEPTH:N/A-NO ACCESS

CAMERA DIRECTION ---->	
STARTING MANHOLE	ENDING MANHOLE
09	10
TOTAL: 81.0 Metres	
FLOW DIRECTION ---->	

Summary Comments

LIGHT DEBRIS UNDER THE FLOW.

Distance	Inspection Comments
At	To
0.0	Starting manhole - 09
81.0	Ending manhole - 10
81.0	End of inspection



**APPENDIX 11**

**SANITARY SEWER TEST RESULTS  
(VIDEO)**





**APPENDIX 12**

**STORM SEWER TEST RESULTS (PRINT)**



Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: "D" GATE SOUTH OF OLD PINCH RD


DATE: Feb 5 1999  
TIME: 08:22:26

INSP. BY: P.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 675mm  
FLOW DIR: South

REP. AREA:  
FILE NAME: TVI90517.RPT  
TAPE COUNT: 00:00:00  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

=====

STARTING LOCATION: NORTH OF GATE "D" PIPE DEPTH:2.5m	ENDING LOCATION: SOUTH OF GATE "D" PIPE DEPTH:N/A
--	---



=====

**Summary Comments**

PONDING AND DEBRIS IN THE LINE.HEAVY  
CALCITE BELOW A SERVICE CONNECTION.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 01
1.5	48.4	Moderate ponding in line
4.9	9.1	Moderate debris in line - Invert
9.1		Service connection - 11 O'clock
9.1		Service protruding greater than 1" - 2 O'clock
14.2	58.2	Moderate debris in line - Invert
26.0		Service connection - 11 O'clock
26.0	26.0	Heavy calcite in line - 8 O'clock
26.9		Service connection - Crown
36.8		Service connection - 11 O'clock
48.4		Service connection - 1 O'clock
59.5		Ending manhole - 02
59.5		End of inspection

Report generated by Ratch Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT


CLIENT: METRO TORONTO ZOO.  
STREET: "D" GATE SOUTH OF OLD FINCH RD

DATE: Feb 5 1999  
TIME: 09:11:29

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 675mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90518.RPT  
TAPE COUNT: 00:06:05  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION: SOUTH OF GATE "D"  
PIPE DEPTH:N/A  
ENDING LOCATION: 2ND MH S OF OF "D" GATE  
PIPE DEPTH:N/A



Summary Comments

LIGHT PONDING IN THE LINE.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 02
1.1		Service connection - 11 O'clock
6.7		Service connection - 11 O'clock
6.7	13.7	Light ponding in line
15.1		Service connection - Crown
17.6		Service connection - Crown
23.7		Service connection - 2 O'clock
31.2		Service connection - 11 O'clock
46.0		Ending manhole - 03
46.0		End of inspection

Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: "D" GATE SOUTH OF OLD FINCH RD


DATE: Feb 5 1999  
TIME: 09:19:08

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 675mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90519.RPT  
TAPE COUNT: 00:10:50  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION:  
2ND MH S OF OF "D" GATE  
PIPE DEPTH:N/A

ENDING LOCATION:  
3RD MH S OF OF "D" GATE  
PIPE DEPTH:N/A



Summary Comments

MH LID IN THE ENDING MH.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 03
19.6	38.3	Light ponding in line
40.0		MH LID IN THE
40.0		Ending manhole - 04
40.0		End of inspection

-----  
Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: "D" GATE SOUTH OF OLD FINCH RD


DATE: Feb 5 1999  
TIME: 09:38:42

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 675mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90520.RPT  
TAPE COUNT: 00:10:50  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

=====

STARTING LOCATION: 2ND MH S OF OF "D" GATE PIPE DEPTH:N/A	ENDING LOCATION: 3RD MH S OF OF "D" GATE PIPE DEPTH:N/A
---	---



-----  
**Report generated by Ratech Data Tech V Sewer TV Inspection System**

**Trans-Video Inspection Ltd.  
 SEWER TV. INSPECTION REPORT**

**CLIENT: METRO TORONTO ZOO.  
 STREET: AREA B**


**DATE: Feb 5 1999  
 TIME: 09:39:24**

**INSP. BY: F.H.  
 DISK No: 02FH  
 TAPE No: 02FH  
 PIPE SIZE: 600mm  
 FLOW DIR: East**

**REF. AREA:  
 FILE NAME: TVI90521.RPT  
 TAPE COUNT: 00:13:25  
 PIPE TYPE: STORM/CONC  
 CAMERA DIR: Against Flow**

=====  
**STARTING LOCATION:  
 1ST MH W OF EURASIA PAV.  
 PIPE DEPTH: 3.3m**

**ENDING LOCATION:  
 N OF NORTH AMERICAN PAV.  
 PIPE DEPTH: N/A**



=====  
**Summary Comments**

**LIGHT DEBRIS AND PONDING IN THE LINE.**

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 05
33.1	60.9	Light debris in line - Invert
35.5		Service connection - 9 O'clock
54.4		Service connection - 10 O'clock
60.9	65.4	Moderate ponding in line
67.0		Ending manhole - 06
67.0		End of inspection

-----  
Report generated by Ratch Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 8

DATE: Feb 5 1999  
TIME: 09:52:20


INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 675mm  
FLOW DIR: East

REF. AREA:  
FILE NAME: TVI90522.RPT  
TAPE COUNT: 00:18:20  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

=====

STARTING LOCATION:  
1ST MH W OF EURASIA PAV.  
PIPE DEPTH: 3.3m

ENDING LOCATION:  
@ EURASIA PAV.  
PIPE DEPTH: N/A



=====

Summary Comments

LIGHT PONDING AND DEBRIS IN THE LINE.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 05
1.5	19.0	Light ponding in line
8.7	19.8	Moderate debris in line - Invert
46.4		Service connection - 2 O'clock
67.5		Internal drop in pipe
70.0		Ending manhole - 07
70.0		End of inspection



Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 8


DATE: Feb 5 1999  
TIME: 10:19:52

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 900mm  
FLOW DIR: East

REF. AREA:  
FILE NAME: TVI90523.RPT  
TAPE COUNT: 00:18:20  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION:  
8 URASIA PAV.  
PIPE DEPTH:3.6m

ENDING LOCATION:  
EAST OF MH 07  
PIPE DEPTH:N/A



Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance	Inspection Comments
At To	
0.0	Starting manhole - 07
3.3	Service connection - 10 O'clock
8.9	Service connection - 2 O'clock
24.0	Service connection - 3 O'clock
27.9	Service connection - 10 O'clock
74.0	Ending manhole - 08
74.0	End of inspection

Report generated by Rotech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 8


DATE: Feb 5 1999  
TIME: 10:27:06

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 900mm  
FLOW DIR: East

REF. AREA:  
FILE NAME: TVI90524.RPT  
TAPE COUNT: 00:26:55  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION:  
EAST OF MH 07  
PIPE DEPTH:N/A

ENDING LOCATION:  
EAST OF MH 08  
PIPE DEPTH:N/A



Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance	Inspection Comments
At To	
0.0	Starting manhole - 08
21.5	Service connection - 2 O'clock
103.9	Service protruding greater than 1" - 1 O'clock
134.0	Ending manhole - 09
134.0	End of inspection

-----  
Report generated by Ratch Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 17


DATE: Feb 5 1999  
TIME: 12:02:36

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 450mm  
FLOW DIR: S/W

REF. AREA:  
FILE NAME: TVI90525.RPT  
TAPE COUNT: 00:33:25  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow

=====

STARTING LOCATION: S OF THE SAV. REST. S/S OF ROAD PIPE DEPTH:N/A	ENDING LOCATION: W/E OF MH 10 PIPE DEPTH:N/A
---	--



=====

Summary Comments

THE CAMERA WAS BLOCKED BY HEAVY GRAVEL.  
REVERSE SETUP WAS NOT REQUESTED.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 10
1.5	9.8	Light debris in line - Invert
4.2		Service connection - 2 O'clock
9.8	29.3	Moderate debris in line - Invert
27.8		Service connection - 2 O'clock
28.7		Service connection - 9 O'clock
29.3	29.3	Heavy debris in line - Invert
29.3		Camera blocked in line
29.3		End of inspection

-----  
Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 17


DATE: Feb 5 1999  
TIME: 12:14:58

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 450mm  
FLOW DIR: West

REF. AREA:  
FILE NAME: TVI90526.RPT  
TAPE COUNT: 00:38:05  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

=====

STARTING LOCATION: S OF THE SAV. REST. S/S OF ROAD PIPE DEPTH:N/A	ENDING LOCATION: WEST OF MH 10 PIPE DEPTH:N/A
---	---



=====

Summary Comments

THE CAMERA WAS BLOCKED BY DEBRIS.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 10
23.3	50.0	Light ponding in line
27.9	50.0	Light debris in line - Invert
50.0		Camera blocked in line
50.0		End of inspection

-----  
Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18


DATE: Feb 5 1999  
TIME: 13:20:43

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 525mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90527.RPT  
TAPE COUNT: 00:43:10  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow

=====

STARTING LOCATION: S/E CORNER OF THE ELEPHANT HOUSE PIPE DEPTH: 3.6m	ENDING LOCATION: S/E OF AFRICAN PAVILLION PIPE DEPTH: N/A
--	---



=====

Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 13
23.2		Service connection - 9 O'clock
26.7		Service connection - 11 O'clock
42.5		Ending manhole - 14
42.5		End of inspection

Report generated by Ratach Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18


DATE: Feb 5 1999  
TIME: 13:29:01

INSP. BY: P.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 525mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90528.RPT  
TAPE COUNT: 00:46:10  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow

STARTING LOCATION:  
S/E OF THE AFRICAN PAV.  
PIPE DEPTH:N/A

ENDING LOCATION:  
EAST ENTRANCE AFRICAN PAV.  
PIPE DEPTH:N/A



Distance		Inspection Comments
At	To	
0.0		Starting manhole - 14
18.0		Service connection - 2 O'clock
20.2		Service protruding greater than 1" - 9 O'clock
20.2		Camera blocked in line
20.2		End of inspection

**Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT**

**CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18**


**DATE: Feb 5 1999  
TIME: 13:36:11**

**INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 525mm  
FLOW DIR: East**

**REF. AREA:  
FILE NAME: TVI90529.RPT  
TAPE COUNT: 00:48:20  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow**

=====

<b>STARTING LOCATION:</b> S/E CORNER OF THE ELEPHANT HOUSE PIPE DEPTH:3.6m	<b>ENDING LOCATION:</b> S/W CORNER OF THE AFRICAN PAV. PIPE DEPTH:N/A
--	---



=====

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18


DATE: Feb 5 1999  
TIME: 13:38:34

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 525mm  
FLOW DIR: East

REF. AREA:  
FILE NAME: TVI90530.RPT  
TAPE COUNT: 00:48:20  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow

=====

STARTING LOCATION: S/E CORNER OF THE ELEPHANT HOUSE PIPE DEPTH:3.6m	ENDING LOCATION: S/W CORNER OF THE AFRICAN PAV. PIPE DEPTH:N/A
---	--



=====

Summary Comments

THE CAMERA WAS BLOCKED BY DEBRIS.REVERSE  
SETUP IS REQUESTED.UNABLE TO GIVE THE  
SURFACE LENGTH,THERE ARE BUILDING IN  
BETWEEN THE MH'S

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 13
1.5	31.2	Moderate debris in line - Invert
31.2		Camera blocked in line
31.2		End of inspection



**Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT**


**CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18**

**DATE: Feb 5 1999  
TIME: 13:52:21**

**INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 450mm  
FLOW DIR: East**

**REF. AREA:  
FILE NAME: TVI90531.RPT  
TAPE COUNT: 00:52:50  
PIPE TYPE: STORM/PVC  
CAMERA DIR: With Flow**

=====  
**STARTING LOCATION: S/W CORNER OF THE AFRICAN PAV.  
PIPE DEPTH: N/A**  
**ENDING LOCATION: S/W CORNER OF THE ELEPHANT HOUSE  
PIPE DEPTH: 3.6m**



=====  
**Summary Comments**

**THE PIPE SIZE IS 450mm. THE PIPE MATERIAL IS PVC. DEBRIS IN THE LINE.**

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 16
2.2	51.5	Moderate ponding in line
4.7	51.5	Moderate debris in line - Invert
51.5		Extra manhole not shown
51.5		End of inspection

Report generated by Raintech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT


CLIENT: METRO TORONTO ZOO.  
STREET: AREA 18

DATE: Feb 5 1999  
TIME: 14:03:13

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 525mm  
FLOW DIR: South

REF. AREA:  
FILE NAME: TVI90532.RPT  
TAPE COUNT: 00:55:35  
PIPE TYPE: STORM/CONC  
CAMERA DIR: Against Flow

STARTING LOCATION: S/W CORNER OF THE AFRICAN PAV.  
PIPE DEPTH: N/A  
ENDING LOCATION: 1ST MH N OF MH 16  
PIPE DEPTH: N/A



Summary Comments

THE CAMERA WAS BLOCKED BY DEBRIS. REVERSE  
SETUP WAS NOT REQUESTED.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 16
2.0	20.5	Moderate debris in line - Invert
20.5		Camera blocked in line
20.5		End of inspection

Report generated by Database Data Tech W Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA ?


DATE: Feb 5 1999  
TIME: 14:38:38

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 250mm  
FLOW DIR: West

REF. AREA:  
FILE NAME: TV190533.RPT  
TAPE COUNT: 00:57:20  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION:  
1ST MH W OF THE CAMEL PEN  
PIPE DEPTH:2.1m

ENDING LOCATION:  
2ND MH W OF THE CAMEL PEN  
PIPE DEPTH:N/A



Summary Comments

DEBRIS IN THE LINE.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 19
0.0	11.0	Moderate debris in line - Invert
11.0		Ending manhole - 19
11.0		End of inspection

Report generated by Rotech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT

CLIENT: METRO TORONTO ZOO.  
STREET: AREA ?


DATE: Feb 5 1999  
TIME: 14:45:04

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 300mm  
FLOW DIR: West

REF. AREA:  
FILE NAME: TVI90534.RPT  
TAPE COUNT: 00:59:00  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION:  
2ND MH W OF THE CAMEL PEN  
PIPE DEPTH: N/A

ENDING LOCATION:  
3RD MH W OF THE CAMEL PEN  
PIPE DEPTH: N/A



Summary Comments

THE PIPE APPEARS TO BE IN GOOD CONDITION

Distance At	To	Inspection Comments
0.0		Starting manhole - 19
1.1		Service connection - 9 O'clock
46.5		Ending manhole - 20
46.5		End of inspection

Report generated by Ratch Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT


CLIENT: METRO TORONTO ZOO.  
STREET: AREA ?

DATE: Feb 5 1999  
TIME: 14:49:40

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 375mm  
FLOW DIR: West

REF. AREA:  
FILE NAME: TVI90535.RPT  
TAPE COUNT: 01:02:10  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION: 3RD MH W OF THE CAMEL PEN  
ENDING LOCATION: 4TH MH W OF THE CAMEL PEN  
PIPE DEPTH: N/A



Summary Comments

THE MAP IS WRONG SUPOSED TO MEET WITH  
MH 08. NOT THE CASE.

Distance		Inspection Comments
At	To	
0.0		Starting manhole - 20
5.2		Service connection - 2 O'clock
9.5		Service connection - 9 O'clock
23.8		Service connection - 10 O'clock
31.8	55.0	Light ponding in line
38.0		Service connection - Crown
38.0	38.0	Moderate calcite in line - Around pipe
55.0		Ending manhole - 21
55.0		End of inspection

Report generated by Ratech Data Tech V Sewer TV Inspection System

Trans-Video Inspection Ltd.  
SEWER TV. INSPECTION REPORT


CLIENT: METRO TORONTO ZOO.  
STREET: AREA ?

DATE: Feb 5 1999  
TIME: 14:57:35

INSP. BY: F.H.  
DISK No: 02FH  
TAPE No: 02FH  
PIPE SIZE: 375mm  
FLOW DIR: West

REF. AREA:  
FILE NAME: TVI90536.RPT  
TAPE COUNT: 01:07:35  
PIPE TYPE: STORM/CONC  
CAMERA DIR: With Flow

STARTING LOCATION: 4TD MH W OF THE CAMEL PEN  
ENDING LOCATION: 5TH MH W OF THE CAMEL PEN



Summary Comments

THE CAMERA WAS UNABLE TO MAKE THE BEND  
IN THE MH.

Distance	Inspection Comments
At To	
0.0	Starting manhole - 21
0.0	CAMERA NOT ABLE TO MAKE THE BEND
0.0	Camera blocked in line
0.0	End of inspection

**APPENDIX 13**

**STORM SEWER TEST RESULTS (VIDEO)**





**APPENDIX 14**

**COMPONENT QUANTITY TAKE-OFFS**



**SITE SERVICES COMPONENTS  
QUANTITY TAKE-OFF**

	Totals	Area 1	Area 2	Area 3	Area 4	Area 5	Area 6	Area 7	Area 8	Area 9	Area 10	Area 11	Area 12
<b>Water</b>													
1. Fire Hydrant	28		1	5					6	1			1
2. Gate Valves	5		3	12	3			4	20	10			1
3. Main Valve	95				2				2	3			7
4. Drinking Fountain	18			2	2			1	7	5			1
5. Building Valves	39			1	2				3	1			3
6. Man Holes	5			1					3	1			
7. Main Sprinkler Building Valve	1		1										
8. Non Freeze Hydrant	9		1					1	2	6			
9. Pumping Stations	1							1					
10. Pool Valve/Water Tap	8				6					2			3
11. Curb Stop	50		1	1	1				4	14			5
12. Curb Stop/Bldg. Valve	1			1	1								
13. Water Bowl	8			2					5				
14. Sprinklers	2												
15. Water Main Chamber	1												
16. Water Spray Post	1												
<b>Gas</b>													
1. Gas Valves	3			2									
2. Building Valve	1												
<b>Sanitary/Storm</b>													
1. Area Drains	4												
2. Clean Outs	5								2				
3. Catch Basins	275		2	46	15	10		2	27	17	11		23
4. Man Holes	328		2	36	24	3		12	33	35	10		25
5. Pool Drains	1												1
6. Pumping Stations	4			1	1				1	1			
7. Catch Basin/Man Hole	1										1		
8. Floor Drain	2								2				
<b>Electrical</b>													
1. Electrical Panels	3		1					1	1				
2. Hydro Outlet	7									4			
3. Light Standards	33												
4. Hydro Vault (transformer)	27		1	2				1	3	7			3
5. Transformer	49												
6. Electrical Man Holes	1												
7. Junction Boxes	14												
8. Elec. Post	2				1				1				

SITE SERVICES COMPONENTS  
QUANTITY TAKE-OFF

	Area 13	Area 14	Area 15	Area 16	Area 17	Area 18	Area 19	Area 20	Area 21	Area 22	Area 23
<b>Water</b>											
1. Fire Hydrant	5	1				7		1			
2. Gate Valves	4										
3. Main Valve	11	2			12	10					1
4. Drinking Fountain	1	4			3	2					
5. Building Valves	5	2			7	5					
6. Man Holes											
7. Main Sprinkler Building Valve											
8. Non Freeze Hydrant						1					
9. Pumping Stations											
10. Pool Valve/Water Tap		1				2					
11. Curb Stop	5	7			4	3					
12. Curb Stop/Bldg. Valve											
13. Water Bowl											
14. Sprinklers							2				
15. Water Main Chamber											
16. Water Spray Post											
<b>Gas</b>											
1. Gas Valves	1										
2. Building Valve											
<b>Sanitary/Storm</b>											
1. Area Drains						4					
2. Clean Outs					3						
3. Catch Basins	22	27			25	30	16				2
4. Man Holes	27	13			40	48	12				8
5. Pool Drains											
6. Pumping Stations											
7. Catch Basin/Man Hole											
8. Floor Drain											
<b>Electrical</b>											
1. Electrical Panels											
2. Hydro Outlet		3									
3. Light Standards		14									
4. Hydro Vault (transformer)	2				3	5	19				
5. Transformer											
6. Electrical Man Holes										1	
7. Junction Boxes										7	
8. Elec. Post											

**SITE SERVICES COMPONENTS  
QUANTITY TAKE-OFF**

	Area 24	Area 25
<b>Water</b>		
1. Fire Hydrant		
2. Gate Valves		
3. Main Valve		
4. Drinking Fountain		
5. Building Valves		
6. Man Holes		
7. Main Sprinkler Building Valve		
8. Non Freeze Hydrant		
9. Pumping Stations		
10. Pool Valve/Water Tap		
11. Curb Stop		
12. Curb Stop/Bldg. Valve		
13. Water Bowl		
14. Sprinklers		
15. Water Main Chamber	1	
16. Water Spray Post		
<b>Gas</b>		
1. Gas Valves		
2. Building Valve		
<b>Sanitary/Storm</b>		
1. Area Drains		
2. Clean Outs		
3. Catch Basins		
4. Man Holes		
5. Pool Drains		
6. Pumping Stations		
7. Catch Basin/Man Hole		
8. Floor Drain		
<b>Electrical</b>		
1. Electrical Panels		
2. Hydro Outlet		
3. Light Standards		
4. Hydro Vault (transformer)		
5. Transformer		
6. Electrical Man Holes		
7. Junction Boxes		
8. Elec. Post		



**APPENDIX 15**

**CITY OF SCARBOROUGH FIRE  
PROTECTION WATER SERVICES  
POLICY**





Thomas L. Powell, Fire Chief  
Guidelines for Water Services for Fire Protection  
February 26, 1992

E) Minimum size of water supply:

1. A single private hydrant only - 6" (150mm);
2. A single private hydrant and sprinklers and/or standpipes - 8" (200mm) to the hydrant or to the sprinklers/standpipe, 6" (150mm) to the rest. Alternatively hydraulic calculations proving the required water supply.
3. Two private hydrants - 8" (200mm). Alternatively hydraulic calculations proving the required water supply.
4. More than two private hydrants - 8" (200mm). Looped system required. (N.B. Main size may be reduced if hydraulic calculations are submitted proving the required water supply.)

Note: Scarborough Public Utilities Commission requirements for domestic water supply taken within building from same water service as the fire protection systems:

1. A 1" domestic supply may be taken from a 6" (150mm) service;
2. A 2" domestic supply may be taken from an 8" (200mm) service;
3. Alternatively hydraulic calculations proving the required water supply for both the fire protection system(s) and the domestic system.

S.P.U.C.

James C. Macdon  
Director  
Fire Prevention D

412-4526

JCM/vs

LOUIS MAGURNO

File #SP130992.J

292-1530 E.Y.T. 20 12

MARIO ZAMMIT 412-4527

RANDALL W. FRANKS 412-4537



**APPENDIX 16**

**CORRESPONDENCE**  
**FROM**  
**ENBRIDGE CONSUMERS GAS**



500 Consumers Road,  
Toronto ON M2J 1P8  
Tel 416 495-5489  
Fax 416 495-6189  
Email brian.black@cg.enbridge.com



**fax**

File Number: \_\_\_\_\_

To: Earnes Onyido	From: Brian Black
Organization: Paradigm Engineering Group	No. of pages (including this cover): 1
Department:	Date: 1999-05-21
Fax: Recipient 416-335-1449	If this transmission is not received in good order, please call: Sender 416-495-5489


Re: Metro Toronto Zoo – Natural Gas Supply and Piping

As I had verbally informed you, The pipe on the property of the Metro Toronto Zoo is owned by the Zoo and does not fall under the jurisdiction of Enbridge Consumers Gas. This means that Enbridge Consumers Gas is only able to provide information regarding the gas that is supplied to the system on the Zoo property.

Concerning the present load which is utilized by the zoo under peak hour conditions as supplied by Enbridge Consumers Gas is 1050 M<sup>3</sup> / Hr at a maximum of 45 psi. This pressure could be boosted to deliver 60 psi to the zoo system. The maximum supply that could be provided using present equipment would be 3000 m<sup>3</sup>/ Hr. This increase however may be limited by the downstream Zoo piping system. An evaluation should be made by the Metro Toronto Zoo to establish whether any increase in capacity delivered by Enbridge Consumers Gas will be acceptable for the zoo's piping system.

As I mentioned previously, there has been no corrosion survey performed on the Zoo's system in approximately the last 12 years. A leak survey however, is completed annually and was completed three weeks ago for 1999. The results of the leak survey identified no leak indications. It is recommended that a corrosion survey be completed by the Metro Toronto Zoo to secure the integrity of the system and identify any upgrades required in the cathodic protection of the plant.

Please contact me if you have any further questions.

  
Brian Black

This teletcopy is intended for the sole use of the person to whom it is addressed and should not be read by, or delivered to, anyone else. It may contain privileged or confidential information, the disclosure of which may result in the breach of certain laws or the infringement of rights of third parties. If you have received this teletcopy in error, please call immediately (collect if necessary) at the number above. We thank you in advance for your cooperation and assistance.



**APPENDIX 17**

**CORRESPONDENCE  
FROM GRAIG ROSE  
OF  
MARSHALL MACKLIN MONAGHAN  
CONSULTING ENGINEERS**





18-93081  
memo to file  
metro toronto zoo

I spoke with Andy Empringham from Scarborough Fire Prevention on Feb. 14 1995. He said that he sent a copy of my Jan. 19 submission to his fire inspector at the City of Scarborough (Steve Doran). He said that they see our design as an improvement to the existing system and will not require the existing mains to be upgraded. He said that he has the final say on this issue and that there was no need for him to provide a letter to me.

Craig Rose

18-93081-03-SU1  
Post-it™ Fax Note 7671E

Date	MAY 19/99	# of pages	2
To	ERNEST ONYIDO		
From	CRAIG ROSE		
Co./Dept	MMM		
Phone #	Phone #		
Fax #	416 3351449	Fax #	



**APPENDIX 18**

**FIRE PROTECTION WATER SUPPLY  
GUIDELINE FOR PART 3  
IN THE ONTARIO BUILDING CODE**



**DRAFT**

Office of the Fire Marshal

OFM-TG-07-98



**FIRE PROTECTION  
WATER SUPPLY  
GUIDELINE FOR PART 3  
IN THE ONTARIO  
BUILDING CODE**

**O**

**F**

**M**

**TECHNICAL  
GUIDELINE**

October 1998

**DRAFT**

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

**TABLE OF CONTENTS**

<b>SECTION</b>	<b>PAGE</b>
Abstract	2
Introduction	3
Overview of the Building Code Requirements	4
Fire Department Response	4
Cost Impact	5
Significant Adverse Environmental Impact	5
Water Supply Requirements:	
1. Buildings Not Requiring an On-site Fire Protection Water Supply	6
2. Sprinklered Buildings	7
3. Buildings Requiring On-Site Fire Protection Water Supply	7
4. Additions to Existing Buildings	8
Table 1 - Water Supply Coefficient -- K	9
Table 2 - Minimum Water Supply Flow Rates	9
Figure 1 - Spatial Coefficient VS Exposure Distance	10
Explaining the Calculations	11
Further Explanation of Guideline Requirements	13
Special Cases	13
Water Supply Adequacy Committee	16
Example Problems	17

June, 1998

OFM Section: Fire Safety Standards at (416) 325-3100

*The reproduction of this guideline for non-commercial purposes is permitted and encouraged. Permission to reproduce the guideline for commercial purposes must be obtained from the Office of the Fire Marshal Ontario.*

**Fire Protection Water Supply Guideline for Part 3 of the OBC**  
**Office of the Fire Marshal**

---

OFM-TG-07-98

## **ABSTRACT**

This guideline will assist those trying to establish an adequate fire protection-water supply for new and renovated Part 3 buildings as required by Article 3.2.5.7. or Part 11 of the Ontario Building Code. The criteria for "adequate water supply" will be detailed and the limitations of this criteria explained. Several other factors will be explained as they relate to the fire protection water supply, such as the fire department, environmental impact and cost.

The guideline provides a method of simple calculation of an on-site water supply, taking into account building occupancy, size, construction and exposure, as well as minimum water duration requirements. Other issues that may effect the need for an on-site water supply or design factors are discussed as well. Sample problems are included to assist the user.

**DRAFT**

## INTRODUCTION

The Office of the Fire Marshal, in cooperation with the Ministry of Municipal Affairs and Housing and the Water Supply Adequacy Committee has developed this guideline to help building owners, consultants and others involved in life safety design of buildings, meet the requirements for "adequate water supply for fire fighting" as found in Part 3 of the Ontario Building Code (OBC). This guideline is not intended for farm buildings or buildings that fall within Part 9 of the OBC.

This guideline has been developed in conjunction with the A-3.2.5.7. Appendix Note on Adequate Water Supply in the 1997 Ontario Building Code.

The *primary purpose* of this guideline is to provide an adequate fire protection water supply to support evacuation and fire department search and rescue operations during a fire, and prevent fire spread to other buildings.

The *secondary purpose* of this guideline is to provide a fire protection water supply that can be used to provide a good measure of property protection during the early stages of a fire.

With the exception of sprinklered buildings, this guideline does not intend to provide the optimum for property protection. However with a timely response by a well trained fire department, the water supply designated in this guideline should be sufficient to allow the fire department to extinguish building fires where adverse circumstances are not encountered.

It should be noted that where "property protection" is a primary expectation of the building owner, or where significant environmental contamination from a fire is a concern, other recognized fire protection guidelines should be referenced (such as the Fire Underwriters Survey) to ensure adequate water supplies for manual fire suppression by available fire fighting means, or the building should be sprinklered. Building owners should be made aware of the limitations of the fire protection water supply as required in this guideline, prior to the design and construction of their building and/or the design of an on-site water supply.

It should be noted that other guidelines, such as the Fire Underwriters Survey, should be used when designing water supply systems for newly developed municipal areas, as this fire protection water supply guideline is not intended to address domestic service water needs.



Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

## OVERVIEW OF THE BUILDING CODE REQUIREMENTS

Article 3.2.5.7. of the Ontario Building Code (OBC) 1997 states: "an adequate water supply for fire fighting shall be provided for every building".

### Q1 What does this mean for unsprinklered buildings?

As interpreted in this guideline, an adequate fire protection water supply for unsprinklered buildings means an immediately available and accessible water supply, with sufficient volume and/or flow to enable the fire department to use their fire hoses to control fire growth until the building is safely evacuated and search and rescue operations have been complete, and to prevent the fire from spreading to adjacent buildings. This water supply should also be sufficient to provide a limited measure of both property protection and protection against fire growth in buildings with contents that could result in a significant environmental impact.

### Q2 What does this mean for sprinklered buildings?

For sprinklered buildings, an adequate fire protection water supply means a reliable water supply providing sufficient water flow for the sprinkler systems in terms of pressure, volume, and duration to limit fire growth until the fire department arrives to suppress the fire. This automatic protection is expected to provide time for the evacuation of buildings, assist the fire department in preventing fire spread to adjacent buildings, limit the environmental impact of fires, and provide significant property protection.

Note: A properly designed sprinkler system, and especially those using modern technology sprinkler heads, will often extinguish a fire even without additional manual fire fighting intervention.

## FIRE DEPARTMENT RESPONSE

### Q1 How does fire department response influence water supply requirements?

Determining an adequate water supply for manual fire protection is not dependent solely on building characteristics. A major factor will be the response time and intervention provided by the local fire department. This guideline assumes a prompt response by a well equipped fire department using modern fire fighting techniques, and assumes that buildings will be evacuated in accordance with established building fire safety plans and fire department pre-fire plans. Where there is no fire department see Q3 in the Special Cases Section.

An immediately available fire protection water supply permits the fire department, at their discretion, to enter a burning building with hose lines to conduct search and rescue operations. The duration of this water supply should, as a minimum, be sufficient to allow complete search and rescue throughout buildings. Once the search and rescue operations are complete, additional water may be required for exposure protection or for fire suppression to limit property damage. Exposure protection and fire suppression to limit property damage go beyond the minimum for life safety as established by water supply requirements set out in this guideline.

The fire department has discretion as to how they will use hose streams on any given fire. Where a limited amount of fire protection water is available on site, decisions will be made on how much water will be used in the initial "search and rescue" stage, the suppression stage and for exposure protection. The Fire Chief may deem it most beneficial to concentrate all fire department resources to suppress a fire in its early growth stage, thereby drawing-down the limited water supply quickly, or may instead "nurse" the limited water supply until the search

and rescue procedure is completed and then concentrate on exposure protection until supplemental water supplies arrive.

Fire departments serving remote or rural areas often have to respond to a fire with a transportable water supply having a duration of approximately five to ten minutes when using one or two 38 mm hose lines. This provides minimal hose streams allowing immediate search and rescue and fire suppression in small buildings with simple layouts. However, where a fire has had a significant head start, this transported water supply is unlikely to be sufficient to save the building.

For larger, more complex buildings, an on-site fire protection water supply is needed to provide an extended duration of hose stream use by the fire department to allow search and rescue of the building, exposure protection and fire suppression. The volume of this on-site fire protection water supply is dependent on the building size, construction, occupancy, exposure and environmental impact potential, and shall be sufficient to allow at least 30-minutes of fire department hose stream use.

## COST IMPACT

Q1 How significant a cost impact will it be to provide an adequate fire water supply?

Cost impact on buildings constructed in rural or remote areas will typically be more than for buildings constructed within areas provided with municipal water mains. The great majority of existing municipal water systems will be able to satisfy the requirements of this guideline for new building construction. This would not preclude situations where new large "high fire demand" type buildings are being proposed in areas where the municipal water supply is not adequate. In these cases the building owner may need to provide supplemental fire protection water to meet the requirements of this guideline. The building owner may alternatively make design modifications to his building to reduce the water supply requirements. These modifications could include providing firewalls, using noncombustible construction in lieu of combustible construction, sprinklering the building, reducing the amount of window openings exposing a property line, etc.

Buildings constructed in rural or remote areas without a municipal water supply or an adjacent accessible body of water (i.e. river or large pond) may require on-site water storage tanks or a water reservoir for the fire protection water supply required by this guideline. Hydrants, suction connections for fire department "drafting", or underground dry mains may also be needed to provide appropriate building coverage. (See Q7 in the Special Cases Section)

## SIGNIFICANT ADVERSE ENVIRONMENTAL IMPACT

Q1 What types of building fires could result in a significant adverse environmental impact and thus require additional fire protection water supplies?

Any building used for the storage or processing of chemicals or materials should be deemed to have the potential for significant adverse environmental impact, if a fully developed fire would result in significant contamination of ground or surface water through direct runoff or atmospheric dispersion.

**Fire Protection Water Supply Guideline for Part 3 of the OBC**  
**Office of the Fire Marshal**

OFM-TG-07-98

**Q2 What fire protection criteria should be used for these buildings?**

Properly designed sprinkler protection should be provided in these buildings to prevent fully developed fires. Sprinklered buildings typically require reduced amounts of water for control or suppression of a fire, thus reducing the potential for environmental impact from contaminated water run-off.

Where sprinkler protection is not provided, other recognized fire protection guidelines (e.g. Fire Underwriters Survey) may instead be used to determine the manual fire fighting water supply needs for these buildings. The Chief Building Official or Fire Official should evaluate these special cases on an individual basis.

**Q3 Why do unsprinklered buildings with occupancies that constitute an adverse environmental impact typically require an increased water supply for manual fire fighting?**

An increased water supply gives the fire department the option of conducting an all out fire hose suppression attack in the early stages of a fire. A successful hose deluge attack at this time may result in extinguishment before significant amounts of environmentally hazardous chemicals and materials are involved.

**Note:** Unsprinklered buildings will require careful preplanning by fire departments to ensure judicious application of this greater amount of fire fighting water to prevent significant adverse environmental impact due to water run-off.

## **WATER SUPPLY REQUIREMENTS**

**Q1 How do I determine water supply requirements?**

To simplify this guide, requirements have been placed into four categories. It is best to use a process of elimination to determine the correct category of water supply requirements. This guideline is not intended to be used for farm buildings or Part 9 buildings. (see Q8 in the Special Cases Section)

The four categories are:

- buildings not requiring on-site fire protection water supply
- sprinklered buildings
- buildings requiring on-site fire protection water supply
- additions to existing buildings

### **1. Buildings Not Requiring On-Site Fire Protection Water Supply**

- (a) A building would not require an on-site water supply for fire fighting if the building satisfies the criteria set out in Item 1(b) or Item 1(c), provided that:
- (i) the building is serviced by a municipal water supply system that satisfies Item 3(b), or
  - (ii) the fire department can respond with a transportable water supply of sufficient quantity to allow them to conduct an effective search and rescue of the building, determined on the basis of other guidelines or standards (such as NFPA 1231, "Standard on Water Supplies for Suburban and Rural Fire Fighting"). (also see Q1 to Q3 in the Special Cases Section)
- (b) A building does not require an on-site water supply for fire fighting where all the following criteria are met.

**Fire Protection Water Supply Guideline for Part 3 of the OBC**

OFM-TG-07-98

Office of the Fire Marshal

- (ii) the building height is 2 stories or less,
  - (iii) the building does not have a Group B occupancy (care or detention),
  - (iv) the building does not require a sprinkler system or a standpipe and hose system,
  - (v) the limiting distance from the property line is at least 13 metres if the building has an F-1 occupancy (high hazard industrial), and
  - (vi) the building constitutes no significant environmental contamination potential under fire conditions.
- (c) A building that exceeds 200 m<sup>2</sup> in building area or 2 storeys in building height may not require an on-site water supply for fire fighting where it has an F-3 occupancy with an insignificant combustible loading (such as found in cement plants, steel stock storage sheds, etc.), as determined by the Chief Building Official.

**2. Sprinklered Buildings**

For sprinklered buildings, NFPA 13, "Standard for the Installation of Sprinkler Systems", as referenced by Article 3.2.5.13. of the Ontario Building Code, shall be used to obtain sprinkler and hosestream water requirements. (see Q1 of the Further Explanation of Guideline Requirements Section)

**3. Buildings Requiring On-Site Fire Protection Water Supply**

- (a) Except for sprinklered buildings and as required by Items 3(c) and 3(d), new buildings shall be provided with a supply of water available for fire fighting purposes not less than the quantity derived from the following formula:

$$Q = KVS_{Tot}$$

- where
- Q = minimum supply of water in litres
  - K = water supply coefficient from Table 1
  - V = total building volume in cubic metres
  - S<sub>Tot</sub> = total of spatial coefficient values from property line exposures on all sides, as obtained from the formula:

$$S_{Tot} = 1.0 + [(S_{Side1}) + (S_{Side2}) + (S_{Side3}) + \dots \text{etc.}]$$

- where S<sub>Side</sub> values are obtained from Figure 1, as modified by Items 3(e) and (f), and S<sub>Tot</sub> need not exceed 2.0

(see Explaining the Calculations Section)

- (b) Except as provided in Item 3(d), water supply flow rates shall not be less than that specified in Table 2. Where the water supply is from a municipal or industrial water supply system then the required flow rate shall be available at a minimum pressure of 140 kPa

**Fire Protection Water Supply Guideline for Part 3 of the OBC**  
**Office of the Fire Marshal**

OFM-TG-07-98

- (c) Except as provided in Item 3(d), the minimum fire protection water supply (Q) required in Item 3(a) shall not be less than what is needed to provide the minimum flow rate specified in Table 2 for a duration of 30 minutes.
- (d) In elementary and secondary schools, the water supply determined in accordance with Items 3(a) and 3(b) may be reduced. The level of reduction to be applied would be at the discretion of the local jurisdictional authority, and should not exceed 30%. Factors to consider should include fire department response time, fire department resources and the size and complexity of the school building. (see Q10 of the Special Cases Section)
- (e) Where a masonry wall with a minimum fire-resistance rating of 2 hr. and no unprotected openings is provided as an exterior wall, the spatial coefficient ( $S_{side}$ ) for this side of the new building may be considered equal to 0. This exterior masonry wall shall be provided with a minimum 150 mm parapet.  
  
Firewalls that divide a structure into two or more buildings may be given similar consideration when evaluating the exposure of the buildings to each other.
- (f) The spatial coefficient ( $S_{side}$ ) may be considered equal to 0 when the exposed building is on the same property and is less than 10m<sup>2</sup> in building area.

#### 4. Additions to Existing Buildings

- (a) Except as permitted in Items 4(b) and (c), additions to existing buildings shall be provided with a fire protection water supply as required in Items 3(a) to 3(f). (See Q2 in the Further Explanation of Guideline Requirements Section)
- (b) Buildings with new additions falling into any one of the following criteria would not require an additional water supply for fire fighting where:
  - (i) the expanded building complies with all the requirements of Item 1(a),
  - (ii) the new addition does not exceed 100m<sup>2</sup> in building area, or
  - (iii) the new addition exceeds 100m<sup>2</sup> but does not exceed 400m<sup>2</sup> in building area, contains an assembly, business and personal services, mercantile or low hazard industrial occupancy, is of noncombustible construction, does not result in a significant increase in exposure to other existing buildings, has no combustible storage or process, and is separated from the existing building by a minimum 1 hour fire-rated separation.
- (c) Where a firewall is provided between the new addition and the existing building, the fire protection water supply may be determined in accordance with Items 1(a) and 3(a), using only the building volume of the new addition.

Note: Consideration should be given to designing the water supply to the more stringent requirements of the two separated buildings.

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

**TABLE 1**  
**WATER SUPPLY COEFFICIENT -- K**

TYPE OF CONSTRUCTION	Classification by Group or Division in Accordance with Table 3.1.2.1 of the Ontario Building Code				
	A-2 B-1 B-2 B-3 C D	A-4 F-3	A-1 A-3	E F-2	F-1
Building is of noncombustible construction with fire separations and fire-resistance ratings provided in accordance with Subsection 3.2.2. of the OBC, including loadbearing walls, columns and arches.	10	12	14	17	23
Building is of noncombustible construction or of heavy timber construction conforming to Article 3.1.4.6. of the OBC. Floor assemblies are fire separations but with no fire-resistance rating. Roof assemblies, mezzanines, loadbearing walls, columns and arches do not have a fire-resistance rating.	16	19	22	27	37
Building is of combustible construction with fire separations and fire-resistance ratings provided in accordance with Subsection 3.2.2. of the OBC, including loadbearing walls, columns and arches. Noncombustible construction may be used in lieu of fire-resistance rating where permitted in Subsection 3.2.2.	18	22	25	31	41
Building is of combustible construction. Floor assemblies are fire separations but with no fire-resistance rating. Roof assemblies, mezzanines, loadbearing walls, columns and arches do not have a fire-resistance rating.	23	28	32	39	53
Column 1	2	3	4	5	6

**TABLE 2**  
**MINIMUM WATER SUPPLY FLOW RATES**

OBC Part 3 Buildings	Required Minimum Water Supply Flow Rate (L/Min.)
One-storey building with building area not exceeding 600m <sup>2</sup> (excluding F-1 occupancies)	1800
All other buildings	2700 (If Q < 108,000L) <sup>(1)</sup>
	3600 (If Q > 108,000L and ≤ 135,000L) <sup>(1)</sup>
	4500 (If Q > 135,000L and ≤ 162,000L) <sup>(1)</sup>
	5400 (If Q > 162,000L and ≤ 190,000L) <sup>(1)</sup>
	6300 (If Q > 190,000L and ≤ 270,000L) <sup>(1)</sup>
	9000 (If Q > 270,000L) <sup>(1)</sup>


Note: <sup>(1)</sup> Q = KVS<sub>TOT</sub> as referenced in Item 5(a)

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

FIGURE 1

SPATIAL COEFFICIENT VS EXPOSURE DISTANCE



## EXPLAINING THE CALCULATIONS

### Q1 What is the "K" factor and how were these values developed?

The K factor, also known as water supply coefficient, is a value that takes into account typical compartmentalization of buildings, combustibility of construction, combustible loading of the building occupancy and evacuation responses by the building occupants.

These factors were developed using the "occupancy hazard classification numbers" and "construction classification numbers" in NFPA 1231, adjusting them to fall within the occupancy classifications of buildings within the Ontario Building Code, and then modifying them so that the final units of the equation are in litres. Table 1 of this guideline lists K values according to type of construction and occupancy classification.

### Q2 What volume is included in "V"?

All spaces below and above grade within a building, measured to the underside of the roof deck, should be included in the volume (cubic metres) for the fire protection water supply formula. An exception may be made to exclude a non-combustible crawl space (with no combustible services) below a non-combustible floor, located under the lowest building floor area, if it will not be developed in the future or used as a storage area.

### Q3 How are "exposures" measured?

Exposure distances from a new building will be measured from the exterior building faces to the property lines of that building. The distance from the face of the building to the property line shall be determined as per OBC 3.2.3.1.(3). When facing a street, the property line shall be deemed to be the centre of the street.

When facing an existing building (exceeding 10 m<sup>2</sup> in building area) on the same property, the exposure distance (for use in Figure 1) shall be the greater of either the "limiting distance" of the new building face as obtained in OBC 3.2.3.1.(1), or the mid-point between the two buildings.

### Q4 How are spatial coefficient values obtained from Figure 1?

Once the exposure distance for each building face has been determined, these values can be located along the horizontal arm at the bottom of Figure 1. By following straight up from these points the graph line may be intersected providing a spatial coefficient value ( $S_{side}$ ) along the left vertical arm of Figure 1. Exposure distance values of at least 10 m. (except F-1 occupancies which require a minimum of 13.0 m) result in a spatial coefficient value of 0.

### Q5 How are multiple exposures calculated?

Where a new building has exposures on more than one side, the percentage increase in the fire protection water supply due to the exposures on each side should be totaled to reflect all exposure protection requirements. [e.g. if exposure to one side results in a 50% increase in water volume (i.e.  $S_{side1} = 0.50$ ), and exposure to another side results in a 25% increase in water volume (i.e.  $S_{side2} = 0.25$ ), then the total increase in water volume for exposure protection is 75%. The totaled spatial coefficient ( $S_{total}$ ) is then



**Fire Protection Water Supply Guideline for Part 3 of the OBC**  
**Office of the Fire Marshal**

OFM-TG-07-98

**Q6 What is the rationale for the minimum 30 minute water supply duration and what new buildings will be most affected by this requirement?**

The minimum 30 minute fire protection water supply duration requirements as stated in Item 3(b), recognizes life safety concerns by providing a dependable and immediately available fire protection water supply for the fire department's use. It is intended that the duration be long enough to allow complete search and rescue of any building by the fire department. This minimum fire protection water supply should also give the fire department a reasonable opportunity to control and/or extinguish a small fire upon their arrival, thereby preventing its growth and spread to adjacent buildings and limit any negative environmental impact. This minimum 30 minute duration requirement also allows a reasonable time for the fire department to arrange for supplementary water supplies using a water shuttle system for most buildings.

Concerns for minimum fire protection water supply volumes are mostly relevant for building sites not serviced by municipal water supply systems, where an on-site fire protection water supply has to be provided. Building sites serviced by municipal water supply systems will usually be provided with sufficient water volumes for their fire protection needs. The guideline focuses on water supply flow rates at minimum pressures for these buildings. It should be noted however that some municipalities have fairly limited water supply storage capacities and should therefore be evaluated when a new "high demand" building is to be constructed.

**Q7 How do exterior 2 hr. rated masonry walls with parapets and no unprotected openings and interior firewalls influence exposure, and thus water supply calculations?**

Interior firewalls and exterior masonry walls fire-rated for 2 hours, with parapets and no unprotected openings, are expected to remain in place during the period that fire exposure is greatest. Exposure to adjacent buildings is reduced to a point where additional exposure protection water may not be needed.

Judgment by the Chief Building Official should be used in determining the design of exterior 2 hour fire-rated masonry walls and interior firewalls with regard to exposures. The usual 6 inch parapet may not be considered adequate exposure protection where a new building exposes a much higher existing building in close proximity. Rather than having to increase the water supply due to exposure, a higher parapet may be sufficient protection. In situations where parapet design or other exposure protection methods do not provide adequate exposure protection for the existing building, then additional exposure fire protection water may be required.

Where firewalls divide a new facility into separate buildings, the fire protection water supply should be sized to the building with the greatest water supply demand.

**Q8 What would be the impact on fire protection water supply requirements for a new building if an existing exposed property has its own on-site fire protection water supply?**

Where a new building exposes an existing property provided with its own independent on-site fire protection water supply, the Chief Fire Official may deduct this water supply from the quantity needed by the new building due to this exposure. This neighbouring water supply should be accessible to the fire department to protect exposed buildings.

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

The Chief Fire Official should be satisfied that the two property owners will properly maintain their respective fire protection water supplies for the life of their buildings. This agreement may require approval from the municipality and may be subject to criteria provided by the Building Code Commission.

## FURTHER EXPLANATION OF GUIDELINE REQUIREMENTS

**Q1** Regarding sprinklered buildings, where in NFPA 13 are hose stream requirements specified?

NFPA 13 contains the hose stream requirement for sprinklered buildings in the "Occupancy Hazard Fire Control Approach" section (in Chapter 5 of 1992 to 1998 NFPA 13 edition). Within, is a table entitled "Hose Stream Demand and Water Supply Duration Requirements". This table provides total inside and outside hosestream requirements and duration for each hazard classification of sprinkler system design.

A sprinkler contractor designing a sprinkler system for a building will determine the minimum water supply requirements for the sprinkler system. Using the duration period obtained from the above referenced table, the contractor will add the sprinkler and hose stream requirements and calculate the total fire protection water supply required for the building.

**Q2** Where new additions are added to existing buildings that do not have an on-site water supply, what volumes of water are considered adequate for life safety and exposure?

Whereas Part 11 of the OBC indicates that only the addition to an existing building is required to conform to OBC Part 3, this might in reality not be adequate to deal with life safety and exposure where fire protection water supply needs are concerned.

When an addition is added to an existing building and water supply calculations are based only on the volume of the addition, the fire protection water supply provided on-site might not be adequate to allow full search and rescue throughout the entire building. As well, exposure to neighbouring buildings from the new addition may not be reflective of the nature and size of a potential fire in the enlarged building. Calculations using the entire volume of an expanded building therefore are the only accurate indication of fire protection water supply needs.

**Q3** Does this guideline apply to buildings that are being renovated under Part 11 of the Building Code?

Part 11 of the Building Code should be reviewed to determine the conditions under which Article 3.2.5.7. applies. This is found in the Compliance Alternative tables in Part 11.

Where Article 3.2.5.7. does apply, the existing water supply should be evaluated to determine if it is sufficient for the renovated building. Some discretion may be used by the building official if the water supply for the renovated building is not significantly greater than the existing water supply.

## SPECIAL CASES

**Q1** Can water transported by the fire department be satisfactory to protect small buildings?

**Fire Protection Water Supply Guideline for Part 3 of the OBC**

OFM-TG-07-98

Office of the Fire Marshal

Smaller buildings of 2 stories or less and with a building area of 200m<sup>2</sup> or less, may be adequately protected by a fire department using proper pre-planning methods and transported fire protection water supplies. NFPA 1231, "Standard on Water Supplies for Suburban and Rural Fire Fighting", provides methods to assist the fire department with this pre-planning. Where the fire department does not have the equipment necessary for a proper water shuttle system to adequately protect these smaller buildings as per NFPA 1231, an on-site fire protection water supply should be considered.

**Q2 What extra precautions, if any, should be taken for institutional occupancies?**

Buildings with Group B, Division 1, 2 and 3 occupancies should be treated in a special manner with respect to fire protection water supplies. The occupants of these buildings require direct supervisory assistance for phased evacuation during a fire. This could result in a prolonged search and rescue by the fire department. If this type of building is located in areas not serviced by municipal water mains, the fire protection water supply that the fire department is capable of transporting to the site may not be adequate for the duration of this search and rescue period. Only a properly sized on-site fire protection water supply will provide the hose stream duration that the fire department needs. Alternatively, sprinkler protection could be provided.

**Q3 What provisions should be made where fire department response is slow or nonexistent?**

For new buildings constructed in areas where fire department response is not expected in a reasonable time, the building should be sprinklered to help ensure safe evacuation. In locations where a fire department pumper truck is not provided, consideration should be given to installing a private water supply capable of providing a minimum 700 kPa (100 psi) water pressure at the required flow rate to permit fire fighters or other persons trained in the use of fire hoses, to effectively use a "fog-nozzle" hose spray on the fire. This type of hose spray is most effective at controlling fires. Alternatively, sprinkler protection could be provided.

**Q4 How should an outdoor reservoir be designed to take into account ice formation?**

When designing an open, unheated reservoir to provide a fire protection water supply as required in this guideline, a 600 mm ice depth allowance should be included in the water volume calculations. Where local winter temperature conditions result in a greater ice depth (as typically found on local lakes or ponds), this should be factored into the volume calculations.

**Q5 What provisions should be made to ensure that water reservoir supplies do not drop to unsafe levels as a result of evaporation or leakage?**

A make-up water supply should be provided to maintain the design volume of fire protection water supply reservoirs. Storage tanks should be provided with limit switches, pressure gauges or water-level gauges to monitor volume.

If make-up water supply for open water supply reservoirs is provided by natural refill methods (i.e. water table seepage) and periods of drought are common, the reservoir capacity should be increased to take into account the reduced water table levels expected from the evaporation of water.

**Q6 What standards should be used to provide an acceptable water supply design?**

**Fire Protection Water Supply Guideline for Part 3 of the OBC**

OFM-TG-07-98

Office of the Fire Marshal

Tanks should conform to NFPA 22, "Water Tanks for Private Fire Protection", and the local fire department should be consulted to determine appropriate connections for their pumping equipment.

Fire main installations should conform to NFPA 24, "Private Fire Service Mains and Their Appurtenances".

On-site fire pump installations should conform to NFPA 20, "Standard for the Installation of Centrifugal Fire Pumps".

Sprinkler standards other than NFPA 13, "Standard for the Installation of Sprinkler Systems", such as NFPA 13D, "Installation of Sprinkler Systems in One- and Two-Family Dwellings and Mobile Homes", and NFPA 13R, "Installation of Sprinkler Systems in Residential Occupancies Up To and Including Four Stories", may be used where appropriate for the type of building covered by these standards. These other standards should be acceptable to the local jurisdictional authority.

For new buildings that present a special hazard to a community as a result of their size, occupancy or economic importance, the Fire Underwriters Survey Guide should be used to determine suitable water supply and hydrant siting.

**Q7 For evaluation of the fire protection water supply and associated fire hydrants, are there other considerations in addition to those set out in the OBC?**

Impounded fire protection water supply for a remote building shall be accessible to the fire department to allow the use of suction lines for drafting either directly from the impounded water source, or from a dry hydrant supplied from the impounded water source. This water source or hydrant shall be located in adherence to OBC 3.2.5.7.(2).

Where at least two widely separated private fire hydrants are required to protect a building and water is to be supplied from a single on-site fire protection water supply (e.g. reservoir), it is acceptable to provide a fire department pumper connection adjacent to the water supply to allow a pumper truck to pump into an underground "dry" main feeding the two remote hydrants. This arrangement permits fire fighters to attach hoses directly to the hydrants or to use a second pumper truck to draw boosted water from these hydrants.

Existing water flow test information obtained to determine the adequacy of the municipal or private water supply for fire protection of a new building should be evaluated with regard to how dated the test information is, whether the flow test was conducted during high or low demand periods, and the possibility that future development in the area will significantly affect the supply. A current hydrant flow test at the proposed construction site will provide the most accurate information.

When dealing with new buildings serviced by municipal or industrial pressurized fire protection water systems, this guideline specifies a minimum water flow rate at 140 kPa pressure. The 140 kPa pressure is the accepted minimum that most fire departments will allow service mains to be drawn down to. Water main and/or booster pump damage could occur from cavitation at pressures below this level.

**Q8 Can this guideline be used for Part 9 of the OBC?**

The OBC does not currently require that Part 9 buildings be provided with an adequate water supply for fire fighting. However, this guideline may be used on a voluntary basis to provide a suitable fire protection water supply for these buildings.

The Water Supply Adequacy Committee recommends that an on-site fire protection water supply as required by this guideline be provided for multi-unit residential (Group C) type buildings (i.e. hotels, motels, apartments, townhouse complexes, etc.) that fall within Part 9 of the OBC. These buildings inherently have delayed building evacuation, resulting in more extensive search and rescue operations, and will likely benefit from an on-site fire protection water supply.

**Q9 How are standpipes and hose systems affected by these requirements?**

Where a building requires a standpipe and hose system per the OBC, the standpipe system should continue to be designed to Article 3.2.9.2. The standpipe will draw from the required water supply specified in this guideline, still leaving a significant fire protection water supply for exterior hose stream use.

**Q10 Can the water supply requirements of this guideline be reduced in buildings with an established fire safety plan that can ensure a rapid building evacuation?**

Elementary and secondary schools have a record of well established and practiced fire safety plans which allow complete school evacuations within 4 minutes. Because of this and the inherent high level of supervision in these types of facilities, a reduction of up to 30% in the fire protection water supply requirements as set out for unsprinklered buildings in this guideline may be given. However, caution should be used if the duration of water supply is reduced to less than 30 minutes, unless other compensating features are also provided.

Other considerations to keep in mind should include disabled students and teachers that are being introduced into the general school population. A delayed evacuation may be expected for them. This could result in prolonged search and rescue operations by the fire department and should be considered when determining water supply reductions.

**Q11 Can the water supply requirements of this guideline be reduced if alternate fire suppression methods are proposed?**

Alternate fire suppression methods may result in reduced water supply requirements when compared to design parameters set out in this guideline. Questions should be directed to the local authority that has jurisdiction over these matters.

Alternative fire suppression methods being considered for allowing a reduction in the water supply requirements of this guideline are, foam/water extinguishing systems, carbon dioxide extinguishing systems or dry chemical extinguishing systems. Exterior water curtain (deluge) systems may be considered in lieu of fire protection water supply requirements for exposure purposes.

**WATER SUPPLY ADEQUACY COMMITTEE**

Kim Bailey - Office of the Fire Marshal  
John Brazan - American Water Works Association  
Roy Chalk - Ontario Municipal Fire Prevention Officers Association  
Steve Penna - Ontario Building Officials Association  
David Shantz - Municipal Engineers Association


Tom Eyre - Ontario Municipal Water Association  
Don Livingston - Ministry of Housing, Buildings Branch  
Ed Coe - Insurers Advisory Organization  
Chief Tom Powell - Ontario Association of Fire Chiefs

## EXAMPLE PROBLEMS

### PROBLEM #1

A new apartment building is to be constructed in your municipality. The building will measure 30m by 25m, with 3m between floors, and consists of 3 storeys plus a basement used for storage and laundry facilities. Parking will be outside. The building is to be of combustible construction and is to conform to 1997 OBC 3.2.2.47. An attic space is also provided in this building with a 750m<sup>3</sup> volume. A 30 min. fire separation is provided between the 3rd floor and the attic space. The building is not to be sprinklered nor provided with a standpipe system.

The building is located on a corner lot and faces 2 streets (see diagram). Property lines are located 5m to the south and 7.5m to the east of the proposed building. All of the buildings are serviced by municipal water mains and hydrants. What is the required minimum flow rate of the municipal main for an adequate fire protection water supply?



### SOLUTION - PROBLEM #1

**(1) Determine building classification**

- residential apartment is Group C

**(2) Check parameters of Item 1(a) to determine whether building requires an on-site water supply.** - building exceeds  $200m^2$ , has ~~two~~ stories with significant combustibles and is not a Part 9 building, therefore needs water supply evaluation

**(3) Calculate  $Q = KVS_{Tot}$**

(i) determine K

- from Table 1, based on building construction and classification, the water supply coefficient K = 18

(ii) calculate the building volume,  $V = L \times W \times H$

- use total height of building, 3 storeys plus basement, and attic space ( $750m^3$ ).

(3m between floors  $\times$  4 floors = 12m)

$$V = (30m \times 25m \times 12m) + 750m^3 = 9750m^3$$

(iii) Determine  $S_{Tot}$  from Figure 1

- consider each side of the building:

- the north and west sides of the building each face a street and the distance to the centre of the streets exceed 10m, so  $S_{Side}$  will be equal to 0.0 on both sides.

- the property line is 5m to the south of the building. From Fig. 1,  $S_{Side}$  is equal to 0.5, meaning that a 50% increase in the volume of water will be required to protect this side.

- the property line to the east of the building is 7.5m. From Fig. 1,  $S_{Side}$  is equal to 0.25, meaning that a 25% increase in the volume of water will be required to protect this side.

- therefore, because of the exposure on the south and east sides of the building, it will be necessary to increase the total volume of the water by 75% (the sum of all the spatial coefficients from each side).

$$\begin{aligned} \text{i.e. } S_{Tot} &= 1 + (\text{total of spatial coefficients}) \\ &= 1 + (0.5 + 0.25) \\ &= 1.75 \quad (\text{Note: } S_{Tot} \text{ need not exceed } 2.0) \end{aligned}$$

$$\begin{aligned} \text{therefore, } Q &= KVS_{Tot} \\ &= 18 \times 9750 \times 1.75 \\ &= 307,125 \text{ litres} \end{aligned}$$

**(4) determine the water supply flow rate**

- from Table 2, since the building either exceeds 1 storey or its area is greater than  $600 m^2$ , and the calculated Q is greater than 270,000 litres, the required minimum water supply flow rate from the municipal system would be 9000 L/Min.

- this flow rate is required at 140 kPa in accordance with Item 3(b).

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal


OFM-TG-07-98

**PROBLEM #2**

A single storey warehouse and distribution center, classified as a low industrial hazard occupancy, is to be built in an area not serviced by a municipal water supply. The building is to be 1500 m<sup>2</sup> in area, 4 metres high and of noncombustible construction conforming to Subsection 3.1.5. of the Ontario Building Code. This building falls within 1997 OBC 3.2.2.80. Storage commodities vary, but in general are farm implements in wood crates.

The warehouse faces one street to the north, with property lines 30m to the east and 7.5m to the west. An existing building is located on the same property and will be 20m to the south of the proposed new warehouse. The new warehouse building will have 10% unprotected openings in its south face.

There is a similar type warehouse that has its own 20,000 litre on-site fire protection water supply located to the west. This water supply is determined by the fire department to be reliable and accessible. How much water will be required on site for fire protection of the proposed building?





## SOLUTION - PROBLEM #2

### (1) Determine building classification

*proposed low hazard warehouse building is Group F-3*

### (2) Check parameters of Item 1(a) to determine whether building requires an on-site water supply.

*building is a Part 3 building as it exceeds 600 m<sup>2</sup> in area and has a significant combustible loading, therefore needs on-site water supply*

### (3) Calculate $Q = KVS_{Tot}$

#### (i) determine $K$

*- from Table 1, based on building construction and classification the water supply coefficient  $K=19$*

#### (ii) calculate the building volume, $V = \text{Area} \times H$

$$= (1500 \times 4) = 6000 \text{ m}^3$$

#### (iii) Determine $S_{Tot}$ from Figure 1 by considering each side of the building:

*- on the east side of the proposed building the distance to the property line exceeds 10 meters so no increase in water volume is necessary.*

*- the proposed building faces a street on the north side with distance to the center of the street 10 meters away. No increase in the water volume will be required due to lack of exposure on this side.*

*- the proposed building faces an existing building on the same property, 20m to the south. The 10% unprotected openings in the south building face of the proposed building results in a "limiting distance" of 2.5m using Table 3.2.3.1.A. of the OBC. Since the midpoint between the two buildings on the same property (10m) is greater than the limiting distance of the south face of the new building, the 10m is deemed the exposure distance. No increase in water volume will therefore be needed from exposure on this side.*

*- the property line to the west is 7.5 meters from the exterior wall, which means a 25% increase in the volume of water to protect the property on that side. However, the neighbour's warehouse has its own reliable 20,000 litre fire protection water supply, so this can be used to reduce the exposure needs. Exposure calculations should be completed to evaluate the neighbouring water supply, therefore,*

$$S_{Tot} = 1 + \text{total of spatial coefficients}$$

$$= 1 + (.25) = 1.25$$

*and,  $Q = KVS_{Tot}$*

$$= 19 \times 6000 \times 1.25 = 142,500 \text{ litres}$$

*Of this amount, 28,500 litres (142,500 - 114,000 = 28,500) is required for exposure, of which 20,000 litres is already provided on the exposed property. Therefore an additional 8,500 litres should be added to the on-site water supply to make up the shortfall in exposure protection. Therefore,  $Q = 122,500$  litres (114,000 + 8,500 = 122,500).*

### (4) determine the water supply flow rate


*- from Table 2, since the building area exceeds 600m<sup>2</sup> and the calculated  $Q$  is greater than 108,000 litres but less than 135,000 litres, the required minimum water supply flow is 3600 L/Min. However, in accordance with Item 3(b) it must also be confirmed that 3600 L/Min. can be flowed for a minimum 30 minutes. Since a 34 min. duration is achieved (122,500 : 3600 = 34 min.), this is satisfactory.*

**PROBLEM #3**

An existing 400 m<sup>2</sup> single storey (with basement) school is being provided with a 400 m<sup>2</sup> addition of noncombustible construction. The existing building is of combustible construction with a 45 min. rated roof and basement ceiling (structural supports rated as well), while the new addition is of noncombustible construction as well and meets the requirements of 1997 OBC 3.2.2.25. Both the new and existing buildings are provided with full basements, 2.5 m. in height. The ground floor has a ceiling height of 3.0 m. An attic space is provided in both buildings, each with volume of 800 m<sup>3</sup>. A 1 hr. fire rated separation is to be provided between the new and existing structures.

No water mains or hydrants are located in the area. A hose standpipe is voluntarily being provided throughout the entire building, with a booster pump. Distances to the property lines are as indicated on the accompanying sketch. An all volunteer fire department with limited equipment is located within 20 min. of the building site.

What size pond is needed on site (assuming no freezing temperatures), to ensure minimum life safety requirements?



Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

**SOLUTION - PROBLEM #3**

(1) Determine building classification  
- school building is Group A-2

(2) Go to Item 4(a) of the water supply guideline. Item 4(b)(iii) indicates that a single storey, noncombustible addition with an assembly occupancy, up to 400m<sup>2</sup> in building area, with no combustible storage or process and separated from the existing building by a minimum 1 hr. fire separation would not require additional water supplies for fire fighting purposes.

(3) The local jurisdictional authority however, may also wish to take into consideration the ability of the local fire department to provide an effective water supply shuttle system to this school by using NFPA 1231 as a guide. If equipment is not available to provide effective amounts of water supply, then an on-site water supply may be the best choice. Note that this is what Item 1(a)(ii) is alluding to.

(4) If an on-site water supply is chosen, it may be sized by calculating  $Q = KVS_{Tot}$

(i) although OBC Part 11 would only size the on-site water supply to the addition, the fire department should determine if this is sufficient for their search and rescue needs.

(ii) assuming the entire building volume is selected to determine  $Q$ , determine  $K$   
- from Table 1, based on building construction and classification the water supply the existing building has a coefficient  $K=18$  and the new addition has a coefficient  $K=16$ .

(iii) calculate the building volume,  $V=L \times W \times H$

$$V_{Existing} = (400 \times 3) + (400 \times 2.5) + 800 = 3000 \text{ m}^3$$

$$V_{Addition} = (400 \times 3) + (400 \times 2.5) + 800 = 3000 \text{ m}^3$$

(iv) Determine  $S_{Tot}$

- From Figure 1, since no property lines are less than 10 m away, all  $S_{sides} = 0.0$ , therefore no addition water volume is needed for exposures.  $\therefore S_{Tot}=1.0$

$$Q = KVS_{Tot}$$

$$= (KVS_{Tot})_{Existing} + (KVS_{Tot})_{Addition}$$

$$= (3000 \times 18 \times 1.0) + (3000 \times 16 \times 1.0)$$

$$= 102,000 \text{ litres}$$

This is the required pond size, assuming a means to maintain the water level and no freezing concerns. Note that Item 3(d) also allows a reduction in the water supply and flow rate for schools. This reduction may not be considered due to the all volunteer fire department with limited equipment.

(5) determine the water flow rate


- from Table 2, since the building area exceeds 600m<sup>2</sup> and the calculated  $Q$  is less than 108,000 litres, the required minimum water supply flow is 2700 L/Min. However, in accordance with Item 3(b) it must also be confirmed that 2700 L/Min. can be flowed for a minimum 30 minutes. Since a 38 min. duration is achieved ( $102,000 \div 2700 = 38$ ), this is satisfactory. Note if the water supply was sized to only the addition then a 54,000 litre pond, allowing a 30 minute duration at a flow rate of 1800 L/Min. would be required. However, at 2700 L/Min., which is a reasonable flow rate for the entire structure, this provides only 20 min. duration.

**PROBLEM #4**

A 300 m<sup>2</sup> single storey restaurant is to be constructed of noncombustible construction in a town with a marginal water supply due to old mains and poor gridding. The municipal water reservoir is sized for 1.0 million gallons. The building will have a 3.5 m. high ceiling. No hose standpipe or sprinklers are planned. Is the existing street supply adequate?

Property lines are located 11m to the east and 20m to the south. Street centre line distances are 10m to the north and west.

The fire department routinely arrives at a fire scene in this part of town with a tanker/pumper truck carrying enough water (4500 litres) for two 38 mm hoses adequate for 5 minutes of discharge. The hydrant at the street can provide 1500 L/Min. at 140kPa.



**SOLUTION - PROBLEM #4**

**(1) Determine building classification**

*-restaurant building is Group A-2 occupancy.*

**(2) Check parameters of Item 1(a) to determine whether building requires an on-site water supply.**

*-building falls within Part 3*

*-building area is more than 200m<sup>2</sup> and is not an F-3 occupancy.*

**(3) Compare existing water supply with required water supply**

*- as the building is  $\leq 600\text{m}^2$ , the required water supply flow rate from Table 2 for this size building is 1800 L/Min.*

*-provided public water supply from hydrant at street is 1500 L/Min at 140kPa (adequate volume of supply)*

*-transported water supply by fire department is 4500 litres.*

*-the required water supply shortfall from public supply only is  $(1800 - 1500) = 300$  L/Min. The transported water supply by the fire department will last 15 minutes if used at a flow rate of 300 L/Min  $(4500/300 = 15 \text{ min.})$  to make up shortfall from the public supply.*

**(4) Solutions to make up water supply shortfall**

**Option #1** - *as the total water supply that is deemed adequate for this new building is  $1800\text{L/Min} \times 30\text{min.} = 54000$  litres, and the provided water supply is  $(1500 \times 30) + 4500 = 49500$  litres, then require an additional on-site water supply of 4500 litres*

**Option #2** - *provide an additional transportable water supply source (i.e. tanker truck) of 4500 L.*


**Option #3** - *the Chief Fire or Building Official may determine that 1650 L/Min is satisfactory based on building occupancy and layout, and the restaurant's fire safety plan. The Chief Fire or Building Official may also determine that "life safety" is no longer a significant concern after 15 minutes in this type of occupancy and the remaining public water supply is satisfactory for exposure concerns.*

Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OEM-TG-07-98

**PROBLEM #5**

A new 4 storey plastics extrusion plant (F-2 occupancy) is being constructed in a town with a marginal water supply. The flat-roofed building will cover a 500 m<sup>2</sup> area and be 12.0 m. in overall height. Construction is to be combustibile and in conformance with 1997 OBC 3.2.2.70. The roof and floor separations have a fire-resistance rating of 45 min. Exposure includes property lines 2m and 3.5m away and street centre lines 9m and 15m away to the west and north. What is the required water supply from the street mains for this new building?



**SOLUTION - PROBLEM #5**

**(1) Determine building classification**

*-Group F-2 occupancy*

**(2) Check parameters of Section (1) to determine whether building requires an on-site water supply.**

*-building is a Part 3 building as it meets dimensional parameters (i.e. more than 3 stories)*

**(3) Calculate  $Q=KVS_{Tot}$**

*(i) determine  $K$*

*- from Table 1, based on building construction and classification, the water supply coefficient  $K=31$*

*(ii) calculate the building volume,  $V=L \times W \times H$*

$$= 500 \times 12$$

$$= 6000m^3$$

*(iii) determine  $S_{Tot}$  from Figure 1 (consider each side of the building) :*

*- the street center line to the north is more than 10m away thereby providing no exposure concerns.*

*- the street center line to the west is 9m away thereby resulting in an  $S_{Side}$  of 0.1*

*- the P/L to the east is 2m away resulting in an  $S_{Side}$  of 0.5*

*- the P/L to the south is 3.5m away, resulting in an  $S_{Side}$  of 0.5*

*- therefore the resulting total of spatial coefficient values is:*

$$S_{Tot} = 1 + (0.1 + 0.5 + 0.5)$$

$$= 1 + (1.1)$$

$$= 2.1$$

*(however as  $S_{Tot}$  need not exceed 2.0, assume  $S_{Tot} = 2.0$ )*

*(iv) therefore,  $Q = KVS_{Tot}$*

$$= 31 \times 6000 \times 2.0$$

$$= 372,000 \text{ litres}$$

*-It should be confirmed that the municipal reservoir has this reserve fire fighting water supply capacity.*

**(4) Determine the water supply flow rate**

*- from Table 2, this type of building requires a minimum fire protection water supply flow rate of 9000 L/Min at 140kPa. Water flow tests on street hydrants at the building site should confirm this minimum flow.*

## Fire Protection Water Supply Guideline for Part 3 of the OBC

OFM-TG-07-98


Office of the Fire Marshal

**PROBLEM #6**

A 200m<sup>2</sup> single storey flammable liquids storage and paint mixing room is being constructed on the southwest corner of this existing remote 600m<sup>2</sup>, single storey metal parts fabricating and treating plant. The property line is no closer than 60m from the building in the south, east and west directions. The center line of the highway to the north is 12m. An existing 5000 Imp. gal. fire protection water supply is currently provided on-site, with a dry hydrant to provide fire department draft from this reservoir.

The building is located in an area surrounded by agricultural lands used for growing cash crops, and lakes used to provide potable water for the local communities.

The existing building has interior hoses but no sprinklers. The new addition is to be separated from the existing building by a 2 hr. firewall, but is not to be sprinklered. The addition is to be 4m in height and of noncombustible, non-rated construction. The walls of the addition at right-angles to the existing building are blank masonry, while the masonry walls of the existing building at right-angles to the addition has 10% openings. Is the existing water supply sufficient for the addition or the existing building.





Fire Protection Water Supply Guideline for Part 3 of the OBC  
Office of the Fire Marshal

OFM-TG-07-98

### SOLUTION - PROBLEM #6:

**(1) Determine new building classification**

*-Group F-1 occupancy*

**(2) Check parameters of Section (4) for this addition. Item 4(c) deals with firewalls separating additions from existing buildings. Check parameters of Section (1) to determine whether addition requires an on-site water supply.**

*- the addition has an F-1 occupancy and is therefore a Part 3 building. Because the chemical occupancy of the addition may result in a significant adverse environmental potential to the local aquifer, the addition does not fall within Section 1. Therefore check Section (2) and (3).*

**(3) Addition is not to be sprinklered so Section (2) does not apply.**

**(4) From Section (3) calculate Q for the addition using  $Q=KVS_{Tot}$**

*(i) determine K*

*- from Table 1, based on building construction and classification, the water supply coefficient  $K=37$*

*(ii) calculate the building volume,  $V=L \times W \times H$*

$$= 200 \times 4$$

$$= 800m^3$$

*(iii) determine  $S_{Tot}$  from Figure 1 (consider each side of the building):*

*- the P/L to the east, west and south exceeds 13m resulting in  $S_{Side}$  values of 0 in each direction.*

*- to the north the limiting distance to the south exposed wall of the existing building from the blank west wall of the addition is determined from 1997 OBC 3.2.3.1.(1). Because of the blank masonry wall the limiting distance is 0.*

*- therefore the resulting total of spatial coefficient values is:*

$$S_{Tot} = 1 + (0 + 0 + 0 + 0)$$

$$= 1.0$$

*(iv) therefore,  $Q = KVS_{Tot}$*

$$= 37 \times 800 \times 1.0$$

$$= 29,600 \text{ litres}$$

**(4) Determine the water supply flow rate**

*- from Table 2, F-1 occupancy buildings require a minimum fire protection water supply flow rate of 2,700 L/Min. The existing on-site fire protection water supply of 5,000 Imp. gal. (22,750 litres) can provide this flow rate for 8 minutes.*

*- Since a minimum 30 minute duration in water supply is needed, an additional 58,250 litres of on-site water supply is needed for the addition to make up the shortfall (81,000-22,750).*

*- The existing building may also be evaluated to see if water supply requirements would be higher. Owner may decide to provide additional water demand if higher.*

Note: Under the OBC the existing building also has to be evaluated to determine the



**APPENDIX 19**

**BLACK & McDONALD –  
HIGH VOLTAGE MAINTENANCE  
REPORTS DATED AUGUST 1999,  
REFERENCE NO. 6621**



***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

August 16, 1999

Toronto Zoo  
361A Old Finch Ave.  
Scarborough, Ontario  
M1B 5K7

**ATTENTION: Mr. Dean Evans, Electrical Supervisor**

**Subject: 1999 High Voltage Maintenance**

**Our Reference #: 6621**

---

***Dear Sir:***

During June this year, we completed the ***Preventive Maintenance Program*** on the high voltage power apparatus located at your site. This work was carried out to the specifications outlined in tender proposal #48 (98-10).

The following sections are included in the report:

- **Deficiencies and recommendations**
- **Inspection Sheets**

**Intent**

The intent of this program was to evaluate and report on the condition of the high and low voltage equipment in your main and unit substations. This evaluation would detect any problems in their early stages, indicating potential problems in your system that would eventually lead to equipment failure.

**Technical Field Service Department**

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907


**Findings**

The problem areas together with detailed recommendations can be found in section "A". Detailed information pertaining to any of the deficiencies listed in this section can be reviewed with the individual test sheets compiled in section "B". In-order to avoid any unexpected downtime we would recommend taking the necessary corrective measures listed in section "A".

Should you require any further assistance or information, please do not hesitate to contact our office at your convenience. We thank you for the opportunity to have been of service.

Yours sincerely,

**BLACK & McDONALD LIMITED**



R.P. (Rodger) Morgan

Technical Field Service Division

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**“A” DEFICIENCIES & RECOMMENDATIONS**

**Technical Field Service Department**

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Deficiencies and Recommendations**

**Main Incoming Switchgear**

**1.) Main Feeder "DIP" Pole**

**Deficiency:**

The main fuses on this pole were found to be out of co-ordination with the downstream switchgear fuses. Both were sized at an amperage of 150E. Due to the subsequent interruptions caused by cable failures, these have been replaced and the pole-mounted fuses re-sized to 200E.

**Recommendation:**

Review sizing and speed (TCC #) requirements with the supply authority. Ensure stock of these S&C SMU-20 style fuse units for future ready availability.

**2.) Main 27.6kV Incoming Switch**

**Deficiency:**

The Blue/ C $\phi$  arcing interrupter was found to be defective.

**Recommendation:**

Replace this S&C interrupter unit.

**3.) Feed to Eurasia Pavilion**

**Deficiency:**

The B & C phase interrupters on this switch measure over the readable scale in both positions. They are defective.

**Recommendation:**

Replace these two arcing interrupters.



**Technical Field Service Department**

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**4.) All Fused Switch Cells**

**Deficiency:**

Due to the power cable failures and the resulting numerous fuse operations, the spare fuse stock in these feeder cells has been significantly depleted.

**Recommendation:**

Restock the spare fuse inventory.

**North America Pavilion**

**5.) Loop Feed to Service Building**

**Deficiency:**

Flash marks were observed on both the left phase barrier and beside the associated lightning arrester.

**Recommendation:**

Replace the phase barrier and touch up cell as required.

**6.) Paddock Feeders**

**Deficiency:**

Only one spare fuse link is available in the switch/ fuse compartment.

**Recommendation:**

Restock the spare fuse inventory.

**Technical Field Service Department**

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Entrance/ Administration Building**

**7.) Feeder to Village Edge South**

**Deficiency:**

Only one spare fuse link is available in the switch/ fuse compartment.

**Recommendation:**

Restock the spare fuse inventory.

**Africa Pavilion**

**8.) Paddock Feeder**

**Deficiency:**

No spare fuse links are present in this feeder cell.

**Recommendation:**

Restock the spare fuse inventory.

**9.) Main Secondary Breaker**

**Deficiency:**

This FPE 75H-2 (s/n. TH-4126-72) 3000 Amp circuit breaker was found to be mechanically problematic. The breaker failed to consistently trip even though the trip bar was fully engaged. The unit was extensively investigated during the maintenance shutdown and repaired to serviceable condition. *Note that this field repair should only be considered as a temporary fix!*

**Recommendation:**

Because of the nature of the discovered defects, this unit will require thorough stripping and rebuilding/ service. This will require the removal of the circuit breaker from service and may necessitate the installation of temporary generator power as per your needs.

**Technical Field Service Department**

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**10.) MCC1 Circuit Breaker**

**Note:**

Due to the time and personnel involved in investigating of the main circuit breaker, the other smaller breaker designated as "MCC1" was not tested. This unit has been previously reported as problematic and may also need additional servicing.

**Indo-Malaya Pavilion**

**11.) Feeder to Entrance Facilities**

**Deficiency:**

The B $\phi$  cable terminator in this switch cell was found with a top porcelain skirt broken.

**Recommendation:**

The damaged area was sealed with contact cement. No further action is required at the present time.

**12.) Indo-Malaya Paddock Feeder**

**Deficiency:**

The arc interrupter operator (attached to the switchblade) was found to be broken. As a result the interrupter now does not function.

**Recommendation:**

To restore the interrupter's functionality, the entire Load Interrupter switchblade arm will have to be replaced.

**Technical Field Service Department**

31 Pallman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**13.) Indo-Malaya Paddock Feeder**

**Deficiency:**

No spare fuse links are present in this cell.

**Recommendation:**

Restock the spare fuse inventory.

**14.) Main Secondary & DP MB Circuit Breakers**

**Deficiency:**

- The front flash barrier is missing on the "Main ..." C.B.
- The front flash barriers are cracked on the "DP MB" C.B.
- "DP MB" mechanism was found to be sticking.

**Recommendation:**

- The "DP MB" mechanism was restored to proper operation. No further action is required.
- Replace the flash barriers on both circuit breakers.

**Eurasia Pavilion**

**15.) Paddock Feeders (Centre & South)**

**Deficiency:**

The Kirk RE12023 interlock is inoperable due to the switch handle being bent out of position. The switch is still operational.

**Recommendation:**

If full functionality is desired, then the switch handle must be replaced. If this is not a priority, then the switch is presently functional and requires no further action.

**Technical Field Service Department**

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**16.) Paddock Feeders (Centre & South)**

**Deficiency:**

Only one spare fuse link is available in the switch/ fuse compartment.

**Recommendation:**

Restock the spare fuse inventory.

**17.) Eurasia Pavilion Transformer T-1**

**Deficiency:**

The top skirt of the H3 primary bushing was found to be cracked.

Bushing Spec.: Westinghouse T1; DWG. No. 25kV400A; S.O. 544C638G05

**Recommendation:**

The crack was sealed with epoxy. No further action is required at the present time. *The condition of this bushing should be monitored during subsequent shutdowns.* Subsequent deterioration will require bushing replacement in this Askarel (PCB)-filled equipment.

**Submersible & Pad-Mount Transformers**

**18.) Submersible Transformers (General)**

**Note:**

The majority of the approximately 50 units on site are more than 25 years old. These units are approaching the end of their operational service lives. While no one can accurately predict the exact moment of failure for each unit, recent events have shown that they may fail at any time.

A graduated replacement program should be considered by engineering and procurement staff so as to modernise the existing transformer inventory, and prevent unnecessary downtime caused by failures.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**19.) Submersible Transformers Oil Levels**

**Deficiency:**

Several of the submersible transformers were observed with the oil level below the manufacturer's recommended fill line. This is likely as a result of there only being a small quantity of oil in the units and them having been sampled on previous occasions.

**Recommendation:**

Purchase a barrel of Voltesso 35 electrical grade insulating oil (or equivalent) to be used to top up the units as needed during future shutdowns. This barrel should be stored in an area where it will be sheltered from elements (moisture, etc.) that can degrade its properties.

**20.) Submersible Vault #1 (Fed from Service Building)**

**Deficiency:**

The "H1B" elbow on this unit (s/n. 871935) was found with burn marks on it.

**Recommendation:**

The elbow and transformer bushing insert should be replaced in the near future

**21.) Submersible Vault #32 (Fed from N. America)**

**Deficiency:**

The manhole gasket on this Red Phase transformer (s/n. 861949) is in poor condition. Improper sealing of the unit can allow the entrance of moisture and degradation of the oil.

**Recommendation:**

Replace this access cover gasket.

**Technical Field Service Department**

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**22.) Interfacial Tension (IFT) Levels**

**Deficiency:**

Interfacial tension is a measure of the barrier between the oil and water. A lowering of this level is an indication that oil is beginning to degrade.

A number of the transformers had borderline IFT levels. The worst of these is the Vault #18 unit (s/n. LO721-1), which has a measured level of 18.2 dynes/ cm; the N.E.T.A. standard recommended minimum is 32 dynes/ cm.

**Recommendation:**

The Vault #18 transformer should be sampled again within 6 months both to confirm the initial reading and trend for deterioration.

**23.) Weston Station**

**Note:**

This unit substation was reported to be in poor condition. The station should be shutdown during daylight hours for a thorough evaluation.





***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**“B” INSPECTION SHEETS**

***Technical Field Service Division***

***31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907***

***METROPOLITAN TORONTO ZOO***

***Infrared Inspection Report***

***Prepared For: Dean Evans***

***Date: July 27, 1999***

***Prepared By: Kevin Josephs***

***Our Reference: 6621***

**Technical Field Service Division**

31 Pullman Court Scarborough, Ontario. MIX 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907

July 27, 1999

Metropolitan Toronto Zoo  
361A Old Finch Avenue  
Scarborough, Ontario  
M1B 5K7

**ATTENTION:** Mr. Dean Evans  
**Subject:** *Infrared Inspection Report*  
**Our Reference:** 6621

*Dear Sir:*

We have completed your infrared inspection on June 9, 1999. There is list of the areas scanned in this report as well as our findings and recommendations for your review and comment.

Within the report you will find an Infrared Survey Sheet that displays a Thermogram window, below that image there is a 'Profile' window. This window measures the object's temperature along that line in the form of a line graph.


The deficiencies found during the inspection do not warrant any quotation for parts.

We advise that in our opinion the electrical power apparatus as covered in the report, having been inspected, tested and not yet repaired. Sub-stations located in the Indo & Australasia Pavilion appears to be in good condition except what's noted f in the applicable section of this report.


If any questions arise regarding these matters, please feel free to contact the undersigned at any time.

Sincerely,

**BLACK & McDONALD LIMITED**



K. (Kevin) Josephs  
Senior Infrared Technologist  
Technical Field Service Division



***Technical Field Service Division***

*31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907*

**Purpose:**

The purpose of an infrared inspection is to detect heat. Heating is normal in an electrical system since it is caused by the flow of current through a conductor. Therefore, the heat we are searching for is heat, which is abnormal. Unusual heating conditions are caused by several phenomena such as:

- Poor Connections Due To:
  - Looseness
  - Dirt
  - Oxidation
  - Over loading
- Other Conditions Producing Heat Are:
  - Load Imbalances
  - Harmonics

**Survey Intent:**

It is the intent of this survey to act as a predictive tool in order to detect unforeseen problems in the specified areas of your electrical distribution system. Further, our report will satisfy all requests by your insurance company with respect to the completion of an infrared scanning program.

**Background:**

Every body emits infrared heat radiation because of its temperature. Infrared Thermovision systems detect the energy and convert it into a visual picture. Infrared radiation is a direct and proportional function of the body temperature and, by utilizing a special feature (Isotherm) on the infrared System, the temperature differentials can be accurately determined.

The isotherm will appear on a visual image as a series of bright green dots, which have a correspondence to a specific temperature reading.

Technical Field Service Division

31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907

Applications:

Infrared technology is used industry wide as a preventive maintenance tool. All major power consumers use this type of survey on a regular basis. The cost savings associated with the reduction of preventive maintenance man-hours have proved time and time again to justify the cost of the original survey.

Results:

The results are presented in the form of a video print out of the thermal image as seen by the infrared system operator. A corresponding real life picture of the area in question is also supplied. This allows for easier location of the hot spot, as sometimes it is difficult for the untrained eye to perceive detail from the thermograph.

Technical data relative to the suspect area is also provided. This includes the exact identity of the suspect area and/ or device and/ or component, the load currents, our comments as to the suspected cause and our recommendations pertaining to corrective action.

If the electrical system is operating at 60% of its rated capacity then the following rule of thumb may be used to determine the severity of the condition.

Temperature Rise	Classification
1 - 10 Degrees Celsius	Minor Problem. Repair At Your Convenience
10 - 35 Degrees Celsius	Intermediate Problem. Repair In The Next Three Months
>35 Degrees Celsius	Serious Problem. Make Repairs Immediately

Corrective Action:

Infrared technology is one of the truly predictive maintenance tools available today. However, it is only as useful as the corrective action taken to remedy problems, which are discovered.

Therefore, when infrared scanning is carried out it should be done during a period of time when the operation of the facility is as high as possible. It should also be carried out in conjunction with and prior to substation maintenance inspections.

In this way detected problem areas can be corrected with a minimum amount of disruption to the normal operation of the facility.

***Technical Field Service Division***

***31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907***

***Areas Scanned***

**Technical Field Service Division**

**31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907**

***Indo Pavilion***

- *Main Electrical Room*
- *Old Orang Holding*
- *New Orang Holding*
- *Lighting Panel(s) Around Exhibit Area*
- *Gaur Building #1 & #2*
- *MCC Board (Booster Switch & Fan #16 Door Didn't Open)*

***African Pavilion***

- *Main Electrical Room*
- *Lighting Panel(s) Around Exhibit Area*

***America's Pavilion Building***

- *Pump Room*
- *Electrical Room*
- *Fan Room*
- *Exhibit Area*

***Australasia***

- *Main Electrical Room*
- *Boiler Room*
- *Panel(S) Around the Exhibit Area*

***Education & Main Gift Shop***

***Technical Field Service Division***

***31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907***

---

***Entrance Facilities***

***(Front Office Room Locked)***

***Animal Hospital Building***

***North Service Building***

- *Main Floor*
- *Shop Area*
- *Basement*
- *3<sup>rd</sup> Floor*
- *Main Electrical Room*





***Technical Field Service Division***

***31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907***


***Inspection Results and Recommendations***

# Infrared Survey Sheet

**Job No.:** 6621  
**Customer:** Metropolitan Toronto Zoo  
**Site Location:** Toronto, Ontario  
**Equipment I.D.:** F.P.E. 200A 120/208V Disconnect (Auto Transfer Sw.)  
**Equipment Location:** Indo Pavilion Main Electrical Room  
**Inspection Date:** 5/2/89 1:18:15 AM





Surface Profile Minimum Temperature:	29.7 °C
Isotherm Area Temperature:	58.0 °C
Surface Profile Maximum Temperature:	54.0 °C




Status	
<b>SCANNER DATA</b>	
Scanner Type	THV470 SWB
Serial Number	73010
Level	415
Sens	5
Aperture	0
Filter	NOF
Lens	20
<b>IMAGE OBJ. PAR.</b>	
Emissivity	0.84
Amb. temp.	23.7 °C
Atm. temp.	24.8 °C
Object dist.	1.0 m
Rel Humidity	0.50
Transmission	0.99

# Infrared Survey Sheet

**Job No.:** 6621  
**Customer:** Metropolitan Toronto Zoo  
**Site Location:** Toronto, Ontario  
**Equipment I.D.:** Square 'D' 60A Starter Fan #5 General Supply-EU1001  
**Equipment Location:** Australasia Pavilion  
**Inspection Date:** 5/2/89 5:37:40 AM



Surface Profile Minimum Temperature:	<51.1 °C
Isotherm Area Temperature:	72.9 °C
Surface Profile Maximum Temperature:	73.9 °C



Status	
<b>SCANNER DATA</b>	
Scanner Type	THV470 SWB
Serial Number	73010
Level	584
Sens	5
Aperture	0
Filter	NOF
Lens	20
<b>IMAGE OBJ. PAR.</b>	
Emissivity	0.81
Amb. temp.	22.9 °C
Atm. temp.	25.2 °C
Object dist.	1.0 m
Rel Humidity	0.50
Transmission	0.99



*Technical Field Service Division*

*31 Pullman Court Scarborough, Ontario. M1X 1E4 Phone: (416) 298-9977 Fax: (416) 298-2907*

**Inspection Recommendations**

NB. Please refer to individual infrared inspection sheets by the designation given in the PHOTO window

**1. F.P.E. 200A 120/208V Disconnect (Auto Transfer Switch)  
Main Electrical Room (Indo Pavilion)**

**Description:** The Centre phase line end fuse clip area recorded a maximum thermal rise of 54.0 °C, thus creating a temperature rise of 30.3 °C above ambient. The load taken at that time was Top  $\phi \cong 55$  Amps, Centre  $\phi \cong 70$  Amps, and the Bottom  $\phi \cong 42$  Amps.

**Required Action:** Checking this area for proper connection and removing any oxidized agents is necessary to correct the anomaly.

**2. Square 'D' 60A Starter (Fan #5 General Supply – EU1001  
Australasia Pavilion)**

**Description:** The Centre phase blade contact area recorded a maximum thermal rise of 73.9 °C, thus creating a temperature rise of 51.0 °C above ambient. All three phases were balanced at 40 Amps.

**Required Action:** This area needs to be disassembled, cleaned and checked for proper connection.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Main Incoming  
Outdoor 27.6kV Switchgear**

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	RPM/KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Main Outdoor Incoming		
Substation	Pole-mounted Supply Fuse		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	25	kVolt
Type	SMU-20 Fuse Unit	Current		Amps
Style/Cat #		Serial #		

### Fuse Link Nameplate Data

Type	SMU-20 Fuse Unit	TCC	119-2
Style/Cat #		Amps	150 E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	N/A	
Support Structure Condition	OK	
Spare Fuses	?	None seen. Provided by Toronto Hydro

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	458	644	496			

Results Satisfactory      These units have subsequently been replaced.

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	RPM/KH/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Main Outdoor Incoming		
Substation	Main 27.6 kV		

**High Voltage Air/Load Break Switch****Nameplate Data**

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34163	Serial #	---	

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	OK	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	POOR	Blue O Defective
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK/ Fair	Some internal rust damage

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (G $\Omega$ )	50.5	28	12.3			
Contact Resistance ( $\mu\Omega$ )	56	63	55			
Arc Interrupter Res.( $\Omega$ )	0.6	0.7	High			
Results Satisfactory	Fair – See Recommendations					

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 15, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH/ TA
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Feed to Eurasia Pavilion		
<b>Substation</b>	Main Outdoor 27.6 kV		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti Interrupter	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34563R4-T2	<b>Serial #</b>	---	

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	OK	Kirk # RE 12045
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	OK	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	Cleaned
<b>Moving Contact Surfaces</b>	OK	Cleaned
<b>Arcing Contact Surfaces</b>	OK	Cleaned
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	POOR	High Resistance in Closed Position
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>						
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	51	53	57			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	1.3	*	*			

<b>Results Satisfactory</b>	See Recommendations
-----------------------------	---------------------

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	KH/ TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Eurasia Pavilion		
Substation	Main Outdoor 27.6 kV		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134250R4	Amps	150E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Fair	2 spares in cell during inspection

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	630	828	636			

Results Satisfactory      See Recommendations

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	RPM/KH/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Service Building		
Substation	Main Outdoor 27.6 kV Incoming		

**High Voltage Air/Load Break Switch****Nameplate Data**

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	OK	Kirk RE 12043
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	Cleaned
Moving Contact Surfaces	OK	Cleaned
Arcing Contact Surfaces	OK	Cleaned
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	49	42	47			
Arc Interrupter Res.( $\Omega$ )	1.3	1.0	0.5			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	RPM/KH/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Service Building		
Substation	Main Outdoor 27.6kV Incoming		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5D	Current	300	Amps
Style/Cat #	86644R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134250R4	Amps	150E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Poor	One only during inspection

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	688	627	623			

Results Satisfactory      Spares Required.

T.S.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**North America Pavilion**

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 14, 1999
<b>File Number</b>	6621	<b>Tested By</b>	JRK
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Loop Feeder to African Pavilion		
<b>Substation</b>	North American Pavilion		

**High Voltage Air/Load Break Switch**

Nameplate Data				
<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34063R2	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	N/A	
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	N/A	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	OK	
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>						
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	90	82	92			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.4	0.4	0.4			
<b>Results Satisfactory</b>	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Loop Feed to Service Building		
Substation	North American Pavilion		

## High Voltage Air/Load Break Switch

Nameplate Data				
Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063R2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	Fair Poor	Flash Marks Present on Barrier, etc.
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	90	81	80			
Arc Interrupter Res.( $\Omega$ )	0.4	0.3	0.5			
Results Satisfactory	See Recommendations					

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 14, 1999
<b>File Number</b>	6621	<b>Tested By</b>	JRK
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Paddock Feeders		
<b>Substation</b>	North American Pavilion		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34563R4-T2	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	OK	Kirk RE12053
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	N/A	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	Fair	Surfaces pitted
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	<i><math>\phi A</math></i>	<i><math>\phi B</math></i>	<i><math>\phi C</math></i>	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>	92	112	153	272	280	300
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	79	82	77			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.4	0.4	0.3			
<b>Results Satisfactory</b>	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Paddock Feeders		
Substation	North American Pavilion		

### High Voltage Power Fuse

Fuse Holder Nameplate Data				
Manufacturer	S&C	Voltage	27.6	kVolt
Type	SM-5	Current	300E	Amps
Style/Cat #		Serial #		

Fuse Link Nameplate Data			
Type	SM-5	TCC	119-4
Style/Cat #	264125-R4	Amps	80E

Mechanical Inspections		
Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Fair	One Spare Present in Cell

Electrical Tests						
Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	1005	1100	1060			
Results Satisfactory	OK					

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	American Pavilion Trans. #5		
Substation	North American Pavilion		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	Alduti	Current	600	Amps
Style #		B.L.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	37	37	40			
Arc Interrupter Res.( $\Omega$ )						
Results Satisfactory	OK					

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM/ TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	North American Pavilion Trans. #5		
Substation	North American Pavilion		

**High Voltage Power Fuse**

**Fuse Holder Nameplate Data**

Manufacturer	S&C	Voltage	27.6	kVolt
Type	SM-5	Current	300	Amps
Style/Cat #	86644R1	Serial #		

**Fuse Link Nameplate Data**

Type	SM-5	TCC	153-4
Style/Cat #	134025R4	Amps	15E

**Mechanical Inspections**

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	3 Spares in Cell

**Electrical Tests**

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	6190	6260	6050			

Results Satisfactory	OK
----------------------	----

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 14, 1999
<b>File Number</b>	6621	<b>Tested By</b>	RPM
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	T5		
<b>Substation</b>	North American Pavilion		

**Power Transformer -Electrical****Nameplate Data**

<b>Manufacturer</b>	Westinghouse	<b>Vector Group</b>	Y-Y		
<b>Type</b>	LNAN	<b>Serial #.</b>	827695		
<b>Neutral</b>	Solid	<b>Liquid Type/Vol</b>	Askarel	200	Gal
<b>Rating</b>	300/ 336	kVA	<b>Total Weight</b>	7020	lbs.
<b>Impedance</b>	5.4	%	<b>Primary Voltage</b>	27.6/ 16	kVolt
<b>Phase</b>	3	$\phi$	<b>Secondary Voltage</b>	208/ 120	Volt
<b>Frequency</b>	60	Hz	<b>BIL</b>	150/ 45	kVolt

**Insulation Tests**

<b>Insulation Resistance @ 5k / 1k VDC</b>	<b>Prim. With Sec. Grounded</b>	<b>Sec. With Prim. Grounded</b>	<b>Prim. &amp; Sec. To Ground</b>		
M $\Omega$	31.6	31.0			
<b>Corrected to 20 °C.</b>					
	<b>CH-L + G</b>	<b>CH-G</b>	<b>CH-L</b>	<b>CL-G</b>	<b>CL-H + G</b>
<b>Cap (pF)</b>		280		9154	
<b>Corr. 20 °C</b>					
<b>Dis. Fact.(%)</b>		5.70		6.56	
<b>Corr. 20 °C.</b>					

**Turns Ratio Tests**

<b>Tap</b>	<b>Primary Volts</b>	<b>Calculated Ratio</b>	<b><u>X0-X1.</u> H0-H1</b>	<b><u>X0-X2</u> H0-H2</b>	<b><u>X0-X3</u> H0-H3</b>
1					
2					
3	27,600	0.754	0.746	0.746	0.746
4					
5					
<b>Tap Position Found &amp; Left</b>		3 (27,600V)			
<b>Results Satisfactory</b>		OK			

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Sample Date</b>	June 14, 1999
<b>File Number</b>	6621	<b>Sampled By</b>	RPM
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	T5		
<b>Substation</b>	North American Pavilion		

**Oil Analysis****Transformer Data**

<b>Manufacturer</b>	Westinghouse	<b>Primary Volts</b>	27.6/ 16	<b>kVolts</b>
<b>Type</b>	LNAN	<b>Rating</b>	300/ 336	<b>kVA</b>
<b>Serial No.</b>	827695	<b>Liquid Volume</b>	200	<b>Gals.</b>

**Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	D877	30 kV	46.7
<b>Neutralization Number</b>	D974	0.05 Max. Mg Koh/G	0.008
<b>Interfacial Tension</b>	D971	32 Dynes/ Cm Min.	N/A
<b>Specific Gravity</b>	D1298	0.84 - 0.91 (Oil)	1.520
<b>Colour</b>	D1500	≤3.5	0.5
<b>Visual Condition</b>	D1524	Clear	Clear
<b>Water Content</b>	D1533	30 ppm (<69kV)	
<b>Power Factor</b>	D924	1.0 % Max @ 25 °C	
<b>PCB Content</b>	D4059	50 ppm Max.	
<b>Inhibitor</b>	D2668	≥0.20%	
<b>Furans</b>	D5837	<100 ppb	
<b>Hydrogen (H<sub>2</sub>)</b>			
<b>Oxygen &amp; Argon</b>			
<b>Nitrogen (N<sub>2</sub>)</b>			
<b>Methane (CH<sub>4</sub>)</b>			
<b>Carbon Monoxide (CO)</b>			
<b>Carbon Dioxide (CO<sub>2</sub>)</b>			
<b>Ethylene (C<sub>2</sub>H<sub>4</sub>)</b>			
<b>Ethane (C<sub>2</sub>H<sub>6</sub>)</b>			
<b>Acetylene (C<sub>2</sub> H<sub>2</sub>)</b>			
<b>Total Gas Content</b>			

**Comments**

<b>Chemical Properties</b>	OK
<b>PCB Content</b>	PCB fluid
<b>Dissolved Gas Content</b>	---

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM/ JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T5		
Substation	North American Pavilion		

## Power Transformer - Mechanical

### Mechanical Inspections

Description of Inspection	Status	Comments
Breather & Silica Gel	N/A	
Explosion Vent Gaskets	N/A	
Pressure Relief Device	OK	
Conservator Tank Gaskets	N/A	
Inspection Cover Gaskets	OK	
Main Cover Gaskets	N/A	
Primary Bushing Gaskets	OK	
Primary Bushing Porcelain	OK	
Primary Bushing Connections	OK	
Secondary Bushing Gaskets	OK	
Secondary Bushing Porcelain	OK	
Secondary Bushing Connections	OK	
Secondary Throat Gaskets	OK	
Radiator	OK	
Pressure Gauge	OK	
Gas Relay	N/A	
Oil Level	OK	
Oil Leaks	OK	
Tank Valves	OK	
Oil Temperature Gauge	OK	
Oil Temperature Run/Max	35   40°c	
Winding Temperature Gauge	N/A	
Winding Temperature Run/Max		
Tap Changer		Unit Locked: Inoperable
Paint Condition	OK	
Pad	OK	
Grounding	OK	
Fan Operation	N/A	
Control Wiring	N/A	
Results Satisfactory	OK	

T.S.

**TECHNICAL FIELD SERVICE DIVISION**  
**Special Projects Group**

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 14, 1999
<b>File Number</b>	6621	<b>Tested By</b>	RPM
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	T5 Secondary		
<b>Substation</b>	North American Pavilion		

**Bus Duct**

**Nameplate Data**

<b>Manufacturer</b>	Square D	<b>Voltage</b>	600	<b>Volts</b>
<b>Type</b>	I-Line	<b>Current</b>	1000	<b>Amps</b>
<b>Style</b>	3 Phase, 4 Wire	<b>B.I.L.</b>		<b>kVolts</b>
<b>Cat #</b>	AF-510-23-FES	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Bus Insulation</b>	OK	
<b>Type of Bus Insulation</b>	OK	
<b>Support Insulators</b>	OK	
<b>Interior Clean</b>	OK	Visible Sections Only
<b>Interior Dry</b>	OK	Visible Sections Only
<b>Bus Duct Enclosure</b>	OK	
<b>Bus Duct Enclosure Ventilated</b>	N/A	
<b>Bus Joints Clean &amp; Dry</b>	OK	
<b>Bus Joints Torqued</b>	OK	
<b>Gaskets at Joints</b>	OK	
<b>Grounding</b>	OK	
<b>Enclosure Paint Condition</b>	OK	
<b>Support Structure</b>	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>N</i>	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>	1120	1260	900	---	2520	2320	2200

**Comments**

**Results Satisfactory**    OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Main Secondary C.B.		
Substation	North American Pavilion		

## Low Voltage Air Circuit Breaker

### Nameplate Data

Manufacturer	ITE	Voltage	600	Volts
Type	K1600	Frame Rating	1600	Amps
Serial #	98012	Int. Rating	65	kAmps
Relay Type	OD4 Dashpots Only	Sensors Ratio		Amps
Rating Plug.		Limiter Rating	N/A	Amps

### Relay Calibration Results

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	1000A	Inst.						
Short Time								
Instantaneous								
			P/U	T.D.				
Ground Fault								

### Mechanical Inspections

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	OK	
Bus & Grounding Stabs	OK	
Interlocks	OK	Rack Out Only
Manual Operation	OK	
Electrical Operation	N/A	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	25	31	27			

Results Satisfactory	OK
----------------------	----

T.S.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Africa Pavilion**



**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 16, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Feeder to Indo-Malaya Pavilion		
<b>Substation</b>	Africa Pavilion		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti Indoor	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34063	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	N/A	
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	N/A	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	OK	
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>	780	540	755	3420	3280	4080
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	55	57	65			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.7	0.5	0.9			
<b>Results Satisfactory</b>	OK					

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 16, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Feeder to North America Pavilion		
<b>Substation</b>	Africa Pavilion		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34063	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	N/A	
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	N/A	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	OK	
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	<i><math>\phi A</math></i>	<i><math>\phi B</math></i>	<i><math>\phi C</math></i>	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (M<math>\Omega</math>)</b>	780	540	755	3420	3280	4080
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	38	36	36			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.7	1.4	0.8			

<b>Results Satisfactory</b>	OK
-----------------------------	----

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Africa Paddock Feeder		
Substation	Africa Pavilion		

**High Voltage Air/Load Break Switch****Nameplate Data**

Manufacturer	S&C	Voltage	27	kVolts
Type	SM Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	OK	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )	780	540	755	3420	3280	4080
Contact Resistance ( $\mu\Omega$ )	50	50	48			
Arc Interrupter Res.( $\Omega$ )	0.6	0.5	0.5			

Results Satisfactory OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Paddock Feeders		
Substation	Africa Pavilion		

### High Voltage Power Fuse

Fuse Holder Nameplate Data				
Manufacturer	S&C	Voltage	27.6	kVolt
Type	SM-5	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

Fuse Link Nameplate Data			
Type	SM-5	TCC	
Style/Cat #		Amps	

Mechanical Inspections		
Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	POOR	No Spares in Cell

Electrical Tests						
Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	1030	960	1030			
Results Satisfactory	Fair. Spares Required.					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH/ RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	McDonald Savannah (Africa Paddock Fed)		

### Pad-Mounted Distribution Transformer

Transformer Nameplate Data					
Manufacturer	Cam Tran	Year Built	1997		
Type	ONAN	Serial #	97DC231201		
Neutral	Solid	Liquid Type/Vol	Oil	1436	Litres
Rating	500	kVA	Total Weight	3492	Kg
Impedance	5.4	%	Primary Voltage	27.6/ 16	KVolt
Phase(s)	3	φ	Secondary Voltage	208/ 120	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)	>505,000				

### Oil Analysis

Laboratory Tests			
Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	44.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.027
Interfacial Tension	D971	32 Dynes/ Cm Min.	40.1
Specific Gravity	D1298	0.84 - 0.91	0.867
Colour	D1500	≤3.5 Max.	<0.5
Visual Condition	D1524	Clear	Clear

### Observations & Comments

Comments:	
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 16, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Padmount to Africa Sub. 3 phases; to T10 3 phases		

**Pad-Mounted Distribution Transformer****Transformer Nameplate Data**

<b>Manufacturer</b>	CARTE	<b>Year Built</b>	1996		
<b>Type</b>	ONAN	<b>Serial #</b>	2B301-001		
<b>Neutral</b>	Solid	<b>Liquid Type/Vol</b>	Oil	1023	Litres
<b>Rating</b>	225	kVA	<b>Total Weight</b>	2227	Lbs.
<b>Impedance</b>	4.34	%	<b>Primary Voltage</b>	27.6/ 16	kVolt
<b>Phase(s)</b>	3	φ	<b>Secondary Voltage</b>	208/ 120	Volt
<b>Frequency</b>	60	Hz	<b>BIL</b>	125	kVolt
<b>Insulation Resistance (MΩ)</b>	435,000				

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	D877	30 kV Min.	32.0
<b>Neutralization Number</b>	D974	0.05 Max. Mg Koh/G	0.013
<b>Interfacial Tension</b>	D971	32 Dynes/ Cm Min.	38.6
<b>Specific Gravity</b>	D1298	0.84 - 0.91	0.889
<b>Colour</b>	D1500	≤3.5 Max.	0.5
<b>Visual Condition</b>	D1524	Clear	Clear

**Observations & Comments**

<b>Comments:</b>	
<b>Results Satisfactory:</b>	OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	African Pavilion Trans. T-6		
Substation	African Pavilion		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	SM Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	780	540	755	3420	3280	4080
Contact Resistance ( $\mu\Omega$ )	38	36	36			
Arc Interrupter Res.( $\Omega$ )	0.7	1.4	0.8			
Results Satisfactory	OK					

T.S

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH/ AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	African Pavilion Transformer T-6		
Substation	African Pavilion		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolt
Type	SM-5	Current	300	Amps
Style/Cat #	86641R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134060R4	Amps	40E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	3 Spares in Cell

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	1760	1733	1760			

Results Satisfactory OK

T.S.



# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-6		
Substation	African Pavilion		

### Power Transformer -Electrical

#### Nameplate Data

Manufacturer	Westinghouse	Vector Group	Y-Y		
Type	LNAN	Serial #.	795154		
Neutral	Solid	Liquid Type/Vol	Askarel	350	Gal
Rating	750/ 850	kVA	Total Weight	11,900	lbs.
Impedance	6.0	%	Primary Voltage	27.6/ 16	kVolt
Phase	3	$\phi$	Secondary Voltage	208/ 120	Volt
Frequency	60	Hz	BIL	150/ 45	kVolt

#### Insulation Tests

Insulation Resistance @ 5k / 1k VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
M $\Omega$	27.2	27.8			
Corrected to 20 °C.	76.2	77.8			
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

#### Turns Ratio Tests

Tap	Primary Volts	Calculated Ratio	<u>X0-X1</u> H0-H1	<u>X0-X2</u> H0-H2	<u>X0-X3</u> H0-H3
1					
2					
3	27,600	0.754	0.747	0.747	0.747
4					
5					
Tap Position Found & Left		3 (27,600V)			
Results Satisfactory		OK			

T.S.

# TECHNICAL FIELD SERVICE DEPARTMENT

Special Projects Group

## Client Information

Customer	Toronto Zoo	Sample Date	June 17, 1999
File Number	6621	Sampled By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-6		
Substation	Africa Pavilion		

## Oil Analysis

### Transformer Data

Manufacturer	Westinghouse	Primary Volts	27.6/ 16	kVolts
Type	LNAN	Rating	750/ 850	kVA
Serial No.	795154	Liquid Volume	350	Gals.

### Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV	46.9
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.004
Interfacial Tension	D971	32 Dynes/ Cm Min.	N/A
Specific Gravity	D1298	0.84 - 0.91 (Oil)	1.520
Colour	D1500	≤3.5	0.5
Visual Condition	D1524	Clear	Clear
Water Content	D1533	30 ppm (<69kV)	
Power Factor	D924	1.0 % Max @ 25 °C	
PCB Content	D4059	50 ppm Max.	
Inhibitor	D2668	≥0.20%	
Furans	D5837	<100 ppb	
Hydrogen (H <sub>2</sub> )			
Oxygen & Argon			
Nitrogen (N <sub>2</sub> )			
Methane (CH <sub>4</sub> )			
Carbon Monoxide (CO)			
Carbon Dioxide (CO <sub>2</sub> )			
Ethylene (C <sub>2</sub> H <sub>4</sub> )			
Ethane (C <sub>2</sub> H <sub>6</sub> )			
Acetylene (C <sub>2</sub> H <sub>2</sub> )			
Total Gas Content			

### Comments

Chemical Properties	OK
PCB Content	PCB fluid
Dissolved Gas Content	---

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 16, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH/ RPM/ TL
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	T-6		
<b>Substation</b>	African Pavilion		

### Power Transformer -Mechanical

#### Mechanical Inspections

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Breather &amp; Silica Gel</b>	N/A	
<b>Explosion Vent Gaskets</b>	N/A	
<b>Pressure Relief Device</b>	OK	
<b>Conservator Tank Gaskets</b>	N/A	
<b>Inspection Cover Gaskets</b>	OK	
<b>Main Cover Gaskets</b>	N/A	
<b>Primary Bushing Gaskets</b>	OK	
<b>Primary Bushing Porcelain</b>	OK	
<b>Primary Bushing Connections</b>	OK	
<b>Secondary Bushing Gaskets</b>	OK	
<b>Secondary Bushing Porcelain</b>	OK	
<b>Secondary Bushing Connections</b>	OK	
<b>Secondary Throat Gaskets</b>	OK	
<b>Radiator</b>	OK	
<b>Pressure Gauge</b>	OK	-7 PSI Vacuum
<b>Gas Relay</b>	N/A	
<b>Oil Level</b>	OK	
<b>Oil Leaks</b>	OK	None visible
<b>Tank Valves</b>	OK	
<b>Oil Temperature Gauge</b>	OK	
<b>Oil Temperature Run/Max</b>	35   45°C	
<b>Winding Temperature Gauge</b>	N/A	
<b>Winding Temperature Run/Max</b>		
<b>Tap Changer</b>		Unit Locked: Inoperable
<b>Paint Condition</b>	OK	
<b>Pad</b>	OK	
<b>Grounding</b>	OK	
<b>Fan Operation</b>	N/A	
<b>Control Wiring</b>	N/A	
<b>Results Satisfactory</b>	OK	

T.S.

**TECHNICAL FIELD SERVICE DIVISION**  
**Special Projects Group**

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH/ TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-6 Secondary		
Substation	African Pavilion		

**Bus Duct**

Nameplate Data				
Manufacturer	Square D	Voltage	120/ 208	Volts
Type	Power Clad	Current	3000	Amps
Style	3 Phase, 4 Wire	B.I.L.		kVolts
Cat #	AF-510-23-FES	Serial #		

Mechanical Inspections		
Description of Inspection	Status	Comments
Bus Insulation	OK	
Type of Bus Insulation	OK	
Support Insulators	OK	
Interior Clean	OK	Visible Sections Only
Interior Dry	OK	Visible Sections Only
Bus Duct Enclosure	OK	
Bus Duct Enclosure Ventilated	N/A	
Bus Joints Clean & Dry	OK	
Bus Joints Torqued	OK	
Gaskets at Joints	OK	
Grounding	OK	
Enclosure Paint Condition	OK	
Support Structure	OK	

Electrical Tests							
Test Description	$\phi A$	$\phi B$	$\phi C$	N	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	1170	1570	1920	---	1080	1980	3180
Comments							
Results Satisfactory	OK						

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	RPM/ TL/ KH
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Main Secondary C.B.		
Substation	African Pavilion		

### Low Voltage Air Circuit Breaker

#### Nameplate Data

Manufacturer	FPE	Voltage	600	Volts
Type	75H-2	Frame Rating	3000	Amps
Serial #	TH-4126-72	Int. Rating	75	kAmps
Relay Type	Carriere FB600E	Sensors Ratio	3000:1	Amps
Rating Plug.	---	Limiter Rating	N/A	Amps

#### Relay Calibration Results

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D.	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	0.85x	7.5		6.021		5.896		
Short Time	7x	0.4		0.477		0.476		0.471
Instantaneous	10x			0.094		0.103		0.111
			P/U	T.D.				
Ground Fault	1200	0.066						

#### Mechanical Inspections

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	OK	
Bus & Grounding Stabs	OK	
Interlocks	OK	
Manual Operation	POOR	See Deficiencies
Electrical Operation		

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	40/ 70	49/ 50	49/ 48			

Results Satisfactory *NO. See Deficiencies.*

T.S.



***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Entrance/ Administration  
Building**

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Eurasia Pavilion		
Substation	Entrance/ Administration Building		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	CDT-2765378	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	58	61	65			
Arc Interrupter Res.( $\Omega$ )	2.0	0.4	1.9			
Results Satisfactory	OK					

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Indo-Malaya Pavilion		
Substation	Entrance/ Administration Building		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34163	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock		
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	77	83	86			
Arc Interrupter Res.( $\Omega$ )	0.43	0.40	0.40			
Results Satisfactory	OK					

T.S

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Village Edge South		
Substation	Entrance/ Administration Building		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	SM Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563-R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock		
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	28	28	35			
Arc Interrupter Res.( $\Omega$ )	0.3	0.3	0.5			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Village Edge South		
Substation	Entrance/ Administration Building		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134125R4	Amps	80E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Fair	One only in cell door

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	780	802	802			

Results Satisfactory      OK. Spare Links Required.

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 15, 1999
<b>File Number</b>	6621	<b>Tested By</b>	AS, AN
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Entrance Facilities Transformer T-7		
<b>Substation</b>	Entrance/ Administration Building		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27.6	<b>kVolts</b>
<b>Type</b>	SM Alduti Indoor	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34563R4-T2	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	N/A	
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	OK	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	OK	
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
<b>Insulation Resistance (G<math>\Omega</math>)</b>	>505	>505	>505	>505	>505	>505
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	71	72	75			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.4	0.2	0.2			
<b>Results Satisfactory</b>	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Entrance Facilities Transformer T-7		
Substation	Entrance/ Administration Building		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	86644R1	Amps	15E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	In Cell Door

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	5276	5318	5400			

Results Satisfactory      OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Entrance Facilities Transformer T-7		
Substation	Entrance/ Administration Building		

### Power Transformer - Electrical

#### Nameplate Data

Manufacturer	Westinghouse	Vector Group	Wye Wye		
Type	LNAN	Serial #.	827694		
Neutral	Solid	Liquid Type/Vol	Askarel	200	Gal
Rating	225	kVA	Total Weight	6450	lbs.
Impedance	5.9	%	Primary Voltage	27.6 Y	kVolt
Phase	3	$\phi$	Secondary Voltage	120/ 208	Volt
Frequency	60	Hz	BIL	150	kVolt

#### Insulation Tests

Insulation Resistance @ 5k / 1k VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
M $\Omega$	30	30			
Corrected to 20 °C.					
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

#### Turns Ratio Tests

Tap	Primary Volts	Calculated Ratio	$\frac{X0-X1}{H0-H1}$	$\frac{X0-X2}{H0-H2}$	$\frac{X0-X3}{H0-H3}$
1					
2					
3	27,600	0.753	0.748	0.748	0.748
4					
5					
Tap Position Found & Left		3 (27,600V)			
Results Satisfactory		OK			

T.S.

# TECHNICAL FIELD SERVICE DEPARTMENT

Special Projects Group

## Client Information

<b>Customer</b>	Toronto Zoo	<b>Sample Date</b>	June 15, 1999
<b>File Number</b>	6621	<b>Sampled By</b>	TL
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Entrance Facilities Transformer T-7		
<b>Substation</b>	Entrance/ Administration Building		

## Oil Analysis

### Transformer Data

<b>Manufacturer</b>	Westinghouse	<b>Primary Volts</b>	27.6/ 16	<b>kVolts</b>
<b>Type</b>	LNAN	<b>Rating</b>	225	<b>kVA</b>
<b>Serial No.</b>	827694	<b>Liquid Volume</b>	200	<b>Gals.</b>

### Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results	
			1999	
Dielectric Breakdown	D877	30 kV		49.4
Neutralization Number	D974	0.05 Max. Mg Koh/G		0.004
Interfacial Tension	D971	32 Dynes/ Cm Min.		N/A
Specific Gravity	D1298	0.84 - 0.91		1.420
Colour	D1500	≤3.5		0.5
Visual Condition	D1524	Clear		Clear
Water Content	D1533	30 ppm (<69kV)		
Power Factor	D924	1.0 % Max @ 25 °C		
PCB Content	D4059	50 ppm Max.		
Inhibitor	D2668	≥0.20%		
Furans	D5837	<100 ppb		
Hydrogen (H <sub>2</sub> )				
Oxygen & Argon				
Nitrogen (N <sub>2</sub> )				
Methane (CH <sub>4</sub> )				
Carbon Monoxide (CO)				
Carbon Dioxide (CO <sub>2</sub> )				
Ethylene (C <sub>2</sub> H <sub>4</sub> )				
Ethane (C <sub>2</sub> H <sub>6</sub> )				
Acetylene (C <sub>2</sub> H <sub>2</sub> )				
Total Gas Content				

### Comments

<b>Chemical Properties</b>	OK
<b>PCB Content</b>	PCB Insulating Fluid
<b>Dissolved Gas Content</b>	

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Entrance Facilities Transformer T-8		
Substation	Entrance/ Administration Building		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	SM Alduti Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	43	49	43			
Arc Interrupter Res.( $\Omega$ )	0.3	0.3	0.4			
Results Satisfactory	OK					

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	AS, AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Entrance Facilities Transformer T-8		
Substation	Entrance/ Administration Building		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	13440R4	Amps	25E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	In cell door

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	2439	2412	2451			

Results Satisfactory OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Entrance Facilities Transformer T-8		
Substation	Entrance/ Administration Building		

### Power Transformer -Electrical

#### Nameplate Data

Manufacturer	Westinghouse	Vector Group	Wye Wye		
Type	LNAN	Serial #.	850912		
Neutral	Solid	Liquid Type/Vol	Askarel	240	Gal
Rating	500	kVA	Total Weight	8500	lbs.
Impedance	6.7	%	Primary Voltage	27.6 Y	kVolt
Phase	3	$\phi$	Secondary Voltage	600	Volt
Frequency	60	Hz	BIL	150	kVolt

#### Insulation Tests

Insulation Resistance @ 5k / 1k VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
M $\Omega$	32	32			
Corrected to 20 °C.					
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

#### Turns Ratio Tests

Tap	Primary Volts	Calculated Ratio	$\frac{X0-X1}{H0-H1}$	$\frac{X0-X2}{H0-H2}$	$\frac{X0-X3}{H0-H3}$
1					
2					
3	27,600	2.173	2.178	2.178	2.178
4					
5					
Tap Position Found & Left		3 (27,600V)			
Results Satisfactory		OK			

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Sample Date</b>	June 15, 1999
<b>File Number</b>	6621	<b>Sampled By</b>	TL
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Entrance Facilities Transformer T-8		
<b>Substation</b>	Entrance/ Administration Building		

**Oil Analysis****Transformer Data**

<b>Manufacturer</b>	Westinghouse	<b>Primary Volts</b>	27.6/ 16	<b>kVolts</b>
<b>Type</b>	LNAN	<b>Rating</b>	225	<b>kVA</b>
<b>Serial No.</b>	850912	<b>Liquid Volume</b>	240	<b>Gals.</b>

**Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			99
<b>Dielectric Breakdown</b>	D877	30 kV	49.0
<b>Neutralization Number</b>	D974	0.05 Max. Mg Koh/G	0.004
<b>Interfacial Tension</b>	D971	32 Dynes/ Cm Min.	N/A
<b>Specific Gravity</b>	D1298	0.84 - 0.91	1.520
<b>Colour</b>	D1500	≤3.5	0.5
<b>Visual Condition</b>	D1524	Clear	Clear
<b>Water Content</b>	D1533	30 ppm (<69kV)	
<b>Power Factor</b>	D924	1.0 % Max @ 25 °C	
<b>PCB Content</b>	D4059	50 ppm Max.	
<b>Inhibitor</b>	D2668	≥0.20%	
<b>Furans</b>	D5837	<100 ppb	
<b>Hydrogen (H<sub>2</sub>)</b>			
<b>Oxygen &amp; Argon</b>			
<b>Nitrogen (N<sub>2</sub>)</b>			
<b>Methane (CH<sub>4</sub>)</b>			
<b>Carbon Monoxide (CO)</b>			
<b>Carbon Dioxide (CO<sub>2</sub>)</b>			
<b>Ethylene (C<sub>2</sub>H<sub>4</sub>)</b>			
<b>Ethane (C<sub>2</sub>H<sub>6</sub>)</b>			
<b>Acetylene (C<sub>2</sub> H<sub>2</sub>)</b>			
<b>Total Gas Content</b>			

**Comments**

<b>Chemical Properties</b>	OK
<b>PCB Content</b>	PCB Insulating Fluid
<b>Dissolved Gas Content</b>	

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.			
Substation	Zoological		

**High Voltage Air/Load Break Switch****Nameplate Data**

Manufacturer	S&C	Voltage	29	kVolts
Type	Alduti Rupter Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	CDT-2768678	Serial #		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	OK	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	60	58	56			
Arc Interrupter Res.( $\Omega$ )	1.3	1.1	1.5			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.			
Substation	Zoological		

## High Voltage Power Fuse

### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5	Current	600	Amps
Style/Cat #	86644R2	Serial #		

### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134025R4	Amps	15E

### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	3 Spares in Cell

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	5130	4865	5065			

Results Satisfactory      OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 18, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH/ TA
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Zoological		

**Pad-Mounted Distribution Transformer****Transformer Nameplate Data**

<b>Manufacturer</b>	CARTE	<b>Year Built</b>	1985		
<b>Type</b>	ONAN	<b>Serial #</b>	NO790-1		
<b>Neutral</b>	Solid	<b>Liquid Type/Vol</b>	Oil	872	Litres
<b>Rating</b>	300	kVA	<b>Total Weight</b>	1909	Kg
<b>Impedance</b>	4.58	%	<b>Primary Voltage</b>	27.6/ 16	KVOLT
<b>Phase(s)</b>	3	φ	<b>Secondary Voltage</b>	208/ 120	VOLT
<b>Frequency</b>	60	Hz	<b>BIL</b>	150	kVOLT
<b>Insulation Resistance (MΩ)</b>					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	<b>D877</b>	<b>30 kV Min.</b>	36.3
<b>Neutralization Number</b>	<b>D974</b>	<b>0.05 Max. Mg Koh/G</b>	0.014
<b>Interfacial Tension</b>	<b>D971</b>	<b>32 Dynes/ Cm Min.</b>	31.3
<b>Specific Gravity</b>	<b>D1298</b>	<b>0.84 - 0.91</b>	0.859
<b>Colour</b>	<b>D1500</b>	<b>≤3.5 Max.</b>	<0.5
<b>Visual Condition</b>	<b>D1524</b>	<b>Clear</b>	Clear

**Observations & Comments**

<b>Comments:</b>	
<b>Results Satisfactory:</b>	OK

T.S.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Service Building**

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Main Switchgear		
Substation	Service Building		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	58	59	57			
Arc Interrupter Res.( $\Omega$ )	0.3	0.3	0.3			
Results Satisfactory	OK					

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to North America Pavilion		
Substation	Service Building		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	56	55	57			
Arc Interrupter Res.( $\Omega$ )	0.5	0.6	0.5			

Results Satisfactory      OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 15, 1999
<b>File Number</b>	6621	<b>Tested By</b>	JC/ EJ
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Paddock Feeder WEST/ EAST		
<b>Substation</b>	Service Building		

**High Voltage Air/Load Break Switch****Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	27	<b>kVolts</b>
<b>Type</b>	Alduti	<b>Current</b>	600	<b>Amps</b>
<b>Style #</b>		<b>B.I.L.</b>	150	<b>kVolts</b>
<b>Cat #</b>	34563R4-T5	<b>Serial #</b>		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
<b>Key Interlock</b>	OK	
<b>Operating Mechanism</b>	OK	
<b>Operating Handle Grounding</b>	OK	
<b>Grounding Mat</b>	N/A	
<b>Stationary Contact Surfaces</b>	OK	
<b>Moving Contact Surfaces</b>	OK	
<b>Arcing Contact Surfaces</b>	OK	
<b>Contact Alignment</b>	OK	
<b>Arcing Interrupter</b>	OK	
<b>Connector Condition</b>	OK	
<b>Insulator Condition</b>	OK	
<b>Phase Barrier Condition</b>	OK	
<b>Support Structure Condition</b>	OK	

**Electrical Tests**

<i>Test Description</i>	<i>WEST</i>	<i>EAST</i>				
<b>Insulation Resistance (M<math>\Omega</math>)</b>						
<b>Contact Resistance (<math>\mu\Omega</math>)</b>	57	60	---			
<b>Arc Interrupter Res.(<math>\Omega</math>)</b>	0.6	0.7	---			
<b>Results Satisfactory</b>	OK. Single phase feeds x2					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Paddock Feeder WEST/ EAST		
Substation	Service Building		

### High Voltage Power Fuse

#### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300	Amps
Style/Cat #		Serial #		

#### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134125R4	Amps	80E

#### Mechanical Inspections

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	

#### Electrical Tests

<i>Test Description</i>	<i>WEST</i>	<i>EAST</i>				
Insulation Resistance (GΩ)	>505	>505	---	---	---	---
Contact Resistance (μΩ)	830	859	---			

Results Satisfactory      OK

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Service Building		
Substation	Service Building		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	OK	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	51	50	46			
Arc Interrupter Res.( $\Omega$ )	0.3	0.3	0.3			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Feeder to Service Building X-Former #4		
Substation	Service Building		

## High Voltage Power Fuse

Fuse Holder Nameplate Data				
Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

Fuse Link Nameplate Data			
Type	SM-5	TCC	153-4
Style/Cat #	134100R4	Amps	65E

Mechanical Inspections		
Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	

Electrical Tests						
Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	>505	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	1136	1044	1021			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T1 27.6kV-600V 3 $\phi$ 4W From HV Board		
Substation	Service Building		

### Power Transformer -Electrical

#### Nameplate Data

Manufacturer	Hammond		Vector Group	Wye Wye	
Type	ANN/ AFN		Serial #.	DB93F	
Neutral	Solid		Liquid Type/Vol	Dry	Type Gal
Rating	1500/ 2000	kVA	Total Weight	16500	lbs.
Impedance	5.7	%	Primary Voltage	27.6/ 15.935	kVolt
Phase	3	$\phi$	Secondary Voltage	600/ 347	Volt
Frequency	60	Hz	BIL	150	kVolt

#### Insulation Tests

Insulation Resistance @ 5k / 1k VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
M $\Omega$	10,000	10,000	10,000		
Corrected to 20 °C.					
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

#### Turns Ratio Tests

Tap	Primary Volts	Calculated Ratio	<u>X0-X2</u> H1-H2	<u>X0-X3</u> H2-H3	<u>X0-X1</u> H3-H1
1	28,980				
2	28,290				
3	27,600	2.177	2.174	2.174	2.174
4	26,910				
5	26,220				
Tap Position Found & Left		3-4 (27,600V)			
Results Satisfactory		OK			

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC/ EJ
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Secondary Breaker from T1		
Substation	Service Building		

## Low Voltage Air Circuit Breaker

### Nameplate Data

Manufacturer	FPE	Voltage	600	Volts
Type	75H-3	Frame Rating	3000	Amps
Serial #	BH-45339-93	Int. Rating	65	kAmps
Relay Type	USR	Sensors Ratio		Amps
Rating Plug.		Limiter Rating	N/A	Amps

### Relay Calibration Results

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	2x	1.1x						
Short Time	3X	0.3						
Instantaneous	OFF							
			P/U	T.D.				
Ground Fault	0.6	0.45						

### Mechanical Inspections

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	OK	
Bus & Grounding Stabs	OK	
Interlocks	OK	
Manual Operation	OK	
Electrical Operation	N/A	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	26	25	25			

Results Satisfactory      OK

T.S.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Eurasia Pavilion**



# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Main Switchgear		
Substation	Eurasia Pavilion		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063R2	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	236	232	278	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	48	52	61			
Arc Interrupter Res.( $\Omega$ )	1.2	1.3	1.6			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM/ AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Entrance Facilities		
Substation	Eurasia Pavilion		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063R2	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	236	232	278	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	39	42	40			
Arc Interrupter Res.( $\Omega$ )	3.1	2.0	3.6			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM/ AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Paddock Feeders (Centre & South)		
Substation	Eurasia Pavilion		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	SM-Alduti-Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34363R4-T5	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	POOR	Kirk RE12023 & RE12019
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	60	---	58			
Arc Interrupter Res.( $\Omega$ )	1.9	---	0.6			
Results Satisfactory	See Deficiencies.					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM/ AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Paddock Feeders (Centre & South)		
Substation	Eurasia Pavilion		

### High Voltage Power Fuse

#### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #		Serial #		

#### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134125R	Amps	80E

#### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Fair	Only One Spare Present in Cell

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	966	---	1286			

Results Satisfactory	Fair. See Recommendations.
----------------------	----------------------------

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Eurasia Pavilion Transformer -T1		
Substation	Eurasia Pavilion		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	SM-Alduti-Indoor	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	236	232	278	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	41	42	44			
Arc Interrupter Res.( $\Omega$ )	0.9	1.2	0.4			
Results Satisfactory	OK					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM/ AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Eurasia Pavilion Trans. #1		
Substation	Eurasia Pavilion		

### High Voltage Power Fuse

#### Fuse Holder Nameplate Data

Manufacturer	S&C	Voltage	34.5	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #	86644R1	Serial #		

#### Fuse Link Nameplate Data

Type	SM-5	TCC	153-4
Style/Cat #	134025R4	Amps	15E

#### Mechanical Inspections

Description of Inspection	Status	Comments
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	3 Spares in Cell

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	6020	5940	6080			

Results Satisfactory	OK
----------------------	----

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM/ TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment LD.	Eurasia Pav. Trans. T-1		
Substation	Eurasia Pavilion		

### Power Transformer -Electrical

#### Nameplate Data

Manufacturer	Westinghouse	Vector Group	Y-Y		
Type	LNAN	Serial #.	849380		
Neutral	Solid	Liquid Type/Vol	Askarel	200	Gal
Rating	225/ 252	kVA	Total Weight	6450	lbs.
Impedance	5.9	%	Primary Voltage	27.6/ 16	kVolt
Phase	3	$\phi$	Secondary Voltage	208/ 120	Volt
Frequency	60	Hz	BIL	150/ 45	kVolt

#### Insulation Tests

Insulation Resistance @ 5k / 500 VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
M $\Omega$	40.0	34.2			
Corrected to 20 °C.	112.0	95.8			
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

#### Turns Ratio Tests

Tap	Primary Volts	Calculated Ratio	<u>X0-X1</u> H0-H1	<u>X0-X2</u> H0-H2	<u>X0-X3</u> H0-H3
1					
2					
3	27,600	0.754	0.746	0.746	0.746
4					
5					
Tap Position Found & Left		3 (27,600V)			
Results Satisfactory		OK			

T.S.

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Sample Date</b>	June 18, 1999
<b>File Number</b>	6621	<b>Sampled By</b>	TL
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	T-1		
<b>Substation</b>	Eurasia Pavilion		

**Oil Analysis****Transformer Data**

<b>Manufacturer</b>	Westinghouse	<b>Primary Volts</b>	27.6/ 16	<b>kVolts</b>
<b>Type</b>	LNAN	<b>Rating</b>	225/ 252	<b>kVA</b>
<b>Serial No.</b>	849380	<b>Liquid Volume</b>	200	<b>Gals.</b>

**Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	D877	30 kV	48.8
<b>Neutralization Number</b>	D974	0.05 Max. Mg Koh/G	0.008
<b>Interfacial Tension</b>	D971	32 Dynes/ Cm Min.	N/A
<b>Specific Gravity</b>	D1298	0.84 - 0.91 (Oil)	1.520
<b>Colour</b>	D1500	≤3.5	0.5
<b>Visual Condition</b>	D1524	Clear	Clear
<b>Water Content</b>	D1533	30 ppm (<69kV)	
<b>Power Factor</b>	D924	1.0 % Max @ 25 °C	
<b>PCB Content</b>	D4059	50 ppm Max.	
<b>Inhibitor</b>	D2668	≥0.20%	
<b>Furans</b>	D5837	<100 ppb	
<b>Hydrogen (H2)</b>			
<b>Oxygen &amp; Argon</b>			
<b>Nitrogen (N2)</b>			
<b>Methane (CH4)</b>			
<b>Carbon Monoxide (CO)</b>			
<b>Carbon Dioxide (CO2)</b>			
<b>Ethylene (C2H4)</b>			
<b>Ethane (C2H6)</b>			
<b>Acetylene (C2 H2)</b>			
<b>Total Gas Content</b>			

**Comments**

<b>Chemical Properties</b>	OK
<b>PCB Content</b>	PCB fluid
<b>Dissolved Gas Content</b>	---

T.S.



# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Eurasia Pavilion Transformer T-1		
Substation	Eurasia Pavilion		

### Power Transformer -Mechanical

#### Mechanical Inspections

Description of Inspection	Status	Comments
Breather & Silica Gel	N/A	
Explosion Vent Gaskets	N/A	
Pressure Relief Device	OK	
Conservator Tank Gaskets	N/A	
Inspection Cover Gaskets	OK	
Main Cover Gaskets	N/A	
Primary Bushing Gaskets	OK	
Primary Bushing Porcelain	POOR	H3 top skirt split/ cracked
Primary Bushing Connections	OK	
Secondary Bushing Gaskets	OK	
Secondary Bushing Porcelain	OK	
Secondary Bushing Connections	OK	
Secondary Throat Gaskets	OK	
Radiator	OK	
Pressure Gauge	OK	-0.8 PSI Vacuum
Gas Relay	N/A	
Oil Level	OK	
Oil Leaks	OK	None Visible
Tank Valves	OK	
Oil Temperature Gauge	OK	
Oil Temperature Run/Max	34   41°C	
Winding Temperature Gauge	N/A	
Winding Temperature Run/Max		
Tap Changer		Unit Locked: Inoperable
Paint Condition	OK	
Pad	OK	
Grounding	OK	One-point grounding
Fan Operation	N/A	
Control Wiring	N/A	
Results Satisfactory	Fair. See Deficiencies.	

T.S.



**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-1 Secondary		
Substation	Eurasia Pavilion		

**Bus Duct****Nameplate Data**

Manufacturer	Square D	Voltage	600	Volts
Type	I-Line	Current	800	Amps
Style	3 Phase, 4 Wire	B.I.L.		kVolts
Cat #	AF-510-23-FES	Serial #	T1	

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Bus Insulation	OK	
Type of Bus Insulation	OK	
Support Insulators	OK	
Interior Clean	OK	Visible Sections Only
Interior Dry	OK	Visible Sections Only
Bus Duct Enclosure	OK	
Bus Duct Enclosure Ventilated	N/A	
Bus Joints Clean & Dry	OK	
Bus Joints Torqued	OK	
Gaskets at Joints	OK	
Grounding	OK	
Enclosure Paint Condition	OK	
Support Structure	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>N</i>	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )	2060	1990	2250	—	4780	4980	5500
Comments							
Results Satisfactory	OK						

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Main Secondary C.B.		
Substation	Eurasia Pavilion		

## Low Voltage Air Circuit Breaker

### Nameplate Data

Manufacturer	ITE	Voltage	600	Volts
Type	K-1600	Frame Rating	1600	Amps
Serial #	98013	Int. Rating	65	kAmps
Relay Type	OD4 Dashpots Only	Sensors Ratio	800	Amps
Rating Plug.		Limiter Rating	N/A	Amps

### Relay Calibration Results

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D.	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	800A	Inst.						
Short Time	3200A							
Instantaneous								
			P/U	T.D.				
Ground Fault	—							

### Mechanical Inspections

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	OK	
Bus & Grounding Stabs	OK	
Interlocks	OK	Rack Out Only
Manual Operation	OK	
Electrical Operation	N/A	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	58	64	52			

Results Satisfactory      OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Weston Station Transformer		

**Padmounted Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Federal Pioneer	Year Built	1976		
Type	ONAN	Serial #	A11808-1		
Neutral	Solid	Liquid Type/Vol	Oil	260	Gal
Rating	225	kVA	Total Weight	4650	lbs.
Impedance		%	Primary Voltage	27.6/ 16	kVolt
Phase(s)	3	φ	Secondary Voltage	208/ 120	Volt
Frequency	60	Hz	BIL		kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	37.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	27.1
Specific Gravity	D1298	0.84 - 0.91	0.853
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:

- IFT of the oil is marginal.
- This station's switchgear was reported to be in POOR condition*

Results Satisfactory: *FAIR/ Poor*

T.S.

*Technical Field Service Department*

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Indo-Malaya Pavilion**

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Loop Feeder to Entrance Facilities		
Substation	Indo-Malaya Pavilion		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	Fair	B $\phi$ terminator skirt broken off.
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (G $\Omega$ )	438	>505	>505	>505	>505	>505
Contact Resistance ( $\mu\Omega$ )	55	47	52			
Arc Interrupter Res.( $\Omega$ )	0.9	0.6	0.7			
Results Satisfactory	OK/ Fair. See Deficiencies.					

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Feeder to Africa Pavilion		
Substation	Indo-Malaya Pavilion		

**High Voltage Air/Load Break Switch****Nameplate Data**

Manufacturer	S&C	Voltage	27	kVolts
Type	Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34063	Serial #		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	62	56	52			
Arc Interrupter Res.( $\Omega$ )	0.6	0.7	0.5			
Results Satisfactory	OK					

T.S.



# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Indo-Malaya Paddock Feeder		
Substation	Indo-Malaya Pavilion		

### High Voltage Air/Load Break Switch

#### Nameplate Data

Manufacturer	S&C	Voltage	27.6	kVolts
Type	SM-Alduti	Current	600	Amps
Style #		B.I.L.	150	kVolts
Cat #	34563R4-T5	Serial #		

#### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	OK	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	OK	
Contact Alignment	OK	
Arcing Interrupter	Poor	Operator is defective
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

#### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	---	---	62			
Arc Interrupter Res.( $\Omega$ )	---	---	*			
Results Satisfactory	Fair. See Deficiencies.					

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 17, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Indo-Malaya Paddock Feeder		
<b>Substation</b>	Indo-Malaya Pavilion		

**High Voltage Power Fuse****Fuse Holder Nameplate Data**

<b>Manufacturer</b>	S&C	<b>Voltage</b>	34.5	<b>kVolt</b>
<b>Type</b>	SM-5	<b>Current</b>	300	<b>Amps</b>
<b>Style/Cat #</b>	86644R1	<b>Serial #</b>		

**Fuse Link Nameplate Data**

<b>Type</b>	SM-5	<b>TCC</b>	
<b>Style/Cat #</b>		<b>Amps</b>	

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	Poor	No Spares in Cell

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )			1015			

<b>Results Satisfactory</b>	Fair. Spare links required.
-----------------------------	-----------------------------

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Indo-Malaya Transformer T2		
Substation	Indo-Malaya Pavilion		

## High Voltage Air/Load Break Switch

### Nameplate Data

Manufacturer	S&C	Voltage	27	kVolts
Type	SM - Alduti	Current	600	Amps
Style #		B.L.L.	150	kVolts
Cat #	34563R4-T2	Serial #		

### Mechanical Inspections

Description of Inspection	Status	Comments
Key Interlock	N/A	
Operating Mechanism	OK	
Operating Handle Grounding	N/A	
Grounding Mat	N/A	
Stationary Contact Surfaces	OK	
Moving Contact Surfaces	OK	
Arcing Contact Surfaces	Fair	Surfaces pitted
Contact Alignment	OK	
Arcing Interrupter	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	50	46	48			
Arc Interrupter Res.( $\Omega$ )	1.0	0.5	0.8			
Results Satisfactory	OK					

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Indo-Malaya Transformer T2		
Substation	Indo-Malaya Pavilion		

**High Voltage Power Fuse****Fuse Holder Nameplate Data**

Manufacturer	S&C	Voltage	27.6	kVolt
Type	SM-5S	Current	300E	Amps
Style/Cat #		Serial #		

**Fuse Link Nameplate Data**

Type	SM-5	TCC	153-4
Style/Cat #	134040R4	Amps	25E

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Operating Mechanism	OK	
Contact Surfaces	OK	
Contact Penetration	OK	
Contact Alignment	OK	
Fuse Barrel	OK	
Connector Condition	OK	
Insulator Condition	OK	
Phase Barrier Condition	OK	
Support Structure Condition	OK	
Spare Fuses	OK	3 Spares in Cell

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )						
Contact Resistance ( $\mu\Omega$ )	3024	3055	3148			
Results Satisfactory	OK					

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Indo-Malaya Pavilion Trans. T-2		
Substation	Indo-Malaya Pavilion		

**Power Transformer -Electrical****Nameplate Data**

Manufacturer	Westinghouse	Vector Group	Y-Y		
Type	LNAN	Serial #.	795156		
Neutral	Solid	Liquid Type/Vol	Askarel	220	Gal
Rating	500/ 560	kVA	Total Weight	8500	lbs.
Impedance	7.1	%	Primary Voltage	27.6/ 16	kVolt
Phase	3	φ	Secondary Voltage	208/ 120	Volt
Frequency	60	Hz	BIL	150/ 45	kVolt

**Insulation Tests**

Insulation Resistance @ 5k / 1k VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
MΩ	28.0	24.2			
Corrected to 20 °C.	78.4	67.8			
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)					
Corr. 20 °C					
Dis. Fact.(%)					
Corr. 20 °C.					

**Turns Ratio Tests**

Tap	Primary Volts	Calculated Ratio	<u>X0-X1</u> H0-H1	<u>X0-X2</u> H0-H2	<u>X0-X3</u> H0-H3
1					
2					
3	27,600	0.754	0.746	0.746	0.746
4					
5					
Tap Position Found & Left		3 (27,600V)			
Results Satisfactory		OK			

T.S.

# TECHNICAL FIELD SERVICE DEPARTMENT

Special Projects Group

## Client Information

Customer	Toronto Zoo	Sample Date	June 17, 1999
File Number	6621	Sampled By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-2		
Substation	Indo-Malaya Pavilion		

## Oil Analysis

### Transformer Data

Manufacturer	Westinghouse	Primary Volts	27.6/ 16	kVolts
Type	LNAN	Rating	500/ 560	kVA
Serial No.	795156	Liquid Volume	220	Gals.

### Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV	48.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.012
Interfacial Tension	D971	32 Dynes/ Cm Min.	N/A
Specific Gravity	D1298	0.84 - 0.91 (Oil)	1.420
Colour	D1500	≤3.5	0.5
Visual Condition	D1524	Clear	Clear
Water Content	D1533	30 ppm (<69kV)	
Power Factor	D924	1.0 % Max @ 25 °C	
PCB Content	D4059	50 ppm Max.	
Inhibitor	D2668	≥0.20%	
Furans	D5837	<100 ppb	
Hydrogen (H2)			
Oxygen & Argon			
Nitrogen (N2)			
Methane (CH4)			
Carbon Monoxide (CO)			
Carbon Dioxide (CO2)			
Ethylene (C2H4)			
Ethane (C2H6)			
Acetylene (C2 H2)			
Total Gas Content			

### Comments

Chemical Properties	OK
PCB Content	PCB fluid
Dissolved Gas Content	---

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-2		
Substation	Indo-Malaya Pavilion		

### Power Transformer -Mechanical

#### Mechanical Inspections

Description of Inspection	Status	Comments
Breather & Silica Gel	N/A	
Explosion Vent Gaskets	N/A	
Pressure Relief Device	OK	
Conservator Tank Gaskets	N/A	
Inspection Cover Gaskets	OK	
Main Cover Gaskets	N/A	Welded Top
Primary Bushing Gaskets	OK	
Primary Bushing Porcelain	OK	
Primary Bushing Connections	OK	
Secondary Bushing Gaskets	OK	
Secondary Bushing Porcelain	OK	
Secondary Bushing Connections	OK	
Secondary Throat Gaskets	OK	
Radiator	OK	
Pressure Gauge	OK	-0.5 lb. Vacuum
Gas Relay	N/A	
Oil Level	OK	
Oil Leaks	OK	None Present
Tank Valves	OK	
Oil Temperature Gauge	OK	
Oil Temperature Run/Max	37   40°C	
Winding Temperature Gauge	N/A	
Winding Temperature Run/Max		
Tap Changer		Unit Locked: Inoperable
Paint Condition	OK	
Pad	OK	
Grounding	OK	One-point grounding
Fan Operation	N/A	
Control Wiring	N/A	
Results Satisfactory	OK	

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	T-2 Secondary		
Substation	Indo-Malaya Pavilion		

**Bus Duct****Nameplate Data**

Manufacturer	FPE	Voltage	120/208	Volts
Type	Power Clad	Current	1600	Amps
Style	3 Phase, 4 Wire	B.I.L.		kVolts
Cat #	08-01599	Serial #		

**Mechanical Inspections**

<i>Description of Inspection</i>	<i>Status</i>	<i>Comments</i>
Bus Insulation	OK	
Type of Bus Insulation	OK	
Support Insulators	OK	
Interior Clean	OK	Visible Sections Only
Interior Dry	OK	Visible Sections Only
Bus Duct Enclosure	OK	
Bus Duct Enclosure Ventilated	N/A	
Bus Joints Clean & Dry	OK	
Bus Joints Torqued	OK	
Gaskets at Joints	OK	
Grounding	OK	
Enclosure Paint Condition	OK	
Support Structure	OK	

**Electrical Tests**

<i>Test Description</i>	$\phi A$	$\phi B$	$\phi C$	<i>N</i>	<i>A/B</i>	<i>B/C</i>	<i>C/A</i>
Insulation Resistance (M $\Omega$ )	1260	1140	1090	---	1980	2160	3280

Comments

Results Satisfactory OK

T.S.



# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	Main Secondary C.B.		
Substation	Indo-Malaya Pavilion		

## Low Voltage Air Circuit Breaker

### Nameplate Data

Manufacturer	FPE	Voltage	600	Volts
Type	50H-2	Frame Rating	1600	Amps
Serial #	TH-4123.72	Int. Rating	50	kAmps
Relay Type	Carriere FB600E	Sensors Ratio	1600:1	Amps
Rating Plug.	---	Limiter Rating	N/A	Amps

### Relay Calibration Results

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D.	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	0.9x	7.5		5.809		5.881		5.963
Short Time	6x	0.40		0.451		0.445		0.450
Instantaneous	10x			0.055		0.065		0.064
			P/U	T.D.				
Ground Fault	0.4x	0.4		0.415				

### Mechanical Inspections

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	Fair/ Poor	Front Barrier Missing
Bus & Grounding Stabs	OK	
Interlocks	OK	Rack Out Only
Manual Operation	OK	
Electrical Operation	N/A	

### Electrical Tests

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	14	17	22			
Results Satisfactory	OK/ Fair					

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scar., Ontario		
Equipment I.D.	DP MB		
Substation	Indo-Malaya Pavilion		

**Low Voltage Air Circuit Breaker****Nameplate Data**

Manufacturer	FPE	Voltage	600	Volts
Type	50H-2	Frame Rating	1600	Amps
Serial #	TH-4124/72	Int. Rating	50	kAmps
Relay Type	Carriere FB600E	Sensors Ratio	1600:1	Amps
Rating Plug.	---	Limiter Rating	N/A	Amps

**Relay Calibration Results**

	Settings		$\phi A$		$\phi B$		$\phi C$	
	P/U	T.D	P/U	T.D.	P/U	T.D.	P/U	T.D.
Long Time	0.65x	7.5		5.945		6.204		6.110
Short Time	4x	0.25		0.282		0.300		0.284
Instantaneous	6x			0.124		0.104		0.108
			P/U	T.D.				
Ground Fault	0.4x	0.4		0.26				

**Mechanical Inspections**

Description of Inspection	Status	Comments
Main & Arcing Contacts	OK	
Arc Chutes	OK	
Phase Barriers	Fair	Front Barriers Cracked
Bus & Grounding Stabs	OK	
Interlocks	OK	Rack Out Only
Manual Operation	Poor (as found)	Mechanism restored to operation
Electrical Operation	N/A	

**Electrical Tests**

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	>999	>999	>999	>999	>999	>999
Contact Resistance ( $\mu\Omega$ )	32	24	28			

Results Satisfactory      Fair as found.

T.S.

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Cable Tests**

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 14-18, 1999
<b>File Number</b>	6621	<b>Tested By</b>	RPM/ KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Loop Feed Underground Power Cables		
<b>Substation</b>	Various		

**Power Cable Inspection****Cable Nameplate Data**

<b>Manufacturer</b>		<b>Voltage</b>	28	<b>kVolts</b>
<b>Insulation Type</b>	XLPE	<b>Ambient Temp.</b>		OC
<b>Conductor Type</b>	Copper (CU)	<b>Humidity</b>		%

**Electrical Test**

<b>Feeder Identification</b>	<b>Insulation Resistance (MΩ)</b>					
	<b>φA</b>	<b>φB</b>	<b>φC</b>	<b>A/B</b>	<b>B/C</b>	<b>C/A</b>
Incoming Outdoor 27.6kV Feeder	68,000	7,700	725	18,100	4,900	34,000
Main Switchgear to Eurasia Pavilion	750	790	785	3,960	4,080	3,920
Main Switchgear to Service Building	805	800	680	4,180	3,700	3,760
Service Bld. to N. America Pavilion	680	710	660	3,400	3,400	3,200
N. America to Africa Pavilion	670	715	680	3,500	3,600	3,380
Africa to Indo-Malaya Pavilion	665	555	665	3,000	3,000	3,340
Ent./ Admin. to Eurasia Pavilion (with Lightning Arrestors connected)	386	396	402	2,040	2,100	2,040
Ent./ Admin. to Indo-Malaya Pavilion	760	810	760	4,080	3,980	3,940

**Results Satisfactory**

T.S.

# TECHNICAL FIELD SERVICE DIVISION

Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 28, 1999
File Number	6693	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment LD.	Loop Feed to Indo-Malaya Pavilion ( <i>tested after <math>\phi B</math> splice repair</i> )		
Substation	Africa Pavilion		

## Cable High-Potential Test

### Cable Nameplate Data

Manufacturer		Voltage	28	kVolts
Insulation Type	XLPE	Conductor Size	3/0	MCM
Conductor Type	Copper (CU)	Temp. & Hum.	28	OC

### Electrical Test

Test Voltage @ 25 kVdc. Voltage Increments	Leakage Current		
	$\phi A$	$\phi B$	$\phi C$
5 kV	17	14	13
10 kV	35	33	39
15 kV	55	47	27
20 kV	45	50	32
25 kV	64	68	46
<b>Time at Test Voltage</b>			
30 Seconds	46	48	27
1 Minute	43	46	25
2 Minutes	39	44	23
3 Minutes	36	43	20
4 Minutes	35	42	18
5 Minutes	34	41	17
6 Minutes			
7 Minutes			
8 Minutes			
9 Minutes			
10 Minutes			
11 Minutes			
12 Minutes			
13 Minutes			
14 Minutes			
15 Minutes			

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )	675	436	1270	1210	1530	1880
Results Satisfactory	$\phi C$ in best condition of 3 cables tested.					

T.S.

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 25, 1999
File Number	6693	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Loop Feed to North America Pavilion ( <i>tested after <math>\phi B</math> splice repair</i> )		
Substation	Africa Pavilion		

### Cable High-Potential Test

#### Cable Nameplate Data

Manufacturer	Pirelli	Voltage	28	kVolts
Insulation Type	XLPE	Conductor Size	3/0	MCM
Conductor Type	Copper (CU)	Temp. & Hum.	28	OC

#### Electrical Test

Test Voltage @ 25 kVdc.	Leakage Current		
	$\phi A$	$\phi B$	$\phi C$
Voltage Increments			
4 kV	63	87	35
8 kV	80	79	43
12 kV	141	98	57
16 kV	149	142	63
20 kV	157	124	105
Time at Test Voltage			
30 Seconds	0.8	48	8
1 Minute	0.7	46	0
2 Minutes	0.7	44	0
3 Minutes	0.8	43	0
4 Minutes	0.9	42	0
5 Minutes	0.7	41	0
6 Minutes			
7 Minutes			
8 Minutes			
9 Minutes			
10 Minutes			
11 Minutes			
12 Minutes			
13 Minutes			
14 Minutes			
15 Minutes			

Test Description	$\phi A$	$\phi B$	$\phi C$	A/B	B/C	C/A
Insulation Resistance (M $\Omega$ )						
Results Satisfactory	$\phi C$ in best condition of 3 cables tested.					

T.S.

T.S. HV\_Hypot

***Technical Field Service Department***

---

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**SUBMERSIBLE  
Distribution Transformers**

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	KH/RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #1		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	971935		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	∅	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	36.5
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.9
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>H1B elbow burnt.</li> <li>Elbow &amp; transformer bushing insert should be replaced.</li> </ul>
Results Satisfactory:	<i>POOR</i>

T.S.



**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #2		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	McGraw Edison	Year Built			
Type	ONAN	Serial #	336007-2		
Neutral	Solid	Liquid Type/Vol	Oil	255	Lit
Rating	100	kVA	Total Weight	522	Kg
Impedance	1.7	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	39.5
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.007
Interfacial Tension	D971	32 Dynes/ Cm Min.	29.5
Specific Gravity	D1298	0.84 - 0.91	0.860
Colour	D1500	≤3.5 Max.	1.0
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	-Red phase connection found loose at the tank. -IFT is borderline. Monitor for deterioration.
Results Satisfactory:	OK/ Fair

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #6		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861979		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	35.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.8
Specific Gravity	D1298	0.84 - 0.91	0.849
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM/JRK/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #7		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861975 White Ø: 861980 Blue Ø: 871930		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	45.1	37.7	49.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.021	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.9	31.4	31.7
Specific Gravity	D1298	0.84 - 0.91	0.849	0.849	0.849
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	• Below marginal oil levels on all units.
Results Satisfactory:	Fair.

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	RPM/TL
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #8		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 871939 White Ø: 871938 Blue Ø: WO383007		
Neutral	Solid	Liquid Type/Vol	Oil	27	Gal
Rating	50	kVA	Total Weight	770	Lbs.
Impedance	1.9	%	Primary Voltage	16	KVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	KVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	42.5	43.1	43.0
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.007	0.021	0.020
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.9	31.4	26.6
Specific Gravity	D1298	0.84 - 0.91	0.850	0.853	0.859
Colour	D1500	≤3.5 Max.	0.5	1.0	<0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>-Red phase oil level is marginal.</li> <li>-Blue phase vault initially inaccessible. The water level in this vault does cover the transformer at times.</li> <li>-Blue phase IFT is borderline.</li> <li>-White phase vault ground to lid is off.</li> </ul>
-----------	---

Results Satisfactory: OK/ Fair

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #11		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861953		
Neutral	Solid	Liquid Type/Vol	Oil	34	Gal
Rating	75	kVA	Total Weight	1080	lbs.
Impedance	20	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	47.5
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.034
Interfacial Tension	D971	32 Dynes/ Cm Min.	34.8
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	$\leq 3.5$ Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>No lock on lid</li> <li>Both hinges broken</li> </ul>
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault 11A		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Carte	Year Built	1988		
Type	ONAN	Serial #	Q1431-28		
Neutral	Solid	Liquid Type/Vol	Oil	186	Lit
Rating	75	kVA	Total Weight	451	Kg
Impedance	2.29	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	46.7
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.013
Interfacial Tension	D971	32 Dynes/ Cm Min.	35.2
Specific Gravity	D1298	0.84 - 0.91	0.876
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	• No lock on vault
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM/JRK/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #12		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1974		
Type	ONAN	Serial #'s	Red Ø: 861968 White Ø:861963 Blue Ø: 861987		
Neutral	Solid	Liquid Type/Vol	Oil	27	Gal
Rating	50	kVA	Total Weight	770	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	38.4	42.8	37.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.014	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.1	30.0	30.4
Specific Gravity	D1298	0.84 - 0.91	0.850	0.851	0.849
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	- Oil levels marginal.
Results Satisfactory:	OK

T.S.

## Special Projects Group

## Client Information

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #13 - Old Elephant House		

## Submersible Distribution Transformer

## Transformer Nameplate Data

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861950 White Ø: 861-954 Blue Ø: 861951		
Neutral	Solid	Liquid Type/Vol	Oil	34	Gal
Rating	75	kVA	Total Weight	1080	lbs.
Impedance	2.0	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL		125lt
Insulation Resistance (MΩ)					

## Oil Analysis

## Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	47.4	38.7	42.7
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.028	0.041
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.7	32.4	30.6
Specific Gravity	D1298	0.84 - 0.91	0.484	0.847	0.853
Colour	D1500	≤3.5 Max.	0.5	0.5	1.0
Visual Condition	D1524	Clear	Clear	Clear	Clear

## Observations &amp; Comments

Comments:	- Blue phase oil level below manufacturer's indication line.
Results Satisfactory:	OK

T.S.

T.S. P\_Trans\_Elect



**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment LD.	Vault #13A		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1982		
Type	ONAN	Serial #'s	Red Ø: LG37989 White Ø: LG37991 Blue Ø: LG37990		
Neutral	Solid	Liquid Type/Vol	Oil	70	Gal
Rating	25	kVA	Total Weight	240	lbs.
Impedance	1.8	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	44.4	47.6	41.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014	0.021	0.027
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.0	25.7	29.5
Specific Gravity	D1298	0.84 - 0.91	0.856	0.853	0.856
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>The oil levels of these units were noted as marginal during the inspection.</li> <li>Note the marginal White φ IFT.</li> <li>The White phase unit subsequently failed and was replaced. (See following Oil test sheet for new unit lab results)</li> </ul>
-----------	---

Results Satisfactory: OK/ Fair

**TECHNICAL FIELD SERVICE DEPARTMENT**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Sample Date	June 28, 1999
File Number	6621	Sampled By	JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #13A Pachyderm Centre/ White phase		
Substation	Outside Elephant Paddock (Fed from Africa Pavilion)		

**Oil Analysis****Transformer Data**

Manufacturer	Cam Tran Co.	Primary Volts	27.6/ 16	kVolts
Type	ONAN Submersible	Rating	100	kVA
Serial No.	99C0846101	Liquid Volume	194	Litres

**Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV	42.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.027
Interfacial Tension	D971	32 Dynes/ Cm Min.	37.7
Specific Gravity	D1298	0.84 - 0.91	0.818
Colour	D1500	≤3.5	<0.5
Visual Condition	D1524	Clear	Clear
Water Content	D1533	30 ppm (<69kV)	
Power Factor	D924	1.0 % Max @ 25 °C	0.014%
PCB Content	D4059	50 ppm Max.	
Inhibitor	D2668	≥0.20%	
Furans	D5837	<100 ppb	
Hydrogen (H <sub>2</sub> )			
Oxygen & Argon			
Nitrogen (N <sub>2</sub> )			
Methane (CH <sub>4</sub> )			
Carbon Monoxide (CO)			
Carbon Dioxide (CO <sub>2</sub> )			
Ethylene (C <sub>2</sub> H <sub>4</sub> )			
Ethane (C <sub>2</sub> H <sub>6</sub> )			
Acetylene (C <sub>2</sub> H <sub>2</sub> )			
Total Gas Content			

**Comments**

Chemical Properties	OK
PCB Content	N/A
Dissolved Gas Content	---

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 17, 1999
<b>File Number</b>	6621	<b>Tested By</b>	KH
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Vault #14		

**Submersible Distribution Transformer****Transformer Nameplate Data**

<b>Manufacturer</b>	Westinghouse	<b>Year Built</b>	1973		
<b>Type</b>	ONAN	<b>Serial #</b>	861970		
<b>Neutral</b>	Solid	<b>Liquid Type/Vol</b>	Oil	16	Gal
<b>Rating</b>	25	kVA	<b>Total Weight</b>	465	lbs.
<b>Impedance</b>	1.9	%	<b>Primary Voltage</b>	16	kVolt
<b>Phase(s)</b>	1	$\phi$	<b>Secondary Voltage</b>	120/ 240	Volt
<b>Frequency</b>	60	Hz	<b>BIL</b>	125	kVolt
<b>Insulation Resistance (M<math>\Omega</math>)</b>					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	<b>D877</b>	<b>30 kV Min.</b>	44.1
<b>Neutralization Number</b>	<b>D974</b>	<b>0.05 Max. Mg Koh/G</b>	0.028
<b>Interfacial Tension</b>	<b>D971</b>	<b>32 Dynes/ Cm Min.</b>	33.4
<b>Specific Gravity</b>	<b>D1298</b>	<b>0.84 - 0.91</b>	0.848
<b>Colour</b>	<b>D1500</b>	<b><math>\leq</math>3.5 Max.</b>	0.5
<b>Visual Condition</b>	<b>D1524</b>	<b>Clear</b>	Clear

**Observations & Comments**

<b>Comments:</b>	
<b>Results Satisfactory:</b>	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH/TL/AN
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #16		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861969 White Ø: 861978 Blue Ø: 861977		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	43.9	37.9	46.2
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.014	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.9	32.1	32.8
Specific Gravity	D1298	0.84 - 0.91	0.849	0.849	0.849
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	OK

T.S.

T.S. P\_Trans\_Elect

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #16		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1974		
Type	ONAN	Serial #	861966		
Neutral	Solid	Liquid Type/Vol	Oil	27	Gal
Rating	50	kVA	Total Weight	770	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	44.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.034
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.2
Specific Gravity	D1298	0.84 - 0.91	0.850
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	IFT is borderline
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	TL/RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #16A		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861974		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	41.9
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.3
Specific Gravity	D1298	0.84 - 0.91	0.849
Colour	D1500	$\leq$ 3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	• Oil level is acceptable
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	TL/RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #18 - Admin/Entrance Fed		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Carte	Year Built	1983		
Type	ONAN	Serial #	L0721-1		
Neutral	Solid	Liquid Type/Vol	Oil	35	Gal
Rating	75	kVA	Total Weight	889	lbs.
Impedance	2.4	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	38.2
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.034
Interfacial Tension	D971	32 Dynes/ Cm Min.	18.2
Specific Gravity	D1298	0.84 - 0.91	0.857
Colour	D1500	$\leq 3.5$ Max.	1.0
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	IFT is marginal
Results Satisfactory:	Fair

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	TL/RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #20 - Eurasia Fed		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861944		
Neutral	Solid	Liquid Type/Vol	Oil	38	Gal
Rating	100	kVA	Total Weight	1300	lbs.
Impedance	1.8	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	43.3
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	36.1
Specific Gravity	D1298	0.84 - 0.91	0.847
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	

T.S.



# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #21		

### Submersible Distribution Transformer

#### Transformer Nameplate Data

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861981		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

### Oil Analysis

#### Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	30.7
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	33.3
Specific Gravity	D1298	0.84 - 0.91	0.849
Colour	D1500	$\leq 3.5$ Max.	0.5
Visual Condition	D1524	Clear	Clear

### Observations & Comments

Comments:	<ul style="list-style-type: none"> <li>Had to pump water out of vault</li> <li>Dielectric of oil is borderline</li> </ul>
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #22		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	861973		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	463	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	42.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.041
Interfacial Tension	D971	32 Dynes/ Cm Min.	33.8
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	• Over one foot of water pumped out of vault.
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	JC
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #23		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built			
Type	ONAN	Serial #	871931		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	36.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.6
Specific Gravity	D1298	0.84 - 0.91	0.849
Colour	D1500	$\leq 3.5$ Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:

Results Satisfactory: OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	TL/ RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #24 - Eurasia Fed		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1974		
Type	ONAN	Serial #	861964		
Neutral	Solid	Liquid Type/Vol	Oil	27	Gal
Rating	50	kVA	Total Weight	770	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	49.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.2
Specific Gravity	D1298	0.84 - 0.91	0.850
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>Slight mark/ burn on H1B elbow.</li> <li>Some secondary cables were found cut off. These ends were taped off by our personnel.</li> </ul>
Results Satisfactory:	OK (as left)

T.S.

T.S. P\_Trans\_Elect

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	KH/RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #26		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1974		
Type	ONAN	Serial #	861962		
Neutral	Solid	Liquid Type/Vol	Oil	27	Gal
Rating	50	kVA	Total Weight	770	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	40.4
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.1
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	- Corrosion present on untaped Neutral bus/ bushing. - Sand present in vault via primary cable duct.
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	KH/ RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment LD.	Vault #27		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	871926		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	35.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.5
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>• Elbows taped by our personnel.</li> <li>• Vault lid has no securing nuts holding grate.</li> </ul>
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 15, 1999
File Number	6621	Tested By	AS/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #28		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	871934		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	40.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	30.7
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	≤3.5 Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION****Special Projects Group****Client Information**

<b>Customer</b>	Toronto Zoo	<b>Date</b>	June 16, 1999
<b>File Number</b>	6621	<b>Tested By</b>	JC
<b>Location</b>	361A Old Finch Ave., Scarborough, Ontario		
<b>Equipment I.D.</b>	Vault # 29		

**Submersible Distribution Transformer****Transformer Nameplate Data**

<b>Manufacturer</b>	Westinghouse	<b>Year Built</b>	
<b>Type</b>	ONAN	<b>Serial #</b>	861972
<b>Neutral</b>	Solid	<b>Liquid Type/Vol</b>	Oil 16 Gal
<b>Rating</b>	25 kVA	<b>Total Weight</b>	465 lbs.
<b>Impedance</b>	1.9 %	<b>Primary Voltage</b>	16 kV
<b>Phase(s)</b>	1 $\phi$	<b>Secondary Voltage</b>	120/ 240 Volt
<b>Frequency</b>	60 Hz	<b>BIL</b>	125 kV
<b>Insulation Resistance (M<math>\Omega</math>)</b>			

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
<b>Dielectric Breakdown</b>	<b>D877</b>	<b>30 kV Min.</b>	39.3
<b>Neutralization Number</b>	<b>D974</b>	<b>0.05 Max. Mg Koh/G</b>	0.021
<b>Interfacial Tension</b>	<b>D971</b>	<b>32 Dynes/ Cm Min.</b>	30.9
<b>Specific Gravity</b>	<b>D1298</b>	<b>0.84 - 0.91</b>	0.848
<b>Colour</b>	<b>D1500</b>	<b>≤3.5 Max.</b>	0.5
<b>Visual Condition</b>	<b>D1524</b>	<b>Clear</b>	Clear

**Observations & Comments**

<b>Comments:</b>	
<b>Results Satisfactory:</b>	OK

T.S.



**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 18, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #30		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861976 White Ø: 871932 Blue Ø: 871933		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	43.0	34.1	39.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.007	0.014	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	33.1	29.6	31.8
Specific Gravity	D1298	0.84 - 0.91	0.849	0.849	0.848
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 16, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #31		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861940 White Ø: 861941 Blue Ø: 861943		
Neutral	Solid	Liquid Type/Vol	Oil	38	Gal
Rating	100	kVA	Total Weight	1300	lbs.
Impedance	1.8	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	40.2	37.0	38.1
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.021	0.007	0.007
Interfacial Tension	D971	32 Dynes/ Cm Min.	31.6	31.1	32.3
Specific Gravity	D1298	0.84 - 0.91	0.850	0.848	0.848
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	
Results Satisfactory:	OK

T.S.

T.S. P\_Trans\_Elect

# TECHNICAL FIELD SERVICE DIVISION

## Special Projects Group

### Client Information

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	JRK/RPM/TA
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #32		

### Submersible Distribution Transformer

#### Transformer Nameplate Data

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861949 White Ø: 961955 Blue Ø: 861952		
Neutral	Solid	Liquid Type/Vol	Oil	34	Gal
Rating	75	kVA	Total Weight	1080	lbs.
Impedance	2	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

### Oil Analysis

#### Laboratory Tests

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	38.5	40.7	42.8
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.028	0.028
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.8	31.4	33.5
Specific Gravity	D1298	0.84 - 0.91	0.848	0.847	0.847
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

### Observations & Comments

Comments:	<ul style="list-style-type: none"> <li>Red &amp; Blue phases' oil level marginal.</li> <li>Red φ manhole gasket should be replaced.</li> </ul>
Results Satisfactory:	OK/ Fair

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 17, 1999
File Number	6621	Tested By	KH
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #33		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #	871937		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	463	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	$\phi$	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (M $\Omega$ )					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results
			1999
Dielectric Breakdown	D877	30 kV Min.	37.7
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	36.9
Specific Gravity	D1298	0.84 - 0.91	0.848
Colour	D1500	$\leq 3.5$ Max.	0.5
Visual Condition	D1524	Clear	Clear

**Observations & Comments**

Comments: Vault fills over top with water

Results Satisfactory: OK

T.S.

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #34		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 861971 White Ø: 871927 Blue Ø: 871936		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	37.7	48.9	42.2
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.028	0.014	0.014
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.2	32.3	33.0
Specific Gravity	D1298	0.84 - 0.91	0.849	0.848	0.848
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments****Comments:**

- Blue & White phases' oil levels are marginal. Blue is lower.
- Signs of "corona" on White φ elbow. Water apparently dropping from above.
- Red φ vault ground broken off grate. This has been repaired by our personnel.

Results Satisfactory: FAIR

T.S.

T.S. P\_Trans\_Elect

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Toronto Zoo	Date	June 14, 1999
File Number	6621	Tested By	RPM/JRK
Location	361A Old Finch Ave., Scarborough, Ontario		
Equipment I.D.	Vault #35		

**Submersible Distribution Transformer****Transformer Nameplate Data**

Manufacturer	Westinghouse	Year Built	1973		
Type	ONAN	Serial #'s	Red Ø: 971929 White Ø: 871928 Blue Ø: 871925		
Neutral	Solid	Liquid Type/Vol	Oil	16	Gal
Rating	25	kVA	Total Weight	465	lbs.
Impedance	1.9	%	Primary Voltage	16	kVolt
Phase(s)	1	φ	Secondary Voltage	120/ 240	Volt
Frequency	60	Hz	BIL	125	kVolt
Insulation Resistance (MΩ)					

**Oil Analysis****Laboratory Tests**

Type of Test	ASTM No.	Acceptable Limits	Test Results		
			Red	White	Blue
Dielectric Breakdown	D877	30 kV Min.	41.8	42.8	38.0
Neutralization Number	D974	0.05 Max. Mg Koh/G	0.021	0.021	0.021
Interfacial Tension	D971	32 Dynes/ Cm Min.	32.4	32.7	31.7
Specific Gravity	D1298	0.84 - 0.91	0.848	0.848	0.848
Colour	D1500	≤3.5 Max.	0.5	0.5	0.5
Visual Condition	D1524	Clear	Clear	Clear	Clear

**Observations & Comments**

Comments:	<ul style="list-style-type: none"> <li>Red Ø – oil level is low</li> <li>Blue Ø – oil is marginal</li> </ul>
Results Satisfactory:	Fair

T.S.

**APPENDIX 20**

**BLACK & McDONALD –  
SUBMERSIBLE TRANSFORMER  
FAILURE/REPLACEMENT REPORT  
DATED AUGUST 1999,  
REFERENCE NO. 6637**





***Technical Field Service Division***

31 Pullman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

June 8, 1999

Metro Toronto Zoo  
361A Old Finch Ave.  
Scarborough, Ontario  
M1B 5K7

**Attention:** Mr. Dean Evans  
**Maintenance/ Facilities Supervisor**  
**Subject:** Submersible Transformer Failure / Replacement Report  
**Our Reference:** 6638

---

Dear Sir:

Further to the power interruption that occurred on May 18<sup>th</sup>, please find the results of our investigation enclosed herein.

**Initial Observations & Action:**

- A single phase feed 27.6kV S&C fuse was found to have operated in the Eurasia Pavilion substation. The affected feed supplied three (3) submersible transformer vaults.
- The blown link was replaced and tested.
- The associated lightning arrestor was also tested at 5kVDC and found to be acceptable for continued use.
- The feed was re-energised and the new fuse did not operate.
- The 3 individual submersible vaults were subsequently inspected.
- The transformer adjacent to the "Bird Barn" was found to not be supplying power.
- After confirming that voltage was indeed present at the cable termination point to the transformer, the feed was isolated and the transformer tested.

**Transformer Test Results:**

- Insulation resistance ("Megger") testing of the transformer 240V secondary winding resulted in a less than acceptable reading  $\cong 3.5M\Omega$ . Industry standards require a minimum value of  $100M\Omega$  for this type of unit.
- Dissipation factor readings measured beyond the readable scale of the test set.
- High capacitance readings on the secondary winding confirmed this as the point of failure.
- Sampling of the transformer oil immediately gave evidence of internal failure by the oil's black/ yellow colour (due to carbonisation).
- The dielectric breakdown of the oil was laboratory tested at 18.6kV – a clear failure by any accepted standard.

**Technical Field Service Division**


31 Pallman Court, Scarborough, Ontario M1X 1E4. Phone: (416)-298-9977 Fax: (416)-298-2907

**Remedial Action Taken:**

- As a result of the clear failure of the existing submersible transformer, it was removed from service.
- A new, compatible unit was sourced, supplied, tested, and installed.
- The failed transformer was removed from site and is being evaluated for repair or replacement.
- The old unit has been confirmed as being PCB-free.

I trust that this report will meet your requirements. We thank you for this service opportunity and invite any questions you may have. If there are any further concerns, please do not hesitate to contact the undersigned or Fred Tanguay (Tech. Service Manager) at any time.

Regards,  
**BLACK & McDONALD LIMITED**



R.P. (Rodger) Morgan  
Utility Technical Field Services

**TECHNICAL FIELD SERVICE DIVISION**

Special Projects Group

**Client Information**

Customer	Metro Toronto Zoo	Date	May 18, 1999
File Number	6638	Tested By	R. Morgan
Location	Scarborough, Ontario		
Equipment I.D.	Submersible Transformer (Old Unit)		
Substation	Bird Barn Submersible Vault		

**Power Transformer -Electrical****Nameplate Data**

Manufacturer	Westinghouse	Vector Group	240/ 120 Centre Tapped		
Type	ONAN	Serial #.	861942		
Neutral	Solid Ground	Liquid Type/Vol	Oil	38	Gal
Rating	100	kVA	Total Weight	1,300	lbs.
Impedance	1.8	%	Primary Voltage	16	kVolt
Phase	1	φ	Secondary Voltage	240/ 120	Volt
Frequency	60	Hz	BIL	125	kVolt

**Insulation Tests**

Insulation Resistance @ 5k / 500 VDC	Prim. With Sec. Grounded	Sec. With Prim. Grounded	Prim. & Sec. To Ground		
MΩ	87,000	3.46	65,500		
Corrected to 20 °C.					
	CH-L + G	CH-G	CH-L	CL-G	CL-H + G
Cap (pF)	122	117	4	3000	3000
Corr. 20 °C					
Dis. Fact.(%)	11.22	13.00	-	>39.99	>39.99
Corr. 20 °C.					

**Turns Ratio Tests**

Tap	Primary Volts	Calculated Ratio	X0-X2 H1-H2	X0-X3 H2-H3	X0-X1 H3-H1
1					
2					
3					
4					
5					
Tap Position Found & Left					
Results Satisfactory			NO		

T.S.

01

01

01