

1 PART DWG. E-11
Scale: NO SCALE


DESCRIPTION OF WORK

1 THE EXISTING AMERICAS/AFRICAS LOOP FEED IN THE MANHOLE IS TO BE SPLICED AND EXTENDED INTO THE NEW SWITCH FEED FROM AMERICAS TO CELL #1.
THE FEED TO AFRICA – CELL #2
THE NEW FEED TO AFRICA PUMPING STATION – CELL #3.

2 IF THE NEW SWITCH IS NOT INSTALLED, INSTALL NEW CABLES IN EXISTING DUCTS FROM AMERICAS CELL #3 TO NEW TRANSFORMER AT AFRICA PUMPING STATION.

3 SUPPLY AND INSTALLATION OF 4-WAY VISTA VI SWITCHGEAR TO BE QUOTED AS PART OF THE TENDER.

4 ITEMIZED PRICING REQUIRED FOR SWITCH AS PER SPECIFICATION.

Client:	Project No.:	Date:	 MORRISON HERSHFIELD	Suite 600 – 235 Yorkland Blvd. Toronto, ON M2J-1T1 Tel: (416) 499-3110 Fax: (416) 499-9658
	1105504	AUG 31, 2010		Checked.: –
	Drawn: AJG	Design: RAW	TORONTO ZOO	
	ADDENDUM #1			SK-3 – ADD #1