




① PART DWG. SP-01 - DETAIL 6
Scale: NO SCALE

LEGEND


 4 x 100mm PRIMARY DUCT BANK FOR POWER AND 2 x 100mm DUCTS FOR COMMUNICATIONS. POWER DUCTS SHALL BE c/w 28kV 1 x 4/0 COPPER XLPE C.N. IN THREE DUCTS ONLY. OTHER POWER DUCT IS SPARE c/w PULL STRING. COMMUNICATION DUCTS SHALL CONTAIN PULL STRINGS.

 2 x 4" SECONDARY DUCT BANK c/w EMPTY CONDUITS c/w PULL STRING.

 DUCT BANKS TO BE CONCRETE ENCASED AT ALL ROAD CROSSINGS.

NOTE:

ALL DUCT BANK ROUTES TO BE CHECKED WITH ZOO STAFF PRIOR TO ANY WORK BEING STARTED. ALL DUCT BANKS CAN BE OPEN CUT OR HORIZONTALLY BORED.

Client:	Project No.:	Date:	 MORRISON HERSHFIELD	Suite 600 - 235 Yorkland Blvd. Toronto, ON M2J-1T1 Tel: (416) 499-3110 Fax: (416) 499-9658
	1105504	AUG 31,2010		Checked.: -
	Drawn: AJG	Design: RAW	TORONTO ZOO	